

PARKS CANADA
NATIONAL PARK PLAYGROUNDS
CAVENDISH, PEI
STANHOPE, PEI
DRAWING SPECIFICATIONS



Prime Consultants

Coles Associates Ltd.
Charlottetown, PEI
#141049

July 2014

INDEX TO SPECIFICATIONS AND DRAWINGS

1 Section 00001 Summary of Work 2

Index to Drawings:

- C1 Cavendish Site Plan**
- C2 Cavendish Southwest Footing Locations**
- C3 Cavendish Northeast Footing Locations**
- C4 Stanhope Site Plan**
- C5 Stanhope North Footing Locations**
- C6 Stanhope South Footing Locations**
- C7 Details**

1 SECTION 00001 SUMMARY OF WORK

1.1 SCOPE OF WORK

Contractors are to allow for the provision of all plant, men and material to accommodate the following work.

- .1 Contractor is to allow for the clearing and grubbing of all tree stumps, roots, grass, weed and other surface litter, wherever they occur within the parameters indicated in drawing C4 for Stanhope location.
- .2 Contractor to allow for 6" of top soil removal and 4" of backfill, using select borrow, as required to construct the landing mats as indicated in drawings C1 and C4 for Cavendish and Stanhope locations, respectively.
- .3 Contractor is to allow for 18" diameter bore holes to the desired depth based on the footing design depicted in the drawings.
- .4 Play equipment installation is to be in accordance with the manufacturer's installation instructions and to match the footing locations indicated in the drawings.
- .5 Contractor is to install all play equipment prior to the landing mat border to allow for onsite equipment access (ie. forklift, etc.)
- .6 Contractor to construct landing mat border as designed in drawing C7 with the geotextile fabric extending over the entire landing mat surface and anchored as required.
- .7 Contractor to fill landing mat with 3/8" minus pea gravel following all play elements being erected and geotextile fabric anchored. Minimum 12" depth extending to 24" around perimeter of all play equipment; minimum 8" and maximum 10" depth around inner perimeter of landing mat.
- .8 Contractor is to allow for manufacturer representative to be on-site full time during footing layout and again for final commissioning.

1.2 PERFORMANCE STANDARDS

- .1 Codes
Standards employed for the work shall be consistent with the:
 - .1 National Building Code
- .2 Standard of Acceptance for Material
 - .1 Playground designed using Little Tikes materials only. Alternative manufacturers will be considered if proposed equipment designs satisfy specified equipment layouts and footing designs.
 - .2 NE 1416; Little Tikes Nu-Edge 1416 Play Structure, or equivalent
 - .1 Remove Transfer Station; insert "C" Challenge Ladder
 - .2 Remove Rocky Rambler; insert Tree Climb
 - .3 Remove two (2) Roofs; insert two (2) Leaf Roofs
 - .4 Remove Medium Fun Rock; insert Nu-edge Rock Challenge Wall
 - .3 NE 1303; Little Tikes Nu-Edge 1303 Play Structure, or equivalent
 - .1 Remove Transfer Deck; insert Arch Log Climber
 - .2 Remove Roof; insert Leaf Roof
 - .4 Medium Rock; Little Tikes Medium Fun Rock Freestanding, or equivalent
 - .5 Crawl Log; Little Tikes NU-edge Crawl Log, or equivalent
 - .6 Pine Stump; Little Tikes NU-edge Short Pine Stump, or equivalent
 - .7 Birch Stump; Little Tikes NU-edge Medium Birch Stump, or equivalent
 - .8 Stacked Timber Climb; Little Tikes Stacked Timber Climb, or equivalent
 - .9 Swing Set; Heavy Duty 8' Swing Set, 2 bay, c/w 2 tot seats, 2 belt seats, Standard/Heavy Duty 8' Add-On Standard Beam
 - .10 Brick; standard brick 2 1/4" x 3 5/8" x 8"
- .3 Acceptable Manufacturers: Little Tikes, Blue Imp, ABC Recreation, & Kangaroo.