



## Addendum 5

**Project Title:** Roof Replacement  
Building 20  
Central Experimental Farm (CEF), Ottawa (Ontario)

**Solicitation No:** 14-1109

August 29, 2014

The following changes in the tender documents are effective immediately. This addendum will form part of the contract documents

---

### Q & A

**Q11. What is the approximate thickness of the existing roof?**

A11. The approximate thickness of the existing roof assembly is 13 to 14 inches.

**Q12. Can alternative materials and methods be used for the insulation (ductwork)?**

A12. Any material used for this project has to be in accordance with the specifications and must be approved before the beginning of the work. Methods, other than the one specified in the bid documents/specifications, will not be used for this work item.

### DRAWINGS AND SPECIFICATIONS

**1. At Drawing 1 “Plan”, Notes Item 4:**

**Delete:** During the new roofing installation, the ductwork might be required to be lifted depending on the existing site conditions (see alternate price).

**Replace with:** During the new roofing installation, the ductwork might be required to be removed and reinstalled depending on the existing site conditions.

**ALL OTHER TERMS AND CONDITIONS REMAIN THE SAME**