

**RETURN BIDS TO:  
RETOURNER LES SOUMISSIONS À:**

Regional Manager/Real Property  
Contracting/PWGSC  
Ontario Region, Tendering Office  
12th Floor, 4900 Yonge Street  
Toronto, Ontario  
M2N 6A6  
Ontario

**SOLICITATION AMENDMENT  
MODIFICATION DE L'INVITATION**

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

**Comments - Commentaires**

**Vendor/Firm Name and Address**  
Raison sociale et adresse du  
fournisseur/de l'entrepreneur

**Issuing Office - Bureau de distribution**  
Regional Manager/Real Property Contracting/PWGSC  
Ontario Region, Tendering Office  
12th Floor, 4900 Yonge Street  
Toronto, Ontario  
M2N 6A6  
Ontario

<b>Title - Sujet</b> Burlington, ON Metal Cladding Repla	
<b>Solicitation No. - N° de l'invitation</b> KW405-135073/A	<b>Amendment No. - N° modif.</b> 002
<b>Client Reference No. - N° de référence du client</b> KW405-135073	<b>Date</b> 2014-09-03
<b>GETS Reference No. - N° de référence de SEAG</b>	
<b>File No. - N° de dossier</b> PWL-4-37045 (003)	<b>CCC No./N° CCC - FMS No./N° VME</b>
<b>Solicitation Closes - L'invitation prend fin</b> <b>at - à 02:00 PM</b> <b>on - le 2014-09-11</b>	
<b>Time Zone</b> Fuseau horaire Eastern Daylight Saving Time EDT	
<b>F.O.B. - F.A.B.</b> <b>Plant-Usine:</b> <input type="checkbox"/> <b>Destination:</b> <input checked="" type="checkbox"/> <b>Other-Autre:</b> <input type="checkbox"/>	
<b>Address Enquiries to: - Adresser toutes questions à:</b> Dhanna, Sheila	<b>Buyer Id - Id de l'acheteur</b> pwl003
<b>Telephone No. - N° de téléphone</b> (416) 512-5855 ( )	<b>FAX No. - N° de FAX</b> (416) 512-5862
<b>Destination - of Goods, Services, and Construction:</b> <b>Destination - des biens, services et construction:</b> ASIF MOHAMMED Administration NWRI 867 Lakeshore Road PO Box 5050 Burlington, ON L7R 4A6	

**Instructions: See Herein**

**Instructions: Voir aux présentes**

<b>Delivery Required - Livraison exigée</b>	<b>Delivery Offered - Livraison proposée</b>
<b>Vendor/Firm Name and Address</b> Raison sociale et adresse du fournisseur/de l'entrepreneur	
<b>Telephone No. - N° de téléphone</b> <b>Facsimile No. - N° de télécopieur</b>	
<b>Name and title of person authorized to sign on behalf of Vendor/Firm</b> (type or print) <b>Nom et titre de la personne autorisée à signer au nom du fournisseur/</b> <b>de l'entrepreneur (taper ou écrire en caractères d'imprimerie)</b>	
<b>Signature</b>	<b>Date</b>

PROJECT TITLE

BURLINGTON, ONTARIO  
CANADA CENTRE FOR INLAND WATERS  
687 LAKESHORE ROAD  
METAL CLADDING REPLACEMENT

AMENDMENT NO. 1, dated [SEPTEMBER 2, 2014]

This Amendment shall form part of documents referred to in the "Bid and Acceptance Form[ - Combined Price]".

The Plans and Specifications are amended as follows:

QUESTIONS and ANSWERS

**QUESTION 1:**

It appears the scale may be incorrect on the north and south elevations. Could you please clarify the correct dimensions?

**ANSWER 1:**

Revised drawings with corrected dimensions are attached. The pricing table has also been revised and is attached.

**QUESTION 2:**

A: Section 01 31 16 item 1.5.4.11 of the specifications (page 2) calls for Commissioning in accordance with Section 01 91 00. The mechanical systems incorporated into the scope of work include three (3) mechanical louvers and their associated controls. Can PWGSC confirm that they wish to proceed with a full commissioning scope of work as outlined in Section 01 91 00?

B: If the response to A above is negative, would PWGSC accept a reduced scope of work?  
a. What would the reduced scope of work be?  
b. Would PWGSC consider utilizing a Controls Design Review, Installed Verification Check and Functional Performance Test approach for the three (3) mechanical louvers as sufficient to demonstrate functionality and performance?

**ANSWER 2:**

Commissioning will not be required as the louvers being replaced are stand-alone louvers and the mechanical equipment within the penthouses will not be affected. Bidders should confirm the number of louvers based on their review of the site and the project drawings.

**QUESTION 3:**

Is there in fact a new door to be replaced per note on drawing A-2 between grid lines Ex and Fx. We took photos, and if not mistaken did not see a door here. Please clarify.

**ANSWER 3:**

There is no door on the east elevation between gridlines Ex and Fx, the drawings have been corrected. There is one single man door on the west elevation between gridlines Ex and Dx, a double door on the west elevation between grid lines Iy and Hy, three hatch roof doors on the south elevation and a fourth on the east elevation. All of these doors are to be replaced, including frames. New doors are to be clad to patch the new metal cladding.

**QUESTION 4:**

Drawing A-2 has a legend with a symbol for expansion joint. Is there any new expansion joint required, or is it simply referring to the existing. The notes also appear in areas where we do not have any work and here in lies the confusion.

**ANSWER 4:**

The new metal cladding is to incorporate expansion joints at the locations shown on the drawings. Specifically, along grid line Dy on the east and west elevations.

**QUESTION 5:**

Can dimensions of the existing louvers be provided?

**ANSWER 5:**

Please refer to revised drawings, attached.

**QUESTION 6:**

Does the upper roof sheet metal cap flashing need to be completed by Flynn as well?

**ANSWER 6:**

No, the sheet metal cap flashing at the upper roof is not currently under warranty and can be replaced by the successful bidder's own forces or a subcontractor of their choice.

**QUESTION 7:**

SK-1 Main Building detail notes ceramic fibre blanket to be fixed to z girts on Drawing A-2. Is this wall to be fire rated and if so what fire rating shall apply?

**ANSWER 7:**

This wall must have a 1 hour fire rating.

**QUESTION 8:**

Please confirm the bird deterrent systems and scientific equipment/antennas will be decommissioned, removed, replaced and re-commissioned by the Owner.

**ANSWER 8:**

The devices will be decommissioned/cables disconnected by the owner but they must be removed from the wall and remounted by the successful bidder. All devices are to be remounted on brackets secured to the backup structure/liner panel that penetrates through the new cladding. Devices are not to be fastened directly to the new cladding.

**QUESTION 9:**

Please confirm if the three openings on the South Elevation are to have new louvers installed or do we install sheet metal access doors to match existing?

**ANSWER 9:**

Access doors are to be provided.

**QUESTION 10:**

Please confirm if the two existing doors on the West Elevation are to completely removed and replaced or if they are to be re-clad with siding ?

**ANSWER 10:**

All existing doors are to be completely replaced, including frames, and the new doors clad with siding.

**QUESTION 11:**

Please confirm the scope of work which is covered under the cash allowance of \$4,000.

**ANSWER 11:**

The cash allowance will be used to pay for any miscellaneous work which may be required but is not included in the scope of work. The cash allowance will only be paid to the contractor if extra work is approved by the owner and consultant.

**QUESTION 12:**

Please confirm the quantities provided on the bid form are to be used for estimating purposes.

**ANSWER 12:**

Yes, the quantities on the bid form are provided for estimating purposes.

**QUESTION 13:**

There is not a Louvre specification that we can base the design and or type of louvres required on this project, will a specification be provided stating the type, if prefinished steel or aluminum louvres are required, all these things will affect the quote?

**ANSWER 13:**

Louvres shall be fixed louvres to match the configuration of the existing. They are to be prefinished steel that complies with the galvanizing/Galvalume requirements for the new cladding material as outlined in Section 07 46 19. Louvres are also to be installed with fasteners as indicated for the new cladding material, as outlined in Section 07 46 19.

END OF SECTION