

RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:
Bid Receiving Public Works and Government
Services Canada/Réception des soumissions Travaux
publics et Services gouvernementaux Canada
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British Columbia
V6Z 0B9
Bid Fax: (604) 775-9381

SOLICITATION AMENDMENT MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Public Works and Government Services Canada -
Pacific Region
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British C
V6Z 0B9

Title - Sujet A & D Area Redevelopment	
Solicitation No. - N° de l'invitation EZ899-150705/A	Amendment No. - N° modif. 003
Client Reference No. - N° de référence du client	Date 2014-09-11
GETS Reference No. - N° de référence de SEAG PW-\$PWY-020-7302	
File No. - N° de dossier PWY-4-37095 (020)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2014-09-16	Time Zone Fuseau horaire Pacific Daylight Saving Time PDT
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Ly, Ronny(PWY)	Buyer Id - Id de l'acheteur pwy020
Telephone No. - N° de téléphone (604) 666-0043 ()	FAX No. - N° de FAX (604) 775-6633
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction: CSC - A & D Area, Kent Institution - Abbotsford, BC	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Solicitation No. - N° de l'invitation

EZ899-150705/A

Client Ref. No. - N° de réf. du client

Amd. No. - N° de la modif.

003

File No. - N° du dossier

PWY-4-37095

Buyer ID - Id de l'acheteur

pw020

CCC No./N° CCC - FMS No/ N° VME

Les documents français seront disponibles sur demande.

This Amendment 003 is raised to incorporate Addendum No. 2.

All other terms and conditions remain unchanged.

The following changes in the tender documents are effective immediately. This addendum will form part of the contract documents.

SPECIFICATIONS

.1 01 01 50 GENERAL INSTRUCTIONS

Clause 1.2 revised in Addendum No1 as Item (2) paragraph 2.2:

- (1) **Add:** new sentence:
Restricted Visits must not be shut down to CSC use, longer than six (6) weeks duration.

Paragraph 3.3.2:

- (2) **Add:** new sentence:
Schedule shutdown of Restricted Visits, for Hazmat removal and renovation, for a maximum of six (6) weeks duration. Restricted Visits room must be secure and functionally usable. Minor deficiencies can be tolerated as approved by the Departmental Representative.

Paragraphs 11.1.1 and 11.1.4:

- (3) **Clarification:**
- .1 "Secure" construction for temporary wall, at interior main corridor adjacent to Restricted Visits and temporary enclosure at new exterior door at main exterior entry, means a wood framed wall/enclosure to underside of ceiling and integrated roof enclosure where exposed to exterior using wood framing at maximum 400 oc, expanded metal mesh screwed to wood framing, on attack side, and sheathed with 12 mm exterior grade plywood screwed to framing. Insulate exterior enclosure and cover with 6 mil polyethylene.
 - .2 Anchor framing securely to adjacent construction, ie, walls, floor and ceiling where applicable. Repair damage to existing surfaces following removal of temporary wall and enclosure, to match existing, as approved by the Departmental Representative.
 - .3 Expanded metal mesh is specified in Section 05 50 00 Metal Fabrications paragraph 2.1.4.
 - .4 Construct the interior secure partition dust tight and the exterior secure enclosure water/wind tight and both sealed with acrylic caulking.
 - .5 Construct wall and enclosure to provide ample working space within each enclosed area.
 - .6 Submit sketch plan of each temporary enclosure to Departmental Representative for review, showing construction of temporary wall and enclosure and indicate any deviations.
 - .7 Install a secure door in temporary wall at corridor location. Secure door can be a salvaged door and frame assembly from one of the existing doors scheduled for removal and disposal. Door and frame must be constructed of 1.6 mm gauge and have a mortised lock with deadbolt.
 - .8 Do not dismantle temporary enclosures until new construction is in place and secure.

Paragraphs 18.1.1.4:

- (4) **Delete:** words "electronic interactive" and **Replace** with: digital pdf.
- (5) **Clarification:** refer to section 23 05 00 - Common Work Results-Mechanical, paragraph 1.10.2 (page 7 of 14) for digital manual requirements.
-

.2 10 56 27 MOBILE SHELVING STORAGE-MANUAL

Para 1.2.3:

(6) Clarification:

- .1 Contractor is to determine whether reusing existing mobile shelving mounted on new mobile base is practical from a manufacturing and installation point of view or whether providing all new mobile shelving is more cost effective.
- .2 See attached photo of existing typical shelving to mobile base connection on page 3 of this addendum no 2.

Para 2.1.1:

- (7) Clarification:** for new mobile shelving components, colour of baked enamel finish will be selected by Departmental Representative from manufacturer's standard available finishes. Submit samples. Matching colours with existing shelving is not an issue.

.3 27 05 13 TELECOMMUNICATIONS CABLING

- (8) Delete:** all references made to "NORDX" within this Section. All new components shall be "AMP" to match existing.

DRAWINGS

.1 DRAWING A100 – DEMOLITION PLAN

Flooring Removal and Slab Saw Cut Demolition Plan

- (9) Delete:** reference to (NIC) in regards to Deleting Existing Flooring. Removal of flooring is included in the contract. Refer to Addendum No. 1.

Reflected Ceiling Demolition Plan:

- (10) Delete:** reference to (NIC) in regards to Remove Existing Gypsum Bd. Ceiling. Removal of gypsum board ceiling is included in the contract. Refer to Addendum No. 1.

.2 Drawing E-1 - NEW AND EXISTING LIGHTING PLAN

Symbol Legend:

- (11) Change:** Description of Existing Surface Mounted Light Fixture with the following new description:

"REMOVE AND DISPOSE OF EXISTING SURFACE MOUNTED LIGHT FIXTURE"

PHOTO



Existing mobile shelving

END OF ADDENDUM No 2
