

PART 1 - GENERAL

- 1.1 DESCRIPTION .1 This section specifies requirements for demolishing and removing wholly or in part various items designated to be removed or partially removed.
- .2 Demolition and removal will consist of, but not necessarily be limited to, the following:
- .1 Demolition, removal, and disposal of twisted gabion baskets.
- .2 Demolition, removal, and disposal of damaged and deteriorated untreated timber cribwork shore protection and associated hardware.
- .3 Remove and salvage any existing armourstone to gain access to the start of new work.
- .4 Rock fill in both the gabion baskets and cribwork to be demolished will be salvaged and reused if it meets the specification. Dispose of any rock fill that is not suitable for reuse.
- 1.2 GENERAL REQUIREMENTS .1 A Notice to Shipping is to be issued prior to commencement and upon completion of work.
- .2 Upon completion of the project, a written Notice to Mariners must be issued.
- 1.3 PROTECTION .1 Protect existing objects designated to remain. In event of damage, immediately replace or make repairs to approval of and at no additional cost to Canada.
- .2 Place a floating boom around entire demolition site to prevent loss of any materials.
- .3 Remove all floating debris from water on a routine and timely basis.
-

1.4 MEASUREMENT FOR PAYMENT .1 This portion of work will not be measured for payment but to be included in the Lump Sum Amount of the Contract.

PART 2 - PRODUCTS NOT APPLICABLE

PART 3 - EXECUTION

3.1 EXECUTION .1 Inspect site and verify with Departmental Representative objects designated for removal.
.2 Locate and protect utility lines. Preserve in operating condition active utilities traversing site.

3.2 REMOVAL .1 Remove in their entirety all materials and objects specified for removal.
.2 Do not disturb adjacent work designated to remain in place.

3.3 SALVAGE/DISPOSAL OF MATERIAL .1 All demolished materials, except materials designated to be reused, will become property of contractor and will be removed from site and disposed of to satisfaction of Departmental Representative and in accordance with environmental guidelines. It is the sole responsibility of the contractor to dispose of all demolished materials at an approved disposal site. Ensure that disposal site is approved and willing to accommodate any materials disposed of from work site.
.2 Contractor shall obtain and pay for all necessary permits and disposal fees for use of an approved waste disposal site.

PWGSC
P/N R.072528.001
SHORELINE PROTECTION
ST. DAVID'S, NL

SITework, DEMOLITION
AND REMOVAL

Section 02 41 16
Page 3
JULY 2014

3.4 RESTORATION

- .1 Upon completion of work, remove debris, trim surfaces and leave work site in clean condition.
- .2 Reinstate areas and existing works outside areas of demolition to conditions that existed prior to commencement of work.