

#### GENERAL DEMOLITION NOTES:


- EXECUTE WORK BY METHODS TO AVOID DAMAGE TO OTHER EXISTING COMPONENTS AND FINISHES.
- COORDINATE DEMOLITION WORK WITH MECHANICAL AND ELECTRICAL WORK.
- CONTRACTOR TO REMOVE AND RETURN TO OWNER ALL EXISTING WALL MOUNTED ITEMS, FIXTURES AND EQUIPMENT AFFECTED BY DEMOLITION.
- FOR MECHANICAL REMOVALS, SEE MECHANICAL
- FOR ELECTRICAL REMOVALS, SEE ELECTRICAL

#### CEILING DEMOLITION NOTES:

- REMOVE EXISTING T-BAR GRID AND ACOUSTIC CEILING TILES. RETURN UNDAMAGED CEILING TILES TO DEPARTMENTAL REPRESENTATIVE FOR RE-USE.
- REMOVE EXISTING SECURITY MESH AND WOOD FRAMING ABOVE FINISHED CEILING.
- REMOVE EXISTING LIGHT FIXTURES AND RETURN TO DEPARTMENTAL REPRESENTATIVE.
- REMOVE AND REINSTALL CEILING TILES AS REQUIRED TO DO DEMOLITION WORK AND INSTALL NEW DOORS. REPLACE ANY DAMAGED TILE TO MATCH EXISTING.

#### LEGEND:

- EXISTING T-BAR CEILING TO REMAIN
- REMOVE EXISTING T-BAR CEILING
- EXISTING LIGHT FIXTURES TO REMAIN
- REMOVE EXISTING LIGHT FIXTURES, SEE ELECTRICAL FOR REMOVALS
- EXISTING PARTITION TO REMAIN
- REMOVE EXISTING PARTITION
- REMOVE EXISTING WINDOW & WINDOW FRAME
- REMOVE EXISTING SECURITY MESH & WOOD FRAMING
- DIFFUSER, SEE MECHANICAL FOR REMOVALS
- EXISTING FIRE ALARM BELL, SEE ELECTRICAL
- CEILING MOUNTED SPEAKER, SEE ELECTRICAL FOR REMOVALS
- DEMOLITION NOTE TAG
- DOOR TAG
- ROOMNAME TAG



0	ISSUED FOR TENDER	SEPT 3 2014
revisions		date
project		projet

**CRA COMPUTER BASED  
TRAINING ROOM  
DATA TAX CENTRE**  
280 EMPIRE AVENUE, ST. JOHN'S, NL

drawing dessin

### EXISTING REFLECTED CEILING & DEMOLITION PLAN

designed	conçu
date	
drawn	T. JOHNSON
date	2014.05.06
approved	approuvé
date	
Tender	V. WARFORD
PWGSC Project Manager	Administrateur de projets TPSCG
project number	no. du projet
	R.061300.004
drawing no.	no. du dessin
	A3



1  
A3

#### DEMOLITION REFLECTED CEILING PLAN

SCALE: 1:75

