

PART 1 - GENERAL

1.1 USE OF SITE  
AND FACILITIES

- .1 Execute work with least possible interference or disturbance to normal use of premises.
- .2 Maintain security measures established by existing facility.

1.2 DISPOSAL OF  
WASTES

- .1 Burying of rubbish and waste materials is prohibited unless approved by Departmental Representative.
- .2 Disposal of waste, volatile materials, mineral spirits, oil or paint thinner into waterways, storm or sanitary sewer is prohibited.
- .3 Regular construction waste shall be handled and disposed of IAW Municipal landfill procedures. Pay tipping fees.
- .4 Contractor to dispose of lead paint and lead paint containing materials having lead in leachate less than <5mg/L; mercury paint and mercury paint containing materials having mercury in leachate less than <0.1mg/L; arsenic paint and arsenic paint containing materials having arsenic in leachate less than >2.5mg/L at local municipal waste dumpsite (15 kilometers off the work site) in designated area. Dispose under supervision of town staff at contractors expense.

1.3 STORAGE,  
HANDLING AND  
PROTECTION

- .1 Store, materials to be reused, recycled and salvaged in locations as directed by Departmental Representative.
- .2 Unless specified otherwise, materials for removal become contractor's property.
- .3 Transport and deliver non-salvageable items other than steel to licensed disposal facility (Municipal Waste Dumpsite). Pay tipping fees.

1.4 SCHEDULING

- .1 Coordinate Work with other activities at site to ensure timely and orderly progress of Work.

PART 2 - PRODUCTS

2.1 NOT USED .1 Not Used.

PART 3 - EXECUTION

3.1 APPLICATION .1 Handle waste materials not reused, salvaged, or recycled in accordance with appropriate regulations and codes.

3.2 CLEANING .1 Remove tools and waste materials on completion of Work, and leave work area in clean and orderly condition.  
.2 Clean-up work area as work progresses.