

GENERAL CONSTRUCTION NOTES:


- EXECUTE WORK BY METHODS TO AVOID DAMAGE TO OTHER EXISTING COMPONENTS AND FINISHES.
- COORDINATE NEW CONSTRUCTION WITH MECHANICAL AND ELECTRICAL WORK.
- MAKE GOOD, REPAIR OR REPLACE ALL MATERIALS AND SURFACES DAMAGED BY REMOVALS. PROVIDE A PROPER SUBSTRATE FOR NEW FINISHES.
- REPAIR AND MAKE GOOD ALL WALL AND CEILING OPENINGS AFTER INSTALLATION OF MECHANICAL AND ELECTRICAL FIXTURES AND WIRING. SEE MECHANICAL AND ELECTRICAL.
- REPAIR AND MAKE GOOD ANY EXISTING WALL IMPERFECTIONS.
- REFINISH SURFACES TO MATCH ADJACENT FINISHES. FOR CONTINUOUS SURFACE REFINISH TO NEAREST INTERSECTION.
- NEW PARTITIONS ARE TO BE DIMENSIONED FROM C/L OF PARTITION. DIMENSIONS ARE GIVEN FROM CLOSEST FACE OF EXISTING WALL IN RENOVATION.
- ALL FIRE SEPARATIONS MUST BE MAINTAINED, ENSURE ALL NEW OPENINGS ARE FIRE STOPPED AS REQUIRED.
- CONTRACTOR TO RE-INSTALL ALL EXISTING WALL MOUNTED ITEMS AND EQUIPMENT REMOVED DURING DEMOLITION. NEW LOCATION TO BE CONFIRMED WITH DEPARTMENTAL REPRESENTATIVE.
- CONTRACTOR TO VERIFY T-BAR GRID UNIT OF MEASUREMENT, COORDINATE SIZING OF FIXTURES AND EQUIPMENT AS REQUIRED.

CEILING CONSTRUCTION NOTES:

- INSTALL NEW T-BAR GRID TO MATCH EXISTING.
- INSTALL NEW ACOUSTIC CEILING TILE TO MATCH EXISTING, RE-USE EXISTING IF POSSIBLE.
- RE-INSTALL CEILINGS IN ALL AREAS AFFECTED BY MECHANICAL WORK.
- CEILING MOUNTED PROJECTOR AND WALL MOUNTED SCREEN, EXACT LOCATION TO BE DETERMINED ON SITE. PROJECTOR SUPPLIED BY OWNER. MOUNTING HARDWARE FOR PROJECTOR SUPPLIED AND INSTALLED BY CONTRACTOR.

LEGEND:

- EXISTING T-BAR CEILING TO REMAIN
- NEW T-BAR CEILING
- NEW LIGHT FIXTURE, SEE ELECTRICAL
- EXISTING LIGHT FIXTURES TO REMAIN
- EXISTING PARTITION TO REMAIN
- NEW PARTITION / AREA OF INFILL
- DIFFUSER, SEE MECHANICAL
- RETURN GRILLE, SEE MECHANICAL
- CO₂ SENSOR, SEE MECHANICAL
- EXISTING FIRE ALARM BELL
- CEILING MOUNTED SPEAKER, SEE ELECTRICAL
- CEILING MOUNTED PROJECTOR, SEE ELECTRICAL
- CH= CEILING HEIGHT
- PARTITION TYPE TAG
- CONSTRUCTION NOTE TAG
- DOOR TAG
- ROOMNAME XXX ROOM TAG
- SECTION REFERENCE
- NEW BULKHEAD ABOVE SUSPENDED CEILING



0	ISSUED FOR TENDER	SEPT 3 2014
revisions		date
project		projet

**CRA COMPUTER BASED
TRAINING ROOM
DATA TAX CENTRE**
290 EMPIRE AVENUE, ST. JOHN'S, NL

drawing dessin

PROPOSED REFLECTED CEILING PLAN

designed	conçu
date	
drawn	T. JOHNSON
date	2014.05.06
approved	approuvé
date	
Tender	V. WARFORD
PWGC Project Manager	Administrateur de projets TPSGC
project number	no. du projet
	R.061300.004
drawing no.	no. du dessin
	A4