

Addenda #1 RFP 201500057

CLARIFICATION – THE PURPOSE OF THIS ADDENDA IS TO REMOVE THE STAND ALONE COMPONENTS OF THE HEATING AND VENTILATION SYSTEM, AND REPLACE IT WITH A WALL MOUNTED COMBINATION AIR CONDITIONING UNIT. THE UNIT SHOULD BE ABLE TO MAINTAIN A CONSTANT TEMPERATURE OF 20C DURING ALL SEASONS.

-INSERT – SUPPLIER TO PROVIDE AND INSTALL A WALL MOUNTED COMBINATION AIR CONDITIONING UNIT. THE WALL MOUNTED UNIT TO BE A:

**BARD AIR CONDITIONER UNIT #W24A2-A05SX4XXJ COMPLETE WITH AN ECONOMISER ECONWM-SERIES.**

-SUPPLIER MAY PROVIDE EQUIVALENT UNIT FROM A DIFFERENT MANUFACTURER. SUPPLIER TO PROVIDE TECHNICAL SHEETS PROVING EQUIVALENCE WITH TENDER PACKAGE.

-SUPPLIER TO PROVIDE SHOP DRAWINGS OF PROPOSED LOCATION AND HEIGHT OF UNIT ON THE SHELTER.

-UNIT TO BE CONTROLLED BY A WALL MOUNTED PROGRAMABLE THERMOSTATE.

MODIFICATION TO EXISTING TENDER DOCUMENTS

## **STRUCTURE**

ITEM 4

DELETE – The structure must be sealed to all water, insects, rodents and dust. Only the active ventilation system will allow air movement.

INSERT - The structure must be sealed to all water, insects, rodents and dust.

ITEM 6

DELETE - The motorized active ventilation system will be controlled a wall-mounted thermostat. Vents must be fitted with grills with openings small enough to keep typical insect from penetrating the structure. The grills must be made of sufficiently robust material to keep typical rodents from penetrating the structure.

## **ELECTRICAL**

ITEM 2

DELETE - Supplier must provide by electric baseboard unit (220V) controlled by a wall mounted thermostat.

ITEM 8

DELETE - Supplier must provide a wall mounted heat pumps and air conditioner.