

PART 1 - GENERAL

1.1 SECTION
INCLUDES

- .1 Barriers.

1.2 INSTALLATION
AND REMOVAL

- .1 Provide temporary controls in order to execute work expeditiously.
- .2 Remove from site all such work after use.

1.3 HOARDING

- .1 Erect temporary site enclosure if required by governing authorities, using new 1.2 m high snow fence wired to rolled steel "T" bar fence posts spaced at 2.4 m centres. Provide one lockable truck gate. Maintain fence in good repair.

1.4 GUARD RAILS
AND BARRICADES

- .1 Provide secure, rigid guard rails and barricades around open excavations and as required to protect against falls. Note steep cliffs around work area and construct barricades where work is expected in these areas.
- .2 Provide as required by governing authorities.