





- GENERAL DEMOLITION NOTES:**
- EXECUTE WORK BY METHODS TO AVOID DAMAGE TO OTHER EXISTING COMPONENTS AND FINISHES.
 - COORDINATE DEMOLITION WORK WITH MECHANICAL AND ELECTRICAL. REMOVE FINISHES, SUBSTRATES AND OTHER CONSTRUCTION AS NEEDED TO PERFORM MECHANICAL AND ELECTRICAL WORK. INCLUDES ELECTRICAL WORK ON THE FOURTH FLOOR REFER TO DRAWING E6.
 - CONTRACTOR TO REMOVE AND RETURN TO OWNER ALL EXISTING WALL MOUNTED ITEMS, FIXTURES AND EQUIPMENT AFFECTED BY DEMOLITION.
 - FOR MECHANICAL REMOVALS, SEE MECHANICAL.
 - FOR ELECTRICAL REMOVALS, SEE ELECTRICAL.
 - OWNER WILL REMOVE SYSTEMS FURNITURE, POWER POLES, DIVIDERS, OFFICE EQUIPMENT, ETC. PRIOR TO CONSTRUCTION START UP. CONTRACTOR TO DISCONNECT ELECTRICAL FROM AFFECTED SYSTEM FURNITURE POWER POLES.

- DEMOLITION NOTES:**
- REMOVE EXISTING CARPET TILES IN AREAS AS INDICATED.
 - REMOVE PORTION OF PLASTIC LAMINATE WINDOW SILL AT NEW PARTITION LOCATION, REFER TO NEW LAYOUT FOR EXACT LOCATION
 - REMOVE EXISTING BORROWED LITE
 - REMOVE PORTION OF EXISTING ACOUSTIC CEILING SYSTEM TO ALLOW FOR NEW FIRE RATED PARTITIONS OF THE NEW LAN ROOM TO EXTEND TO UNDERSIDE OF STRUCTURE ABOVE.
 - REMOVE PORTION OF GYPSUM BOARD CEILING AS REQUIRED TO ALLOW FOR ELECTRICAL WORK.
 - REMOVE EXISTING GYPSUM BOARD FROM BOTH SIDES OF PARTIOTN AS INDICATED.



PARTIAL PLAN LEVEL 3:
DEMOLITION & EXISTING FLOOR PLAN
SCALE: 1:75
0m 1m 2m 3m 4m 5m 6m 7m 8m 9m 10m
PROJECT NORTH