

---

**Part 1            General**

**1.1                REFERENCES**

- .1 Canadian General Standards Board (CGSB)
  - .1 CAN/CGSB 1.189-00, Exterior Alkyd Primer for Wood.
  - .2 CGSB 1.59-97, Alkyd Exterior Gloss Enamel.
- .2 Canadian Standards Association (CSA International)
  - .1 CSA-A23.1/A23.2-04, Concrete Materials and Methods of Concrete Construction/Methods of Test and Standard Practices for Concrete.
  - .2 CSA-0121-M1978(R2003), Douglas Fir Plywood.
  - .3 CAN/CSA-S269.2-M1987(R2003), Access Scaffolding for Construction Purposes.
  - .4 CAN/CSA-Z321-96(R2001), Signs and Symbols for the Occupational Environment.

**1.2                SUBMITTALS**

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures .

**1.3                INSTALLATION AND REMOVAL**

- .1 Provide construction facilities in order to execute work expeditiously.
- .2 Remove from site all such work after use.

**1.4                SCAFFOLDING**

- .1 Scaffolding in accordance with CAN/CSA-S269.2.
- .2 Provide and maintain scaffolding, ramps, ladders, swing staging, platforms and temporary stairs.

**1.5                HOISTING**

- .1 Not uses.

**1.6                ELEVATORS**

- .1 Designated existing and permanent elevators to be used by construction personnel and transporting of materials . Co-ordinate use with Departmental Representative .
- .2 Provide protective coverings for finish surfaces of cars and entrances.

**1.7                SITE STORAGE/LOADING**

- .1 Confine work and operations of employees by Contract Documents. Do not unreasonably encumber premises with products.

- .2 Do not load or permit to load any part of Work with weight or force that will endanger Work.

## **1.8 CONSTRUCTION PARKING**

- .1 Parking will not be permitted on site.

## **1.9 SECURITY**

- .1 Provide and pay for responsible security personnel to guard site and contents of site after working hours and during holidays.

## **1.10 OFFICES**

- .1 Not used.

## **1.11 EQUIPMENT, TOOL AND MATERIALS STORAGE**

- .1 Provide and maintain, in clean and orderly condition, lockable weatherproof sheds for storage of tools, equipment and materials.
- .2 Locate materials not required to be stored in weatherproof sheds on site in manner to cause least interference with work activities.

## **1.12 SANITARY FACILITIES**

- .1 Provide sanitary facilities for work force in accordance with governing regulations and ordinances.
- .2 Post notices and take precautions as required by local health authorities. Keep area and premises in sanitary condition.

## **1.13 CONSTRUCTION SIGNAGE**

- .1 No other signs or advertisements, other than warning signs, are permitted on site.

## **1.14 PROTECTION AND MAINTENANCE OF TRAFFIC**

- .1 Not used.

## **1.15 CLEAN-UP**

- .1 Remove construction debris, waste materials, packaging material from work site daily.
- .2 Stack stored new or salvaged material not in construction facilities.

## **Part 2 Products**

### **2.1 NOT USED**

- .1 Not Used.

---

**Part 3            Execution**

**3.1                TEMPORARY EROSION AND SEDIMENTATION CONTROL**

.1            Not used.

**END OF SECTION**