



- 1. ALL DIMENSIONS AND QUANTITIES SHOWN ARE A VERY ROUGH ESTIMATE AND FOR REFERENCE ONLY WITH NO CHANGE TO CONTRACT VALUE IF OTHERWISE FOUND DURING CONSTRUCTION, CONTRACTOR TO VERIFY ALL QUANTITIES & RUN LENGTHS
- 2. ALL PARTS SUPPLIED BY OWNER TO BE FULLY INSTALLED BY CONTRACTOR.
- 3. ALL BRAZING TO BE SIL-FOS 15% WITH ARGON PURGE.
- 4. NO FLUX ON COPPER COPPER CONNECTIONS.
- 5. FLUX RECOMMENDED FOR COPPER BRASS CONNECTIONS.





TV1 CMP, TP2 Conditioner Liquid Nitrogen Supplies and PRVs

		PARTS LIST	
ITEM	QTY	PART NAME	SUPPLIED BY
2	2 22 ft Type "K" 1/2" copper pipe on TV1 CMP and TP2		Contractor
		Conditioner liquid Nitrogen supplies	
3	12 ft	Type "K" 1/2" copper pipe on PRV exhaust lines	Contractor
4	5	1/2" copper 90° elbow	Contractor
5	4	1/2" copper 45° elbow	Contractor
6	3	1/2" copper Tee	Contractor
7	3	Copper adaptor 1/2" pipe X 3/8 FNPT	Contractor
8	5	Copper adaptor 1/2" pipe X 1/2" MNPT	Cotractor
9	1	Copper adaptor 1/2" pipe X 1/2" FNPT	Contractor
10	1	Copper adaptor 3/4" pipe X 3/4" MNPT	Contractor
11	2	Copper reducing Tee 3/4" X 3/4" X 1/2"	Contractor
12	1	3/4" bronze cast cap	Contractor
14	1	3/4" copper coupling	Contractor
15	1	Reducing Tee 1/2" x 1/2" x 1/4"	Contractor
16	3	1/2" SS Hex Nipple 1-7/8" length	Contractor
17	1	SS Hex Reducing Bushing 1/4" Male X 1/8" Female	Contractor
18	3	Swagelok SS adaptor 5/8 Tube X 1/2" FNPT, SS-1010-7-8	Owner
19	4	Swagelok 5/8" brass elbow, B-1010-9	Owner
20	4	Swagelok brass adaptor 5/8" tube X 1/2" MNPT, B-1010-1-8	Owner
21	1	Swagelok VCR adaptor 1/2" FNPT X 1/2" MVCR, SS-8-VCR-7-8	Owner
22	1	Swagelok VCR adaptor 3/8" FNPT X 1/2" MVCR, SS-8-VCR-7-6	Owner
23	1	Swagelok brass adaptor 1/4" Tube X 1/2" FNPT, B-400-7-8	Owner
24	1	TV1 CMP VCR 1/2" weld elblow assembly	Owner
25	3	SS Koncentric Union 1/2" with FNPT ends, SSP 1/2 KUT	Owner
26	4	Pressure Releave Valve	Owner
27	1	1/2" SS flexible hose for TP2 Conditioner LN2 supply	Owner
28	1	1/2" SS flexible VJ hose for TV1 CMP LN2 supply	Owner
29	3	3/4" OD PRV SS tube. Modified from McMaster 89895K762	Owner
30	2	1/2" Wrochester manual isolation valve	Owner
31	1	1/2" Worcester Control Valve 60° V Seat	Owner
32	2	Swagelog 1/2" VCR Gasket, SS-8-VCR-2-GR	Owner



YVES GUINDON MANAGER, SECURITY AND FACILITIES

M. FARID, P. Eng. PROJECT MANAGER

THIS DRAWING IS THE SOLE PROPERTY OF THE CANADIAN SPACE AGENCY "CSA" AND CAN NOT BE DISTRIBUTED OR REPRODUCED WITHOUT THE EXPRESS WRITTEN PERMISSION OF THE "CSA".

COPY AND/OR ELECTRONIC FORMAT TO ANY OTHER ORGANIZATION MUST BE FOR A SPECIFIC AND LIMITED USE ONLY WITH PRE-AUTHORIZATION FROM THE "CSA" PROJECT AUTHORITY.

UPON COMPLETION OF SUCH USE, ALL HARD COPIES AND ELECTRONIC FILES MUST BE DESTROYED AND/OR RETURNED TO THE "CSA" PROJECT AUTHORITY.

5.		
4.		
3.	ISSUED FOR TENDER	SEPT, 14
2.	ISSUED FOR FINAL REVIEW	SEPT, 14
1.	ISSUED FOR REVIEW	AUG, 14
No.	REVISION	Date

PROFESSIONAL STAMP


A detail no. no. du detail B location drawing no. sur dessin no.


DAVID FLORIDA LABORATORY BUILDING No. 65, SHIRLEY'S BAY, ONTARIO

TQF TV1 / TP2 REFIT

urawing	TV1 CMP & TP2 CONDITIONER LN2	uessiii
designed	TQF	concu
date		
drawn	TQF / B-OPS	dessine
date		
reviewed	TQF	examine
date		
approved	TQF	approuve
date		
scale	N.T.S.	
project no.	CSA13-G1	no. du projet

M5





## TV1 and TP2 Gas Nitrogen Supplies

		PARTS LIST	
ITEM	QTY	PART NAME	SUPPLIED BY
1	5.5 ft	1-1/4" Type "K" copper pipe on GN2 supply manifold to TV1 and TP2	Contractor
2	5 ft	3/4" Type "K" copper pipe on TP2 GN2 supply manifold	Contractor
3	30 ft	1/2" Type "K" copper pipe on TV1 GN2 manifold, TP2 Chamber Purge and TP2 Conditioner Purge	Contractor
4	3 ft	1/4" Type "K" copper pipe on TV1 CMP purge, TV1 Pnematcis and TV1 Chamber Vent	Contractor
5	2	Copper Tee 1-1/4"	Contractor
6	2	1-1/4" to 3/4" Copper Reducing Coupling	Contractor
7	2	3/4" to 1/2" Copper Reducing Coupling	Contractor
8	1	3/4" X 3/4" X 1/2" Copper Reducing Tee	Contractor
9	1	1-1/4" 90° Copper Elbow	Contractor
10	7	1/2" Copper 90 Deg Elbow	Contractor
11	2	Copper Adaptor 1-1/4" pipe to 1-1/4" MNPT	Contractor
12	1	Copper Adapter1/2" pipe to 1/2" MNPT	Contractor
13	2	Copper Reducing Tee 1/2" x 1/2" x 1/4"	Contractor
14	1	Copper Adapter 1/4" pipe to 3/8" MNPT	Contractor
15	4	Copper Adaptor 1/2" pipe to 1/4" MNPT	Contractor
16	2	1/4" 90 Deg Copper Elbow	Contractor
17	1	1/4" 45 degree Copper Elbow	Contractor
18	1	Copper Reducing Elbow 1/2" to 1/4"	Contractor
20	1	1-1/4" GN2 Main isolation valve, McMaster 47865K26	Owner
21	3	1/2" Manual Isolation Valve, McMaster 47865K530	Owner
22	5	1/4" Miniture Regulator with Gauge, Parker R344-02CG	Owner
23	1	3/8" Solenoid Valve, ASCO 8263G206LT	Owner
24	1	3/8" Brass 3 Way Ball Valve, McMaster 4093T22	Owner
25	1	SS Tube To CMP Purge Inlet, Modify from McMaster 9157K91	Owner
26	1	3/8" Brass Ball Valve FNPT End, McMaster 4114T25	Owner
27	1	Swagelok Reducing Union 5/8" to 3/8", B-1010-6-6	Owner
28	1	Swagelok Elbow for 3/8" OD Tube, SS-600-9	Owner
29	1	Swagelok Soft Tube 3/8" ID Insert, B-815-6	Owner
30	1	Swagelok 3/8" to 1/4" Reducing Union, B-600-6-4	Owner
31	4	Swagelok Adaptor 3/8" tube to 3/8' MNPT, B-600-1-6	Owner
32	6	Swagelok Adaptor 3/8" tube to 1/4' MNPT, B-600-1-4	Owner



Agence Spatial

YVES GUINDON MANAGER, SECURITY AND FACILITIES

M. FARID, P. Eng. PROJECT MANAGER

THIS DRAWING IS THE SOLE PROPERTY OF THE CANADIAN SPACE AGENCY "CSA" AND CAN NOT BE DISTRIBUTED OR REPRODUCED WITHOUT THE EXPRESS WRITTEN PERMISSION OF THE "CSA".

TRANSFER OF THIS DRAWING IN HARD COPY AND/OR ELECTRONIC FORMAT TO ANY OTHER ORGANIZATION MUST BE FOR A SPECIFIC AND LIMITED USE ONLY WITH PRE-AUTHORIZATION FROM THE "CSA" PROJECT AUTHORITY.

UPON COMPLETION OF SUCH USE, ALL HARD COPIES AND ELECTRONIC FILES MUST BE DESTROYED AND/OR RETURNED TO THE "CSA" PROJECT AUTHORITY.

5.		
4.		
3.	ISSUED FOR TENDER	SEPT, 14
2.	ISSUED FOR FINAL REVIEW	SEPT, 14
1.	ISSUED FOR REVIEW	AUG, 14
No.	REVISION	Date
		•

PROFESSIONAL STAMP







DAVID FLORIDA LABORATORY
BUILDING No. 65, SHIRLEY'S BAY, ONTARIO

TQF TV1 / TP2 REFIT

drawing		dessin
	TV1 & TP2 GN2	
designed	TOF	concu
date	TQF	
drawn	TOE / B ODS	dessine
date	TQF / B-OPS	
reviewed	TQF	examine
date	IQF	
approved	TQF	approuve
date	IQF	
scale	N.T.S.	
	14.11.0.	
project no.	CSA13-G1	no. du projet





TV1 Compressed Air, TV1 Pneumatics and TV1 Pump Exhaust

	PARTS LIST			
ITEM	QTY	PARTNAME	SUPPLIED BY	
1	27 ft	1" Standard Wall White PVC Pipe on TV1 Roughing Pump Exhaust	Contractor	
2	5	1 inch 90° White PVC Elbow	Contractor	
3		PVC Adaptor 1" pipe to 1' MNPT	Contractor	
4	1	PVC 1" FNPT Coupling	Contractor	
5	32 ft	1/4" (3/8" OD) Copper Tubing on TV1 Compressed Air Supply and on TV1 Pneumatic	Contractor	
6	3 ft	1/8" (1/4" OD) Copper Tubing on Pnematic Supply to TV1 CMP Control Valve	Contractor	
7	2	Bronze Redusing Bushing 1" MNPT to 3/4" FNPT	Contractor	
8	1	Air Dryer	Contractor	
9	1	Copper Adapter 3/4" pipe to 1" MNPT	Contractor	
10	1	1/4" Miniture Regulator with Gauge, Parker R344-02CG	Owner	
11	1	3/8 Ball Valve FNPT End, McMaster 4114T25	Owner	
12	4	Swagelok Adaptor 3/8" tube to 3/8" MNPT, B-600-1-6	Owner	
13	2	Swagelok Adaptor 3/8" tube to 1/4" MNPT B-600-1-4	Owner	
14	2	Swagelok Adaptor 3/8" tube to 3/4" MNPT, B-600-1-12	Owner	
15	1	Swagelok Union 3/8", B-600-6	Owner	
16	1	Swagelok Reducing Tee 3/8" X 3/8" X 1/4", B-600-3-6-4	Owner	
17	1	Swagelok Adaptor 1/4" tube to 1/4" MNPT, B-400-1-4	Owner	



Agence Spatiale

YVES GUINDON MANAGER, SECURITY AND FACILITIES

M. FARID, P. Eng. PROJECT MANAGER

THIS DRAWING IS THE SOLE PROPERTY OF THE CANADIAN SPACE AGENCY "CSA" AND CAN NOT BE DISTRIBUTED OR REPRODUCED WITHOUT THE EXPRESS WRITTEN PERMISSION OF THE "CSA".

TRANSFER OF THIS DRAWING IN HARD COPY AND/OR ELECTRONIC FORMAT TO ANY OTHER ORGANIZATION MUST BE FOR A SPECIFIC AND LIMITED USE ONLY WITH PRE-AUTHORIZATION FROM THE "CSA" PROJECT AUTHORITY.

UPON COMPLETION OF SUCH USE, ALL HARD COPIES AND ELECTRONIC FILES MUST BE DESTROYED AND/OR RETURNED TO THE "CSA" PROJECT AUTHORITY.

5.		
4.		
3.	ISSUED FOR TENDER	SEPT, 14
2.	ISSUED FOR FINAL REVIEW	SEPT, 14
1.	ISSUED FOR REVIEW	AUG, 14
No.	REVISION	Date

PROFESSIONAL STAMP

A detail no. no. du detail B location drawing no. sur dessin no.

DAVID FLORIDA LABORATORY BUILDING No. 65, SHIRLEY'S BAY, ONTARIO

TQF TV1 / TP2 REFIT

drawing	C
TV1 COMP AIR, PNEUMATIC & PUMP EXHAUST	

designed	TQF	0011
date	I QI	
drawn	TQF / B-OPS	dessi
date	10175010	
reviewed	TQF	exami
date		
approved	TQF	approu
date		
scale	NTS	

CSA13-G1

M7

## GENERAL ELECTRICAL NOTES:

- 1. THESE DRAWINGS MUST BE READ IN CONJUNCTION WITH ALL ISSUED CONTRACT SPECIFICATIONS, ARCHITECTURAL, STRUCTURAL, MECHANICAL AND ELECTRICAL DRAWINGS, EXCEPT WHERE REPLACED OR CHANGED BY DIRECTIVE OR CORRECTIVE ADDENDA OR REVISED DRAWINGS AND SPECIFICATIONS.
- 2. ALL WORK MUST BE IN FULL ACCORDANCE WITH THE CANADIAN ELECTRIC CODE PART 1 C22.1-02 AND THE LATEST EDITION OF THE ONTARIO SAFETY CODE.
- 3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROVISION (SUPPLY, INSTALLATION & WIRING) OF ALL EQUIPMENT SHOWN ON THE CONTRACT DRAWINGS AND SPECIFICATIONS UNLESS CHANGED OR REPLACED BY REVISED DRAWINGS, SPECIFICATIONS ADDENDA.
- 4. THE SUCCESSFUL BIDDER SHALL ARRANGE AND PAY FOR ALL NECESSARY PERMITS AND WORK REQUIRED TO BE PERFORMED BY LOCAL AUTHORITIES INCLUDING INSPECTION BY ESA AND TESTING.
- 5. ALL DIMENSIONS SHALL BE VERIFIED ON SITE. EXACT LOCATION OF EQUIPMENT IS SUBJECT TO SITE MEASUREMENTS. DIMENSIONS SHOWN ON DRAWINGS
- 6. ALL BIDDERS AND THEIR SUB TRADES ARE STRONGLY ADVISED TO ATTEND THE SITE VISIT TO FAMILIARIZE THEMSELVES WITH THE SITE CONDITIONS AND EXACT SCOPE OF WORK.
- 7. IF ANY DISCREPANCY OCCURS ON THE ENGINEER'S DRAWINGS, THE CONTRACTOR SHALL, DURING TENDERING, ASSUME THE LARGER / GREATER. ANY DISCREPANCY SHALL BE REFERRED TO THE ENGINEER BEFORE PROCEEDING WITH THE WORK.
- 8. DRAWINGS ARE NOT INTENDED TO SHOW THE DETAILS OF CONDUIT ROUTES, OFFSETS, ETC. BE RESPONSIBLE FOR CAREFULLY EXAMINE THE WORK SITE PRIOR TO TENDER CLOSE-OUT AND INCLUDE IN THE TENDER PRICE ALL NECESSARY LABOR AND MATERIAL REQUIRED FOR A FULLY OPERABLE SYSTEM AS INTENDED.
- 9. PARTS NOTED ON DRAWINGS TO BE SUPPLIED BY OWNER SHALL BE FULLY INSTALLED & SUPPORTED BY CONTRACTOR.
- 10. ALL WIRING TO BE MINIMUM #12 AWG COPPER STRANDED WIRES UNLESS OTHERWISE STATED. CONDUITS & JUNCTION BOXES SHALL NOT BE LOADED MORE THAN 60% OF ITS MAXIMUM RATED CAPACITY.
- 11. ALL ELECTRICAL RACEWAYS & EQUIPMENT TO BE SQUARE TO BUILDING LINES AND SHALL BE SEPARATELY SUPPORTED FROM BUILDING STRUCTURE. A GROUND CONDUCTOR IS REQUIRED IN ALL RACEWAYS.
- 12. ALL CONNECTORS & COUPLINGS SHALL BE STEEL WITH INSULATED THROATS, ALL CONDUITS TO BE EMT, MINIMUM OF 3/4" UNLESS OTHERWISE STATED, ARMORED CABLE IS NOT A CONDUIT & PROJECT MANAGER MUST APPROVE THE USE OF IT.
- 13. LOCATE ALL BOXES ON STRAIGHT RUNS, EACH BOX TO BE BONDED.
- 14. ALL CONDUIT RUNS SHALL BE COLOR CODED TO BUILDING COLOR CODE, ALL CONDUITS TO BE MARKED AT THE START AND END OF EACH RUN & AT BOTH SIDES OF ANY WALL, STANDARD ELECTRIC TAPE IS TO BE USED FOR MARKING.
- 15. ALL OUTLETS, SWITCHES, COMMUNICATION JACKS TO BE WHITE, DECORA STYLE w/ BRUSHED STAINLESS STEEL COVER PLATE UNLESS OTHERWISE STATED.
- 16. USE OF TIE WRAPS OR TIE WIRE IS NOT ACCEPTABLE.
- 17. 3D MODELS SHOWS ON DRAWINGS ARE FOR REFERENCE ONLY AND NOT INTENDED TO SHOW ALL ELECTRICAL PARTS SUCH AS JUNCTION BOXES, LB'S ETC. CONTRACTOR IS RESPONSIBLE FOR FULL INSTALLATION AS DIRECTED BY CODE.
- 18. ALL CONDUITS RUNS LENGTH SHOWN ON DRAWINGS ARE FOR GENERAL REFERENCE ONLY, CONTRACTOR TO EXAMINE SITE TO DETERMINE EXACT ROUTE & DIMENSIONS.
- 19. SOME CONDUIT RUNS ARE NOT SHOWN ON 3D MODELS. CONTRACTOR TO FOLLOW ALL LINE DIAGRAMS, SCHEMATICS, 3D MODELS & TABLES FOR FULL ELECTRICAL SCOPE.
- 20. IMMEDIATELY AFTER AWARDING THE CONTRACT, THE CONTRACTOR SHALL SUBMIT TO THE ENGINEER A DETAILED WORK SCHEDULE, IN THE FORM OF COMPUTERIZED BAR CHART OUTLINING ALL PROJECT ACTIVITIES AND SCHEDULED SHUT DOWNS.
- 21. CORE DRILL WALLS AND FLOORS FOR NEW SERVICES & WIRING. SEALING OF ALL EXISTING OPENINGS AFTER SERVICES ARE REMOVED SHALL FORM PART
- 22. INSTALL EQUIPMENT IN FULL ACCORDANCE WITH THE MANUFACTURER RECOMMENDATIONS.
- 23. REFER TO NOTES 29, 30, 31 & 32 ON DRAWING A1 FOR ALL SERVICES SUPPORTS & HANGERS.
- 24. ALL WORK CARRIED OUT IN THE CLEAN ROOMS SHALL BE PRE-SCHEDULED AND SUBJECT TO CSA PROJECT MANAGER'S APPROVAL. MAINTAIN CLEAN ROOM CLASS 100,000 STANDARDS AT ALL TIMES.
- 25. WORK UNDER THIS PROJECT MAYBE CONDUCTED AT ELEVATIONS IN EXCESS OF 15m± (50 ft ±), CONTRACTOR MUST ENSURE THAT ALL STAFF & SUB CONTRACTORS ARE TRAINED IN ELEVATED WORK AND FALL PROTECTION.
- 26. ALL SERVICES OR EQUIPMENT THAT IS SHOWN TO BE REMOVED SHALL BE REMOVED IN THEIR ENTIRETY COMPLETE WITH ALL ASSOCIATED SERVICES, SUPPORTS, HANGERS ETC. ANY ABANDONED OR UNUSED COMPONENTS FOUND WITHIN THE SCOPE OF THIS PROJECT SHALL BE TERMINATED, REMOVED AND REMAINING IF ANY SHALL BE MADE SAFE.
- 27. DRAWINGS ARE NOT INTENDED TO SHOW THE DETAILS OF EACH COMPONENT TO BE INSTALLED OR REMOVED. THEY ARE ONLY PROVIDING A GENERAL OVERVIEW OF THE PROJECT SCOPE. BE RESPONSIBLE TO REVIEW THE SITE CONDITIONS DURING THE TENDER PERIOD AND EXAMINE THE EXTENT OF THE DEMOLITION, REMOVALS & NEW INSTALLATIONS.
- 28. OWNER SHALL BE GIVEN THE OPTION OF RETAINING ANY REMOVED COMPONENTS OR EQUIPMENT. COORDINATE AND HAND OVER AS NECESSARY. DISPOSE OF ANY REMAINING UNWANTED EQUIPMENT OR SERVICES AND REMOVE OFF SITE.
- 29. DO NOT SUBJECT ANY PART OF THE BUILDING TO ANY NOISE, DUST OR ANY OTHER UNACCEPTABLE ENVIRONMENTAL CONDITIONS DURING THE COURSE OF THE PROJECT. ANY NOISY / DUSTY / SMELLY ACTIVITIES SHALL BE DONE AFTER HOURS OR AT WEEKENDS, COORDINATE WITH CSA PROJECT MANAGER WITH A MINIMUM NOTICE OF 48 HOURS.



ITEMS TO BE REMOVED FROM SIDE OF SERVICE CHASE

OVERALL VIEW, REMOVE WIRE TRAY

REMOVE CONNECTOR

REMOVE

TV1 POWER CONNECTION






TP2 CONDITIONER DISCONNECT







REMOVE EXISTING WIRE TRAY C/W ALL SUPPORTS & ACCESSORIES.







No. REVISION



ISSUED FOR TENDER

ISSUED FOR REVIEW

ISSUED FOR FINAL REVIEW

AUG, 14

DAVID FLORIDA LABORATORY

Agence Spatiale

Space Agency Canadienne

YVES GUINDON

M. FARID, P. Eng.

PROJECT AUTHORITY.

PROJECT MANAGER

MANAGER, SECURITY AND FACILITIES

THIS DRAWING IS THE SOLE PROPERTY OF THE CANADIAN SPACE AGENCY "CSA"

REPRODUCED WITHOUT THE EXPRESS WRITTEN PERMISSION OF THE "CSA".

TRANSFER OF THIS DRAWING IN HARD COPY AND/OR ELECTRONIC FORMAT TO

ANY OTHER ORGANIZATION MUST BE FOR

A SPECIFIC AND LIMITED USE ONLY WITH

PRE-AUTHORIZATION FROM THE "CSA"

UPON COMPLETION OF SUCH USE, ALL

HARD COPIES AND ELECTRONIC FILES

MUST BE DESTROYED AND/OR RETURNED TO THE "CSA" PROJECT AUTHORITY.

AND CAN NOT BE DISTRIBUTED OR

TQF TV1 / TP2 REFIT

BUILDING No. 65, SHIRLEY'S BAY, ONTARIO

ELECTRICAL NOTES, MODIFICATIONS AND DEMOLITION

designed	TOF	concu
date	TQF	
drawn	TQF / B-OPS	dessine
date	1Q1 / D-O1 3	
eviewed	TQF	examine
date	IQI	
approved	TQF	approuve
date	ıQı	
scale	N.T.S.	
roject no		no du projet

TV1 OLD ELECTRICAL PANEL





RUN THIS CONDUIT TO TV1 POWER PANEL

VIEW 3





CSA13-G1

