

Harbour Development - Phase II

Mary's Harbour, Labrador

P/N: R.071733.001

Page 1

2014-09-29

1.1 GENERAL

- .1 Canada will supply certain materials in the Contract for installation and incorporation into the Work by the Contractor.

1.2 MATERIAL
SUPPLIED

- .1 Canada will supply the following:
- light fixtures associated with the poles.
 - 463 pieces of 200mm X 200mm crib timbers at 7.62m lengths. Note that the crib timbers supplied by Canada is not a complete list of crib timber required to complete the work as shown on the drawings.
 - 616 pieces of 200mm X 200mm crib timbers at 6.1m lengths. Note that the crib timbers supplied by Canada is not a complete list of crib timber required to complete the work as shown on the drawings.
 - 360 pieces of 100mm X 150mm untreated fenders at 3.05m lengths. Note that the fenders supplied by Canada is not a complete list of fenders required to complete the work as shown on the drawings.
 - 90 linear metres of 200mm X 200mm treated timber wheelguard (unpainted). Note that the wheelguard supplied by Canada is not a complete list of wheelguard length required to complete the work as shown on the drawings.
 - 90 linear metres of 200mm X 250mm treated timber coping. Note that the coping supplied by Canada is not a complete list of coping length required to complete the work as shown on the drawings
- .2 The location of all Canada supplied materials to be turned over to the

Contractor upon award of contract is the small boat basin in Mary's Harbour, Labrador.

1.3 DELIVERY
REQUIREMENTS

- .1 Once turned over to the Contractor, the Contractor will be responsible for delivery to the work site.
- .2 The Contractor will become responsible to supply all missing materials and repair or replace damaged items and missing parts discovered during transportation to site.
- .3 Failure of the Contractor to make a complete check of the Canada-supplied material and to acknowledge receipt of same shall not relieve him of this contractual responsibility to replace or repair any item subsequently found to be missing or damaged.
- .4 Departmental Representative will make final determination as to whether an item can be repaired or must be replaced.

1.4 CONTRACTOR'S
DUTIES

- .1 Pick-up Canada-supplied material, at the small boat basin in Mary's Harbour, Labrador.
- .2 Take possession of Canada-supplied material immediately upon pick-up and be responsible for transportation to site.
- .3 Obtain and pay for services to load and transport to site.
- .4 Unload and handle at site, including lifting, uncrating etc.
- .5 Store material on site at a location

approved by Departmental Representative.
Provide protection against inclement
weather and site damage by use of
appropriate covers.

- .6 Be responsible for the protection of such material against damage, loss, theft and fire from date of receipt, during transportation, loading, unloading, temporary storage and until final installation of work is accepted by the Departmental Representative.
- .7 Any damage or loss of such material shall result in the Contractor being responsible for replacement or repair of equipment at no cost to Canada.
- .8 The decision as to whether damaged items may be repaired or must be replaced with new equipment shall be the Departmental Representative's decision.
- .9 Install such material and incorporate into the work. Perform assembly and make all connections as required to make item functional.
- .10 Dispose of containers, crating and protective covering off site as directed by the Departmental Representative.