

ADDENDUM 3

Please be advised of the following changes to the Contract Drawings and Tender Documents:

DRAWINGS

Discipline	Drawing No.	Revisions
Waste Transfer	PGWMF-X-02	a. No revision, PGWMF-X-02 was inadvertently not included with September IFT, now provided as part of Addendum 3.

SPECIFICATIONS

Section	Page	Article	Description
Appendices	N/A	N/A	<p>New Appendices added:</p> <ul style="list-style-type: none"> R9: Golder 2013 Summary of Historical Geotechnical Information PGWMF R10: Golder 2010 Spring Geotechnical Report R11: Golder 2010 Fall Geotechnical Report R12: Golder 2011 Spring Geotechnical Report R13: Golder 2011 Fall Geotechnical Report R14: Golder 2012 Spring Geotechnical Report R15: Golder 2013 Spring Geotechnical Report
01 14 00	1	1.3.2	Text added: Limit construction activities to the hours of 7:00am to 11:00pm Monday through Saturday and 10:00am to 5:00pm Sunday, in accordance with the Municipality of Clarington Noise By-law 2007-071, as amended. As required by the 2009 Port Granby Long-Term Low-Level Radioactive Waste Management Project Screening Report (Appendix L) site work involving the use of haul vehicles, heavy machinery or construction equipment is limited to daylight hours.
01 52 00	11	1.15.7	Added: "Contractor is to operate and maintain the weigh scales and associated equipment as necessary." All other sub-paragraphs renumbered.
	11	1.15.9.5 (formally 1.15.8.5)	Text deleted: The Contractor shall supply a scale house or trailer properly ventilated and shall be clean, dry and weathertight, with a minimum floor space of 8.0 square metres and minimum head room of 2.1 metres.
02 41 23	1	1.1.2.3	Revised: 150 mm treated effluent discharge pipe from the Sedimentation Lagoon as well and associated abandoned discharge piping from Sedimentation and Treatment lagoons.
	2	1.1.2.14	Item deleted, remaining items renumbered.
	2	1.1.2.15	Text added to sub-paragraph: Select hydro poles and associated wiring per the direction of the Departmental Representative. Poles may require either complete

Section	Page	Article	Description
			removal or relocation, direction to be provided in the field by the Departmental Representative.
	2	1.1.3.5 and 1.1.3.6	Sub-paragraphs.5 and .6 added to 1.1.3.
	2	1.1.4.2	Text added: Components of the New East Reservoir pumping station not required as part of the East Gorge Groundwater Collection system final configuration .
	3	1.1.4.3	Text added / revised: Constructed Storm Water Management Ponds and associated appurtenances, drainage ditches and berms if not a part of the final site plan or covered designated as to remain elsewhere in the Contract Documents.
	3	1.1.4.4	Text added: Applicable facilities (stockpile areas, laydown areas, construction facilities , decontamination facilities, parking areas etc.) and site services if not designated as to remain elsewhere in the Contract Documents and not indicated as to remain in the final site plan.
40 05 13	11	1.5.6	Revised: Provide hanger, guide, anchor, support system design details including locations, load information, design calculations and illustrative drawings, stamped and signed by a Professional Departmental Representative Engineer .