

PART 1 - GENERAL

1.1 WASTE
MANAGEMENT GOALS

- .1 Prior to start of Work conduct meeting with Departmental Representative to review and discuss PWGSC's Waste Management Plan and Goals.
- .2 PWGSC's Waste Management Goal 75 percent of total Project Waste to be diverted from landfill sites. Provide Departmental Representative documentation certifying that waste management, recycling, reuse of recyclable and reusable materials have been extensively practiced.
- .3 Accomplish maximum control of solid construction waste.
- .4 Preserve environment and prevent pollution and environment damage.

1.2 RELATED
REQUIREMENTS

- .1 Division 14.

1.3 REFERENCES

- .1 LEED Canadian Green Building Council (CGBC), Green Building Rating System, For New Construction and Major Renovations LEED Canada-NC, Version 1.0 - December 2004.

1.4 DEFINITIONS

- .1 Class III: non-hazardous waste - construction renovation and demolition waste.
- .2 Cost/Revenue Analysis Workplan (CRAW): based on information from WRW, and intended as financial tracking tool for determining economic status of waste management practices.
- .3 Demolition Waste Audit (DWA): relates to actual waste generated from project.
- .4 Inert Fill: inert waste - exclusively asphalt and

concrete.

- .5 Materials Source Separation Program (MSSP): consists of series of ongoing activities to separate reusable and recyclable waste material into material categories from other types of waste at point of generation.
- .6 Recyclable: ability of product or material to be recovered at end of its life cycle and re-manufactured into new product for reuse.
- .7 Recycle: process by which waste and recyclable materials are transformed or collected for purpose of being transferred into new products.
- .8 Recycling: process of sorting, cleansing, treating and reconstituting solid waste and other discarded materials for purpose of using in altered form. Recycling does not include burning, incinerating, or thermally destroying waste.
- .9 Reuse: repeated use of product in same form but not necessarily for same purpose. Reuse includes:
 - .1 Salvaging reusable materials from re-modelling projects, before demolition stage, for resale, reuse on current project or for storage for use on future projects.
 - .2 Returning reusable items including pallets or unused products to vendors.
- .10 Salvage: removal of structural and non-structural materials from deconstruction/disassembly projects for purpose of reuse or recycling.
- .11 Separate Condition: refers to waste sorted into individual types.
- .12 Source Separation: acts of keeping different types of waste materials separate beginning from first time they became waste.
- .13 Waste Audit (WA): detailed inventory of materials in building. Involves quantifying by volume/weight amounts of materials and wastes generated during construction, demolition, deconstruction, or renovation project. Indicates quantities of reuse, recycling and landfill. Refer to Schedule A.
- .14 Waste Management Co-ordinator (WMC) : contractor representative responsible for supervising waste management activities as well as coordinating related, required submittal and reporting requirements.

- .15 Waste Reduction Workplan (WRW): written report which addresses opportunities for reduction, reuse, or recycling of materials. Refer to Schedule B. WRW is based on information acquired from WA (Schedule A).

1.5 DOCUMENTS

- .1 Maintain at job site, one copy of following documents:
 - .1 Waste Audit.
 - .2 Waste Reduction Workplan.
 - .3 Material Source Separation Plan.
 - .4 Schedules A, B, C, D and E completed for project.

1.6 WASTE AUDIT (WA)

- .1 Conduct WA prior to project start-up.
- .2 Prepare WA: Schedule A.
- .3 Record, on WA - Schedule A, extent to which materials or products used consist of recycled or reused materials or products.

1.7 WASTE REDUCTION WORKPLAN (WRW)

- .1 Prepare WRW prior to project start-up.
- .2 WRW should include but not limited to:
 - .1 Destination of materials listed.
 - .2 Deconstruction/disassembly techniques and sequencing.
 - .3 Schedule for deconstruction/disassembly.
 - .4 Location.
 - .5 Security.
 - .6 Protection.
 - .7 Clear labelling of storage areas.
 - .8 Details on materials handling and removal procedures.
 - .9 Quantities for materials to be salvaged for reuse or recycled and materials sent to landfill.
- .3 Structure WRW to prioritize actions and follow 3R's hierarchy, with Reduction as first priority, followed by Reuse, then Recycle.

- .4 Describe management of waste.
- .5 Identify opportunities for reduction, reuse, and recycling of materials. Based on information acquired from WA.
- .6 Post WRW or summary where workers at site are able to review content.
- .7 Set realistic goals for waste reduction, recognize existing barriers and develop strategies to overcome these barriers.
- .8 Monitor and report on waste reduction by documenting total volume and cost of actual waste removed from project.

1.8 DEMOLITION
WASTE AUDIT (DWA)

- .1 Prepare DWA prior to project start-up.
- .2 Complete DWA: Schedule C.
- .3 Provide inventory of quantities of materials to be salvaged for reuse, recycling, or disposal.

1.9 COST/REVENUE
ANALYSIS WORKPLAN
(CRAW)

- .1 Prepare CRAW: Schedule D.

1.10 MATERIALS
SOURCE SEPARATION
PROGRAM (MSSP)

- .1 Prepare MSSP and have ready for use prior to project start-up.
- .2 Implement MSSP for waste generated on project in compliance with approved methods and as reviewed by Departmental Representative.
- .3 Provide on-site facilities for collection, handling, and storage of anticipated quantities of reusable and recyclable materials.
- .4 Provide containers to deposit reusable and recyclable materials.
- .5 Locate containers in locations, to facilitate deposit of materials without hindering daily operations.

- .6 Locate separated materials in areas which minimize material damage.
- .7 Collect, handle, store on-site, and transport off-site, salvaged materials in separate condition.
 - .1 Transport to approved and authorized recycling facility.
- .8 Collect, handle, store on-site, and transport off-site, salvaged materials in combined condition.
 - .1 Ship materials to site operating under Certificate of Approval.
 - .2 Materials must be immediately separated into required categories for reuse or recycling.

1.11 WASTE
PROCESSING SITES

- .1 Contact Province.

1.12 STORAGE,
HANDLING AND
PROTECTION

- .1 Store, materials to be reused, recycled and salvaged in locations as directed by Departmental Representative.
- .2 Unless specified otherwise, materials for removal do not become Contractor's property.
- .3 Protect, stockpile, store and catalogue salvaged items.
- .4 Separate non-salvageable materials from salvaged items. Transport and deliver non-salvageable items to licensed disposal facility.
- .5 Protect structural components not removed for demolition from movement or damage.
- .6 Support affected structures. If safety of building is endangered, cease operations and immediately notify Departmental Representative.
- .7 Protect surface drainage, mechanical and electrical from damage and blockage.
- .8 Separate and store materials produced during dismantling of structures in designated areas.
- .9 Prevent contamination of materials to be salvaged and recycled and handle materials in accordance

with requirements for acceptance by designated facilities.

- .1 On-site source separation is recommended.
- .2 Remove co-mingled materials to off-site processing facility for separation.
- .3 Provide waybills for separated materials.

1.13 DISPOSAL OF WASTES

- .1 Do not bury rubbish or waste materials.
- .2 Do not dispose of waste, volatile materials, mineral spirits, oil and or paint thinner into waterways, storm, or sanitary sewers.
- .3 Keep records of construction waste including:
 - .1 Number and size of bins.
 - .2 Waste type of each bin.
 - .3 Total tonnage generated.
 - .4 Tonnage reused or recycled.
 - .5 Reused or recycled waste destination.
- .4 Remove materials from deconstruction as deconstruction/disassembly Work progresses.
- .5 Prepare project summary to verify destination and quantities on a material-by-material basis as identified in pre-demolition material audit.

1.14 USE OF SITE AND FACILITIES

- .1 Execute work with least possible interference or disturbance to normal use of premises.
- .2 Maintain security measures established by existing facility.

1.15 SCHEDULING

- .1 Co-ordinate Work with other activities at site to ensure timely and orderly progress of Work.

PART 2 - PRODUCTS

<u>2.1 NOT USED</u>	.1	Not Used.
---------------------	----	-----------

PART 3 - EXECUTION

<u>3.1 SELECTIVE DEMOLITION</u>	.1	Reuse of Building Elements: this project has been designed to result in end of project rates for reuse of building elements as follows: do not demolish building elements beyond what is indicated on Drawings without approval by Departmental Representative's.
-------------------------------------	----	---

- | | | |
|--|----|---|
| | .1 | Building Structure and Shell: 75 percent. |
| | .2 | Interior Non-Shell Elements: 50 percent. |

<u>3.2 APPLICATION</u>	.1	Do Work in compliance with WRW.
	.2	Handle waste materials not reused, salvaged, or recycled in accordance with appropriate regulations and codes.

<u>3.3 CLEANING</u>	.1	Remove tools and waste materials on completion of Work, and leave work area in clean and orderly condition.
	.2	Clean-up work area as work progresses.
	.3	Source separate materials to be reused/recycled into specified sort areas.

<u>3.4 DIVERSION OF MATERIALS</u>	.1	From following list, separate materials from general waste stream and stockpile in separate piles or containers, as reviewed by Departmental Representative, and consistent with applicable fire
---------------------------------------	----	--

regulations.

.1 Mark containers or stockpile areas.

.2 Provide instruction on disposal practices.

.2 On-site sale of salvaged, recovered, reusable and or recyclable materials is not permitted.

.3 Demolition Waste:

Material Type	Recommended Diversion %	Actual Diversion %
Acoustic Tile	50	_____
Acoustical Insulation	100	_____
Carpet	100	_____
De-mountable Partitions	80	_____
Doors and Frames	100	_____
Electrical Equipment	80	_____
Furnishings	80	_____
Marble Base	100	_____
Mechanical Equipment	100	_____
Metals	100	_____
Rubble	100	_____
Wood (uncontaminated)	100	_____
Other		_____

.4 Construction Waste:

Material Type	Recommended Diversion %	Actual Diversion %
Cardboard	100	_____
Plastic Packaging	100	_____
Rubble	100	_____
Steel	100	_____
Wood (uncontaminated)	100	_____
Other		_____

3.5 WASTE AUDIT (WA)

.1 Schedule A - Waste Audit (WA):

(1) Material Category	(2) Material Quantity Unit	(3) Estimate d Waste %	(4) Total Quantity of Waste (unit)	(5) Generati on Point	(6) % Recycled	(7) % Reused
--------------------------	-------------------------------	---------------------------	---------------------------------------	--------------------------	-------------------	-----------------

Wood
and

PWGSC Elevator Upgrade
John Cabot Bldg.
St. John's, NFLD
Project No. R.053455.006

WASTE MANAGEMENT/DISPOSAL

Section 01 74 21
Page 9
2014-07-13

Plastics
Material
Description

Off-cuts

Warped
Pallet
Forms

Plastic
Packaging

Cardboard
Packaging

Other

Doors
and
Windows
Material
Description

Painted
Frames

Glass

Wood

Metal

Other

3.6 WASTE REDUCTION .1 Schedule B:
WORKPLAN (WRW)

(1) Material Category	(2) Person(s) Responsible	(3) Total Quantity of Waste (unit)	(4) Reused Amount (units) Projected	Actual	(5) Recycled Amount (unit) Projected	Actual	(6) Material(s) Destination
-----------------------------	---------------------------------	--	---	--------	--	--------	-----------------------------------

Wood
 and
 Plastic
 s
 Materia
 l
 Descrip
 tion

Chutes

Warped
 Pallet
 Forms

Plastic
 Packagi
 ng

Cardboa
 rd
 Packagi
 ng

Other

Doors
 and
 Windows
 Materia
 l
 Descrip
 tion

Painted
 Frames

Glass

Wood

Metal

Other

3.7 DEMOLITION
WASTE AUDIT (DWA)

.1 Schedule C - Demolition Waste Audit (DWA):

(1)	(2)	(3) Unit	(4)	(5)	(6)	(7)
-----	-----	----------	-----	-----	-----	-----

Material Description	Quantity	Total	Volume (cum)	Weight (cum)	Remarks and Assumpti ons
Wood					
Wood Stud					
Plywood					
Baseboard-Wood					
Door Trim - Wood					
Cabinet					
Doors and Windows					
Panel Regular					
Slab Regular					
Wood Laminate					
Byfold - Closet					
<u>Glazing</u>					

3.8 COST/REVENUE ANALYSIS WORKPLAN (CRAW) .1 Schedule D - Cost/Revenue Analysis Workplan (CRAW):

(1) Material Description	(2) Total Quantity (unit)	(3) Volume (cum)	(4) Weight (cum)	(5) Disposal Cost/Credit \$ (+/-)	(6) Category Sub-Total \$ (+/-)
Wood					
Wood Stud					

Plywood

Baseboard
- Wood

Door Trim
- Wood

Cabinet \$

Doors and
Windows

Panel
Regular

Slab
Regular

Wood
Laminate

Byfold -
Closet

Glazing \$

(7) Cost \$
(-) /
Revenue
(+)