



SMALL CRAFT HARBOURS CENTRAL AND ARCTIC REGION




NOTES:


1. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS OTHERWISE STATED
2. ELEVATIONS SHOWN ARE IN METRES
3. ALL DIMENSIONS ARE TO FACE UNLESS SHOWN OTHERWISE
4. COIR DRINKING TO BE RIGIDLY SAW-CUT
5. TIMBER FOR FLOAT WHARVES TO BE S4S
6. ALL WELDS TO BE FINE CONTINUOUS TILLET WELDS UNLESS OTHERWISE NOTED
7. PROVIDE ENGINEER WITH 48 HOURS NOTICE
8. CONTRACTOR TO SUPPLY NEW FLOAT WHARF (SEE DRAWING C-5) AT PAVING PLANT SITE
9. ALL ALUMINUM RAMP AND FLOAT WHARVES TO BE STORED AT HARBOUR SITE - INSTALL AS DETAILED ON DRAWING C-3
10. CONTRACTOR TO SUPPLY ANY ADDITIONAL HINGES AND HARDWARE REQUIRED TO COMPLETE INSTALLATION OF FLOATS AND RAMP AS SHOWN
11. CONTRACTOR TO TRANSPORT 1 - 1829 x 4877 AND 2 - 1219 x 4877 FLOATS TO CANADIAN COAST GUARD YARD IN SELKIRK, MB
12. CONTRACTOR WILL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS
13. CONTRACTOR TO ENSURE SOURCE OF ROCK MATERIAL HAS BEEN IDENTIFIED PRIOR TO SUBMISSION OF TENDER, INCLUDING TIMELINES FOR PERMITTING



SITE PLAN
SCALE: 1:750



SITE PLAN - PACKING PLANT



SITE PLAN - HARBOUR

REVISED:		DATE:
0	ISSUED FOR TENDER	SEPT. 24, 2014
SCALE:	CLASS:	
AS SHOWN		
PROJECT:		
BREAKWATER REPAIRS		
DESCRIPTION:		
SITE PLAN		
DRAWN:	APPROVED:	
SCH	SCH	
DATE:	DATE:	
SEPTEMBER 2014	SEPTEMBER 2014	
LOCATION:		
PINE DOCK MANITOBA		
DRAWING NO.:	LOCATOR CODE:	
C-1 of 5	5537	