



**Project Title:** Emergency Generator Installation  
Building 49  
Central Experimental Farm (CEF), Ottawa (Ontario)

**Solicitation No:** 14-1234

November 18, 2014

The following changes in the tender documents are effective immediately. This addendum will form part of the contract documents

---

### **Q & A**

**Q8. The details 5 and 6 on drawing E02 state: Compacted “A” backfill. Can you define what the “A” Backfill is?**

A8. The “A” Backfill is Granular “A” size stone. See below modifications to the Drawings.

**Q9. Could you confirm there are only 3 bollards to be installed as per drawing E01?**

A9. There will be a total of 5 bollards to be installed. Their locations will be provided on site during construction.

**Q10. At drawing E01, specific notes ask for 2 x 100mm and 3 x 27mm conduits but details 5 and 6 of drawing E02 seem to indicate 1 x 53mm, 1 x 41mm, 1 x 35mm and 2 x 27mm. It appears that none of the conduits in details 5 and 6 can accommodate the 2 x 4(350MCM) runs back to the building. Could you confirm what is required for the project?**

A10. The conduits sizes should be 2 x 100mmC and 3 x 27mmC. See below modifications to the Drawings.

**Q11. Are any trees around the location of the generator to be removed?**

A11. No. Tree removal is the sole responsibility of Agriculture and Agri-Food Canada (AAFC). The Contractor must not remove any trees.

### **INVITATION TO TENDER**

1. In accordance with GI13 “Approval of Alternative Materials” or the General Instructions to Bidders, for the purpose of the present project, the following material is approved as an Alternative Material and can be used for the execution of the work:

MTU Onsite Energy  
MTU Model 6R0113 DS200 (200kWe/ 60Hz / Standby)  
Enclosure 12 gauges and tank ULC S601 370 Gal. Extended  
The enclosure will not have an Exhaust Scoop to meet the required dB.

### **DRAWINGS**

1. At Drawing E02, Details 5 and 6, Notes:

**Add:** 5. THE “A” BACKFILL IS GRANULAR “A” SIZE STONE.



## Addendum 5

**Project Title:** Emergency Generator Installation  
Building 49  
Central Experimental Farm (CEF), Ottawa (Ontario)

**Solicitation No:** 14-1234

November 18, 2014

---

**2. At Drawing E02, Details 5 and 6:**

**Delete:** 53mm, 41mm and 35mm.

**Replace with:** 100mmC, 100mmC and 27mmC

**ALL OTHER TERMS AND CONDITIONS REMAIN THE SAME**