NOTES

SURVEY PARTY CHIEF GERALD SPEAR
SURVEY VESSEL N/A
SURVEY DATE(S) JUNE 25,2014

SOUNDER TYPE: N/A
SOUNDER SETTING MIN/INST N/A
DEPTH GATE USED 1.0m

POSITIONING SYSTEM USED TRIMBLE R7 RTK
LAND SURVEY POSITION BY

RAW DATA FILE(S): N/A
CAD DRAWING FILE(S): TIGNISHCONTAINMENT2014.DWG

TIDAL REDUCTION SCHEME PWC PT"BANK2012"(REBAR AND CAP) ELEV. +2.477m ABOVE C.D.
REFERENCED TO C.H.S. B.M. 91P9348 ELEV. +2.550m ABOVE C.D.

OFFICE PROCESSOR GERALD SPEAR
DATE OF PROCESSING JUNE 27,2014

MODE OF PLOTTING N/A
MATRIX CELL 1.2 by 3.0m

CONTROL POINTS:

Pt. NAME	EASTING	NORTHING	CD ELEV	DESCRIPTION
WHARF	424352.964	5200202.286	+2.54m	PWC CONTROL
BANK2012	423807.631	5200522.001	+2.477m	PWC CONTROL
91P9348			+2.550m	CHS BM

DRAWING REVIEWED BY:

SIGNATURE DATE

NOTE: ALMOST ALL SHORELINE, WHARF AND BUILDING INFORMATIONS WERE OBTAINED FROM PWGSC REALTY COMPOSITE PLANS SURVEYED IN JUNE 1997. AREAS WHERE ELEVATIONS ARE SHOWN HAVE STRUCTURES UPDATED TO DECEMBER,2012.THE PLAN IS BASED ON THE NAD83 (1989) AND UTM ZONE 20 PROJECTION.

NOTES

1. LOCATION OF BM/ A CHS BRONZE TABLET STAMPED 91P9348 SET HORIZONTALLY INTO THE CONCRETE FOUNDATION FOR THE LIGHTHOUSE. THE BM IS IN THE W FACE OF THE SW CORNER 0.24m S OF AIR VENT AND 0.23 m N OF SW
2. CROSS HATCHET LOCATES THE SLOPE AREAS.
3. CROSS HATCH AREA WILL BE SLOPED AT 3:1
4. THE ESTIMATED VOLUME TO BE REMOVED FROM THE CELLS AND SLOPES WAS CALCULATE FROM THE PLAN TO BE 20,000 cm.

GRID NORTH
UNIVERSAL TRANSVERSE MERCATOR
N.A.D. 83 ZONE 20

Public Works and Government Services Canada / Travaux Publics et Services gouvernementaux Canada

revisions | date

project | projet

DISPOSAL CELL
TIGNISH
PRINCE COUNTY, P.E.I.

drawing | dessin

SITE PLAN

designed | conçu
date
drawn PWGSC | dessiné
date OCTOBER 30, 2014
approved | approuvé
date 2014/11/02
Tender | Soumission
PWGSC Project Manager | Administrateur de projets TPSGC
project number | no. du projet
R.034760.002
drawing no. | no. du dessin
1 OF 1

PWGSC AO (2004)

E-DRM/GDD-E: 499595 Version 1