

Solicitation No. W8476-145074/B	Amd. No. 001	Buyer ID 019qd
Client Ref. No. W8476-145074	File No. 019qdW8476-145074	

Questions and Answers for Solicitation W8476-145074/B
Closing December 17, 2014

Q1- In regards to the drawings in this file, Drawing No. 1377692, the bottom right hand corner says Drawing 1 of 2 however the second drawing 2 of 2 is not included in the package. Would you be able to provide this drawing?

A1 – Yes, provided. See attached drawing.

Q2- Line item number 12 on page 4 is a “Grounding Long Strap Assy.” the drawing number says “9381496-8.”The drawing for this Grounding Long Strap Assy is not included in the package. Please provide?

A2 – Provide. See attached drawing.

Q3 - We would need item 10 drawing 9379540-1

A3 – Provide. See attached drawing.

Q4 – The attached hard copies of drawings received with the above subject tender are not clear enough to read. Please reissue them in a CD or PDF Format

A4 – Yes, please send me an email and a PDF format or CD will be provided.

Q5 – Will you extend the closing date of the tender sufficiently, to allow time to prepare an offer?

A5 – Yes, the solicitation closing date will be extended to January 7, 2015 at 2pm.

Solicitation No.
W8476-145074/B

Amd. No.
001

Buyer ID
019qd

Client Ref. No.
W8476-145074

File No.
019qdW8476-145074

Drawing No. 1377692




NOTICE



This documentation has been reviewed by the technical authority and does not contain controlled goods. Disposal notices and handling instructions originally received with the document shall continue to apply.


AVIS

Cette documentation a été revue par l'autorité technique et ne contient pas de marchandises contrôlées. Les avis de divulgation et les instructions de manutention reçues originellement doivent continuer de s'appliquer.

NOT

UNLESS OTHERWISE SPECIFIED SAUF INDICATION CONTRAIRE:	
1.	DIMENSIONS ARE IN DIMENSIONS SONT EN INCHES
2.	TOLERANCE/TOLÉRANCES
	FRACTIONS ± —
	DECIMALS .XXX ± —
	DECIMALES .XX ± —
	ANGLES X ± —
	ANGLES ± —
3.	SURFACE FINISH FINIS DE SURFACES 
INTERPRETATION: IF STD D-61-400-201/ISO-030	
INTERPRÉTATION: L'ÉCHELLE/ÉCHELLE 3.	

ES	APPLICATION/USAGE
	SCALE/ ÉCHELLE 1:2
	 

-	-	TDAN 134470154				-	-	-	-
ZONE	LTM LET	REVISION				DATE	SWN DES	CHD VER	APP APP
	National Defense					Canada			
DWNGDES	G. GAUTHIER	CHKDVR	W. MAYDA	INSPECT/INSPECTE	DSO-4	CF APPLICATION FC	CLC/PM-103		
DESIGN AGENT CONCEPTION	3AT8D	NORMC/MCF	35907			APPLD DATE EXAMIN	13-09-15		AC
TITLE/TITRE						DRAWING NO NO Dessin			
RISER ASSY, GENERAL PURPOSE						1377692			
						SHEET	2	CF	2
						FEUILLE	2	DE	2

NOTICE

THE DEPARTMENT OF NATIONAL DEFENCE DOES NOT WARRANT OR GUARANTEE THE CORRECTNESS OR ACCURACY OF THE INFORMATION CONTAINED IN THIS DOCUMENT FOR OTHER THAN OFFICIAL DEFENCE PURPOSES. THE DEPARTMENT OF NATIONAL DEFENCE DOES NOT GRANT ANY LICENSE, CONVEY ANY INTELLECTUAL PROPERTY RIGHTS, OR GIVE PERMISSION FOR ANY USE IN WHOLE OR IN PART BY ANY RECIPIENT, HOLDER OR USER OF THIS DOCUMENT, AND ANY SUCH PERSON USING THIS DOCUMENT OR THE INFORMATION THEREIN DOES SO AT THEIR OWN RISK.

NOTICE

DOI 10.1002/ps.1456

10

10543-6 Ch-GW

9

8

7

6

5

4

Solicitation No. W8476-145074/B	Amd. No. 001	Buyer ID 019qd
Client Ref. No. W8476-145074	File No. 019qdW8476-145074	

Drawing No. 9381496-8

Time (months)	Number of individuals
0	0
20	20
40	40
60	60
80	80
100	100
120	100
140	100
160	100
180	100
200	100

	-	TDAN 914471164/A059	-	-	-	-
20	A	EC 4504 INCORPORATED	02-03-15	SP	TS	BD
10	-	PRODUCTION RELEASE	01-08-03	S.P.	M.P.	M.F.
ZONE	LTR LET	REVISION	DATE	DWN DESS	CKD VER	APPY APP
 National Defense Défense nationale			Canada TM			
DWN/DESS S. PEREIRA		CKD/VER M. FEDORUK	INSPECT/INSPECTE DTICS 3	CF APPVL/APP CF DLCSRM		
DESIGN AGENT/CONCEPTION 3AF83		NSCM/CAOF 35907	APPVL DATE D'APPROB 01-08-03		A2	
TITLE/TITRE			DRAWING NO DU DESSIN 9381496			
GROUNDING STRAP ASSY, LONG			SHEET FOLIO 1 OF 2			

THE DEPARTMENT OF NATIONAL DEFENCE DOES NOT WARRANT OR GUARANTEE THE CORRECTNESS OR ACCURACY OF THE INFORMATION CONTAINED IN THIS DOCUMENT FOR OTHER THAN OFFICIAL DEFENCE PURPOSES. THE DEPARTMENT OF NATIONAL DEFENCE DOES NOT GRANT ANY LICENSE, CONVEY ANY INTELLECTUAL PROPERTY RIGHTS, OR GIVE PERMISSION FOR ANY USE IN WHOLE OR IN PART BY ANY RECIPIENT, HOLDER OR USER OF THIS DOCUMENT, AND ANY SUCH PERSON USING THIS DOCUMENT OR THE INFORMATION THEREIN DOES SO AT THEIR OWN RISK.


INCH PO																								0 1 2 3 4 5 6 7 8 9 10												NO -2 -1		ITEM NO DE L'ART	IDENTIFYING NO D'IDENTIFICATION	NOMENCLATURE/DESCRIPTION	SPECIFICATION	CODE IDENT CODE D'IDENT
																								QTY/QTÉ																		

DASH NO.	DIM X	DIM Z	PART MARKING	DATALIST
-1	127.0 ^{+10 -0}	178.8 ^{+10 -0}	9381496-1	DL-9381496-1
-2	127.0 ^{+10 -0}	178.8 ^{+10 -0}	9381496-2	DL-9381496-2
-3	127.0 ^{+10 -0}	178.8 ^{+10 -0}	9381496-3	DL-9381496-3
-4	165.0 ^{+10 -0}	216.8 ^{+10 -0}	9381496-4	DL-9381496-4
-5	165.0 ^{+10 -0}	216.8 ^{+10 -0}	9381496-5	DL-9381496-5
-6	206.0 ^{+15 -0}	257.8 ^{+15 -0}	9381496-6	DL-9381496-6
-7	206.0 ^{+15 -0}	257.8 ^{+15 -0}	9381496-7	DL-9381496-7
-8	316.0 ^{+25 -0}	367.8 ^{+25 -0}	9381496-8	DL-9381496-8
-9	316.0 ^{+25 -0}	367.8 ^{+25 -0}	9381496-9	DL-9381496-9
-10	206.0 ^{+15 -0}	257.8 ^{+15 -0}	9381496-10	DL-9381496-10
-11	206.0 ^{+15 -0}	257.8 ^{+15 -0}	9381496-11	DL-9381496-11
-12	316.0 ^{+25 -0}	367.8 ^{+25 -0}	9381496-12	DL-9381496-12
-13	450.0 ^{+25 -0}	501.8 ^{+25 -0}	9381496-13	DL-9381496-13
-14	1000.0 ^{+40 -0}	1051.8 ^{+40 -0}	9381496-14	DL-9381496-14
-15	316.0 ^{+25 -0}	367.8 ^{+25 -0}	9381496-15	DL-9381496-15
-16	165.0 ^{+15 -0}	216.8 ^{+15 -0}	9381496-16	DL-9381496-16
-17	1348.2 ^{+40 -0}	1400 ^{+40 -0}	9381496-17	DL-9381496-17
-18	62.0 ^{+10 -0}	127.0 ^{+10 -0}	9381496-18	DL-9381496-18
-19	62.0 ^{+10 -0}	127.0 ^{+10 -0}	9381496-19	DL-9381496-19
-20	141.0 ^{+10 -0}	206.0 ^{+10 -0}	9381496-20	DL-9381496-20
-21	141.0 ^{+10 -0}	206.0 ^{+10 -0}	9381496-21	DL-9381496-21
-22	385.0 ^{+25 -0}	450.0 ^{+25 -0}	9381496-22	DL-9381496-22
-23	250.0 ^{+15 -0}	300.0 ^{+15 -0}	9381496-23	DL-9381496-23
-24	698.2 ^{+40 -0}	750.0 ^{+40 -0}	9381496-24	DL-9381496-24

Technical drawing of a mechanical part, likely a connector or bracket. The drawing shows a cross-section of the part, which has a central threaded section (hatched) and two circular end features. Dimension lines indicate X (length of the central section) and Z (total length).

Technical drawing of a mechanical part, likely a connector or bracket. The drawing shows a side view of the part, which has two circular end features. Dimension lines indicate 1 (length of the central section) and 2 (total length).

3 4 5 - SEE NOTE 4



NOTES:

1. REMOVE ALL BURRS AND SHARP EDGES.
2. BAG AND TAG IAW MIL-STD-129, COLOUR, HEIGHT, METHOD ANY, PART NUMBER AS PER TABLE ABOVE.
3. GROUND STRAPS MUST BE REPLACED AFTER NBC DECONTAMINATION.
4. THE BRAID IS TO BE FLUSH TO A MAX OF +1mm PAST THE TERMINAL END OF THE LUG BARREL.

NOTICE

THE DEPARTMENT OF NATIONAL DEFENCE DOES NOT WARRANT OR GUARANTEE THE CORRECTNESS OR ACCURACY OF THE INFORMATION CONTAINED IN THIS DOCUMENT FOR OTHER THAN OFFICIAL DEFENCE PURPOSES. THE DEPARTMENT OF NATIONAL DEFENCE DOES NOT GRANT ANY LICENSE, CONVEY ANY INTELLECTUAL PROPERTY RIGHTS, OR GIVE PERMISSION FOR ANY USE IN WHOLE OR IN PART BY ANY RECIPIENT, HOLDER OR USER OF THIS DOCUMENT, AND ANY SUCH PERSON USING THIS DOCUMENT OR THE INFORMATION THEREIN DOES SO AT THEIR OWN RISK.

5. DIMENSION Z FOR REFERENCE ONLY

UNLESS OTHERWISE SPECIFIED/SAUF INDICATION CONTRAIRE:

1. DIMENSIONS ARE IN DIMENSIONS SONT EN mm

2. TOLERANCES

FRACTIONS ±

DECIMALS XXX±

DECIMALES XX±

ANGLES X±

±

3. SURFACE FINISH

FINIS DE SURFACES

INTERPRETATION/ OF STD D-01-400-001/SG-00

INTERPRÉTER LEVEL/NIVEAU 3


APPLICATION/USAGE

SCALE/ÉCHELLE


ZONE	-	TDAN 914471164/A059	-	-	-	-
LTR LET	-	PRODUCTION RELEASE	01-08-03	S.P.	M.P.	M.F.
REVISION			DATE	DWN DESS	CKD VER	APPVL APP
National Defence			Canada			
DWN/DESS S. PEREIRA			CKD/VER M. FEDORUK			CF APPVL/APP CF DLGSPM
DESIGN AGENT/CONCEPTION 3AF83			NSCM/CAOF 35907			APPVL DATE D'APPROB 01-08-03
TITLE/TITRE			DRAWING NO DU DESSIN			
GROUNDING STRAP			9381496			
ASSY, LONG			SHEET			
			FEUILLE			
			2			
			OF			
			DE			
			2			

Solicitation No. W8476-145074/B	Amd. No. 001	Buyer ID 019qd
Client Ref. No. W8476-145074	File No. 019qdW8476-145074	

Drawing No. 9379540-1



-NO	ITEM NO DE L'ART	IDENTIFYING NO D'IDENTIFICATION	NOMENCLATURE/DESCRIPTION	SPECIFICATION	CODE IDENT CODE D'IDENT
1	1		SHEET, 3.2 THK, RUBBER, BUNA-N, BLACK	NOTE 1	



NOTES:

- 1 MATERIAL SPECIFICATION: ASTM D2000 M5BG 604 A14 B14E034F17
- 2 BAG AND TAG AS PER MIL-STD-129, COLOUR, HEIGHT, METHOD ANY, PART NUMBER 9379540-1.

NOTICE

THE DEPARTMENT OF NATIONAL DEFENCE DOES NOT WARRANT OR GUARANTEE THE CORRECTNESS OR ACCURACY OF THE INFORMATION CONTAINED IN THIS DOCUMENT FOR OTHER THAN OFFICIAL DEFENCE PURPOSES. THE DEPARTMENT OF NATIONAL DEFENCE DOES NOT GRANT ANY LICENSE, CONVEY ANY INTELLECTUAL PROPERTY RIGHTS, OR GIVE PERMISSION FOR ANY USE IN WHOLE OR IN PART BY ANY RECIPIENT, HOLDER OR USER OF THIS DOCUMENT, AND ANY SUCH PERSON USING THIS DOCUMENT OR THE INFORMATION THEREIN DOES SO AT THEIR OWN RISK.

UNLESS OTHERWISE SPECIFIED/SAUF INDICATION CONTRAIRE:
1. DIMENSIONS ARE IN/DIMENSIONS SONT EN mm
2. TOLERANCES
FRACTIONS ±
DECIMALS XXX±
DECIMALES XX±
X± 1.0
ANGLES ±
3. SURFACE FINISH
FINIS DE SURFACES
INTERPRETATION/ OF STD D-01-400-001/SG-000
INTERPRETER LEVEL/NIVEAU 3

APPLICATION/USAGE
COMMON
SCALE/ÉCHELLE 1:1

TDAN 914471164/A059	-	-	-	-
PRODUCTION RELEASE	01-08-03	S.P.	M.P.	M.F.
REVISION	DATE	DWN DESS	CKD VER	APPVL APP
National Defence	Défense nationale	Canada		
DWN/DESS S. PEREIRA	CKD/VER M. FEDORUK	INSPECT/INSPECTE DTICS 3	CF APPVL/APP CF DLCSM	
DESIGN AGENT/CONCEPTION JAF83	NSCM/CAOF 35907	APPVL DATE D'APPROB 01-08-03		A2
TITLE/TITRE GASKET		DRAWING NO DU DESSIN 9379540		
		SHEET FEUILLE 1	OF DE 1	