

RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:
Bid Receiving Public Works and Government
Services Canada/Réception des soumissions Travaux
publics et Services gouvernementaux Canada
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British Columbia
V6Z 0B9
Bid Fax: (604) 775-9381

SOLICITATION AMENDMENT
MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise
indicated, all other terms and conditions of the Solicitation
remain the same.

Ce document est par la présente révisé; sauf indication contraire,
les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Public Works and Government Services Canada -
Pacific Region
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British C
V6Z 0B9

Title - Sujet Penstock & Cylinder Refurbishment	
Solicitation No. - N° de l'invitation EZ108-151488/A	Amendment No. - N° modif. 001
Client Reference No. - N° de référence du client	Date 2014-12-18
GETS Reference No. - N° de référence de SEAG PW-\$PWY-026-7394	
File No. - N° de dossier PWY-4-37231 (026)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2014-12-29	Time Zone Fuseau horaire Pacific Standard Time PST
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Liu (PWY), Patty	Buyer Id - Id de l'acheteur pwy026
Telephone No. - N° de téléphone (604) 775-6227 ()	FAX No. - N° de FAX (604) 775-6633
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction: PWGSC - Esquimalt Graving Dock - Victoria, BC	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Solicitation No. - N° de l'invitation

EZ108-151488/A

Client Ref. No. - N° de réf. du client

Amd. No. - N° de la modif.

001

File No. - N° du dossier

PWY-4-37231

Buyer ID - Id de l'acheteur

pw026

CCC No./N° CCC - FMS No/ N° VME

Les documents français seront disponibles sur demande.

Amendment 001 has been raised to incorporate questions and answers from the site visit.

*Please note: The closing date cannot be extended at this time as the physical site work is scheduled in between vessel movements (due to the direct affect this work has on the watering/de-watering of the drydock). This is why the schedule wording in the specifications is quite detailed.

All other terms and conditions remain unchanged.

Solicitation No.: EZ108-151488/A

Penstock and Cylinder Refurbishment

Esquimalt Graving Dock

Tender Site Visit December 17, 2014 1030hrs

Questions and Responses from Tender Site Visit

Q: Is there mechanical ventilation in the tunnels? Who determines if ventilation is required?

A: There is no existing mechanical ventilation in any of the watering/de-watering tunnels. Tunnels have limited passive ventilation.

A: The contractor may be required to provide mechanical ventilation based on the contractor's initial air quality testing performed by the contractor following all applicable health and safety regulations and requirements. Refer to Section 013533.

Q: Are there confined space services available on site?

A: There are no confined space services available on site. Local ship repair firms may have confined space services available and the contractor should make their own inquiries to what services are available to contract.

Q: Who is responsible for water management within the tunnels?

A: The contractor is responsible for water management within the tunnels. Refer to Section 011155.

Q: Is power available on site?

A: Power may be obtained on site for the contractor's use. Refer to Section 015100.

Q: What is the capacity of cranes available for use on site? Does the crane come with an operator? Is the contractor responsible for rigging?

A: Various, depending on type of equipment. Rail mounted cranes on the north side of the drydock are 30T and 150T capacity. Rail mounted cranes can access anything within the specified work area. Refer to Appendix E Schedule of Dock Charges for equipment available on site.

A: All cranes come with an operator. Cranes also may come with an EGD spotter depending on EGD operational requirements. This does not relieve the contractor from their obligation to provide qualified spotter(s) as necessary for all of their lifts per the specification. Refer to Section 15100.

A: Yes, the contractor is responsible for all rigging and associated equipment below the hook necessary to perform lifts. Refer to Section 15100.

Q: Where is the water in the tunnels able to be pumped to?

A: The existing storm water system located within the contractor's work area can be used to discharge water into. Refer to Section 011155.

Q: What is the requirement for cylinder shaft smoothness?

A: *Refer to Section 210501.01 for requirements.*