Room A
Paint floor.
Paint Walls and Ceiling including mecanical and electrical.
Remove Electrical for cart chargers.
New electrical for Mobile shelving.
2 new doors and block access between room A and Room B
Secure ventilation opening to prevent access

Room B
Paint floor.
Paint Walls and Ceiling including mecanical and electrical.
2 new doors and block access between room A and Room B

Room C
Remove Door between room C and Room D
Remove plywood and Inslall blocks between Room C and B
where a doorway used to be,

Room D
Remove Door between room C and Room D
Paint floor
Paint Walls and Ceilling including mecanical and electrical
Raise low light fixtures to be same as the rest of the room
New carpet in two areas
3 New 120V 20A, additional electrical and conduit to run
dedicated outlets for buisness center

Meeting Room and storage room
Paint walls
New Carpet
If needed modify HVAC for a 20 person boardroom
Modernize lighting for AV applications
New power and communications to reach unde the table via
conectrac system
Add Film to window to prevent outside existing security
camera view of inside.

Kitchen
New Cabinets
Paint walls
New Flooring
New electrical for Kitchen application

Other Notes
Recommendations for adequate fire protection
Replace Damaged Ceiling Tiles
Install modern electrical outlets and switches
Paint Hallway walls and ceiling.
Buff and re-wax floors in Hallways
Furniture purchased by other
Shelving purchased and installed by other
Repair walls were necessary to maintain proper security level
as indicated on the plan
Supply and Install carpet in specified areas as well as within
the mobile shelving units

The Electrical details for the shelving unit will follow shortly

Existing Mobile 158 Bays
Mobile From 9West, 5W, 17East
and new approx 642 Bays
Total Approx 800 Bays



Before