

Part 1 General

1.1 RELATED REQUIREMENTS

- .1 The list of work sections in this division is indicative and non-exhaustive. It does not exclude the works described in the other specification sections, shown in the drawings or necessary for the execution of the works in keeping with overall intent of the plans.
- .2 Section 01 35 00.06 - Special Procedures for Traffic Control.

1.2 REFERENCES

- .1 Canadian General Standards Board (CGSB)
 - .1 CAN/CGSB-15.1-92, Calcium Chloride.
- .2 U.S. Environmental Protection Agency (EPA)/Office of Water
 - .1 EPA 832/R-92-005, Storm Water Management for Construction Activities :
Developing Pollution Prevention Plans and Best Management Practices.

1.3 INFORMATIONAL/ACTION SUBMITTALS

- .1 Submit submittals and data sheets in accordance with Section 01 33 00 – Submittal Procedures.

Part 2 Products

2.1 MATERIALS

- .1 Water : subject to Departmental Representative's approval.

Part 3 Execution

3.1 PREPARATION

- .1 Temporary erosion and sedimentation control :
 - .1 Use temporary erosion and sedimentation control measures to prevent soil erosion and discharge of soil-bearing water runoff or airborne dust to adjacent properties and walkways, in accordance with requirements of authorities having jurisdiction.

3.2 APPLICATION

- .1 Apply water using approved equipment when directed by the Departmental Representative.

- .2 Apply water with sprayer system equipped with shut-off device, ensuring uniform application.

3.3 CLEAN UP

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion, remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.

END OF SECTION