

**CORRECTIONAL SERVICE
CANADA**

**BOWDEN INSTITUTION
INNISFAIL, ALBERTA**

ELECTRICAL SUBSTATION SECONDARY TANK COMPLIANCE


Drawn by **C. McGEE** Dessiné par

PWGSC Project Manager Administrateur de Projets TPSG
S. PHYPERS

FENCE DISPLACEMENT DETAILS

Project no./No. du projet	Drawing no./No. du dessin	Revision no.
R.072042.001	S3 OF 3	00


1 EXISTING FENCEPOST, GATE, AND FENCING TO BE TEMPORARILY REMOVED TO ALLOW FOR SUFFICIENT CLEARANCE TO TRANSPORT ST-1 INTO ROOM 101. FENCEPOST, GATE, AND ASSOCIATED FENCING TO BE REINSTITATED UPON COMPLETION OF WORK.




3 FENCEPOST DISPLACEMENT LOCATION
S3 SCALE: NONE

1.	ALL POSTS AND FRAME MEMBERS ARE SCHEDULE 40, REGULAR GRADE, STEEL PIPE.
2.	THE ACTUAL WEIGHT SHALL NOT VARY BY MORE THAN 10% OF THE NOMINAL WEIGHT.

1.	REMOVE EXISTING GATE FROM FENCEPOST TO BE REMOVED.
2.	EXCAVATE EXISTING FENCEPOST FROM CONCRETE BASE.
3.	ROLL BACK EXISTING FENCE SEGMENT AS REQUIRED TO FACILITATE TRANSFER OF NEW TANK ST-1 INTO ROOM 101. TRANSFER OF TANK TO BE DONE BY DIVISION 23.
4.	INSTALL NEW TANK ST-1 IN ROOM 101. INSTALLATION WORK TO BE DONE BY DIVISION 23.
5.	REINSTALL FENCEPOST AND POUR NEW CONCRETE BASE AS SHOWN ON DETAIL 1.
6.	REATTACH FENCE AND GATE TO REINSTALLED FENCEPOST.



1 EXISTING FENCEPOST REINSTATEMENT



2 EXISTING FENCE REINSTATEMENT