

3.13 DAMAGES

- .1 Restore or replace to their original condition existing public and/or privately owned property, structures, finishes, services, and/or utilities damaged during the execution of the work of this contract, or make adequate compensation to affected parties.
- .2 The terms “restore” and “replace” include labour, equipment and material costs.

3.14 CLEAN-UP

- .1 Provide on-site waste containers for collection of waste materials and debris and locate as directed by NCC Representative. Store volatile waste in covered metal containers, and remove from premises at end of each working day.
- .2 At the end of each work period, and more often if directed by the NCC Representative, remove debris from site, neatly stack material for use, and clean up generally. Conduct disposal operations to comply with municipal and site ordinances, anti-pollution laws and as required by the Contract Documents.
- .3 Upon completion, remove temporary protections installed under this contract and remove surplus materials. Make good defects noted at this stage.
- .4 Cleaning during construction
 - .1 Clean-up work area as the work progresses in order to prevent migration of dust and debris.
 - .2 Clean as directed by the NCC Representative.
- .5 Final clean-up
 - .1 For site, broom clean hard landscaped surfaces. Rake clean other landscaped areas. Hose down with water and wash hard landscaped surfaces as directed by NCC Representative.
 - .2 Broom clean all interiors before inspection process.
 - .3 Clean as directed by the NCC Representative.

3.15 SITE SAFETY BARRIERS AND SIGNAGE RELATED TO TEMPORARY ELECTRICAL CABLES

- .1 Provide 4 precast concrete security barriers (jersey barriers) approximately 613mm wide x 2135mm long x 800mm high at the manhole in road where temporary electrical splice shall be done. Position security barriers to create 4 sided perimeter around manhole. Provide 4 sided plywood hoarding within security barrier perimeter and fully around manhole. Hoarding shall be 2440mm high self-supporting plywood faced wood framed structure complete with hinged access door with hasp and padlock to prevent unauthorized access to manhole. Paint finish (single colour selected by NCC Representative) on exposed to sight plywood surfaces. Provide reflective warning signage on east and west sides of hoarding to alert motorists to barriers in road. Remove security barriers and hoarding at completion of work.
- .2 Provide 2 self-supporting reflective signs to east and west side of electrical cables and ramps where cables cross road in order to warn motorists and pedestrians of bump and trip hazard. Remove at completion of the work.
- .3 Provide 2 self-supporting reflective signs to east and west side of electrical cables and ramps where cables cross sidewalk in order to warn pedestrians of trip hazard. Remove at the completion of the work.

END OF SECTION