





## GROUND LEVEL FLOOR PLAN - COMMUNICATIONS




GROUND LEVEL FLOOR PLAN - FIRE ALARM



GROUND LEVEL FLOOR PLAN - SECURITY



FLOORPLAN - TELECOM RM.



GROUND

DEMOLITION NOTES:

**COMMUNICATION:**

1. DISCONNECT AND REMOVE ALL VOICE AND DATA CABLE, FROM EXISTING OUTLETS, BACK TO PATCH PANELS IN TELECOM ROOM AR-631 WITH THE FOLLOWING EXCEPTION:
  - 1.1. BOARDROOM AR-634, ALL COMMUNICATIONS OUTLETS ARE TO REMAIN.
  2. REMOVE CABLES FROM PATCH PANEL AND COIL NEATLY. DISPOSITION OF CABLES BY SHARED SERVICES CANADA (SSC).
  3. REMOVE ALL EXCESS COMMUNICATIONS CABLE COILED IN CEILING SPACE BACK TO TELECOM ROOM AR-631. COIL EXCESS CABLES NEATLY. DISPOSITION OF CABLES BY SHARED SERVICES CANADA (SSC).
  4. REMOVE ALL VOICE AND DATA OUTLETS, FACEPLATES AND JACKS. DISPOSITION OF FACEPLATES AND JACKS BY SHARED SERVICES CANADA (SSC).
  5. DISPOSITION OF ALL EXISTING VOICE/DATA EQUIPMENT IN ROOM AR-631 & AR-632 BY SHARED SERVICES CANADA (SSC).
  6. ALL UNDER SLAB COMMUNICATION CONDUITS TO REMAIN.
  7. EXISTING DFO AND PWSC NETWORK FIBRE CONNECTION IS TO REMAIN UNTIL DURING AND AT THE END OF DEMOLITION. COORDINATE WITH PWSC AND DFO IT PERSONNEL.

FIRE ALARM:

1. DISCONNECT AND REMOVE ALL FIRE ALARM DEVICES AND ALL ASSOCIATED WIRING AND CONDUIT BACK TO MAIN FIRE ALARM PANEL.
- SECURITY:**
1. DISCONNECT AND REMOVE ALL SECURITY DEVICES AND ALL ASSOCIATED WIRING AND CONDUIT BACK TO MAIN SECURITY PANEL.

SECURITY:

1. DISCONNECT AND REMOVE ALL SECURITY DEVICES AND WIRING AND CONDUIT BACK TO MAIN SECURITY PANEL.