

ARGO BUILDING GROUND LEVEL EXISTING HEATING

SCALE : 1:100

0m 1m 2m 3m 4m 5m 6m 7m 8m 9m 10m

HEATING LEGEND:

EXISTING HEATING SUPPLY RADIATOR TO REMAIN

REMOVE EXISTING HEATING SUPPLY RADIATOR

HEATING NOTES:

1. PERIMETER RADIATORS AND UNIT HEATER TO REMAIN.
2. ALL EXISTING HEATING MECHANICAL EQUIPMENT, PIPING AND CONTROL WIRING TO AHU UNITS, HEATING COILS, MINI SPLITS AND FAN COILS HEATERS TO BE REMOVED.
3. EXISTING PIPING IN EXISTING MECHANICAL/SPRINKLER ROOM NOT TO BE REMOVE.
4. ALL EXISTING THERMOSTATS AND EXISTING CONTROL WIRING TO BE REMAIN, HANG FROM CEILING IN AREAS WHERE WALLS ARE REMOVED.
5. ALL MECHANICAL OPENINGS IN OUTSIDE WALLS AND ROOF OPENINGS TO BE REPAIRED AND WEATHERTIGHT.



EXISTING HEATING SYSTEM SCHEMATIC IN MECHANICAL/SPRINKER ROOM DO NOT REMOVE

N.T.S.



ARGO BUILDING GROUND LEVEL EXISTING VENTILATION

SCALE : 1:100

0m 1m 2m 3m 4m 5m 6m 7m 8m 9m 10m

HVAC LEGEND:

REMOVE EXISTING SUPPLY AND RETURN DUCTWORK

REMOVE EXISTING SUPPLY AND RETURN DUCTWORK

REMOVE EXISTING SUPPLY DIFFUSERS

REMOVE EXISTING RETURN AIR GRILLES

HVAC NOTES:

1. ALL EXISTING SUPPLY AND RETURN DUCTWORK TO BE REMOVED.
2. ALL EXISTING EXHAUST DUCTWORK, FANS EXHAUST GRILLES AND CONTROLS WIRING TO BE REMOVED, OUTSIDE WALLS OPENINGS AND ROOF OPENINGS REPAIRED AND WEATHERTIGHT.
3. ALL EXISTING SUPPLY DIFFUSERS AND RETURN AIR GRILLES TO BE REMOVED.
4. ALL EXISTING MECHANICAL EQUIPMENT,PIPING AND CONTROLS WIRING TO AHU UNITS, HEATING COILS, MINI SPLITS AND FAN COILS HEATERS TO BE REMOVED.
5. PIPING IN EXISTING MECHANICAL/SPRINKLER ROOM NOT TO REMOVE.
6. ALL EXISTING THERMOSTATS AND EXISTING CONTROL WIRING TO BE REMAIN, HANG FROM CEILING IN AREAS WHERE WALLS ARE REMOVED.
7. ALL MECHANICAL OPENINGS IN OUTSIDE WALLS AND ROOF OPENINGS TO BE REPAIRED AND WEATHERTIGHT.

Public Works and Government Services Canada / Travaux Publics et Services gouvernementaux Canada



PARTIAL B.I.O. SITE MAP
N.T.S.

0	ISSUED FOR TENDER	JAN. 16 2015
revisions		date

project / projet

ARGO BUILDING
BEDFORD INSTITUTE OF OCEANOGRAPHY
DARTMOUTH, NS

drawing / dessin

DEMOLITION
EXISTING HEATING AND VENTILATION
FLOOR PLANS

designed / conçu: F.A.M. — date: 2015-01
drawn / dessiné: F.A.M. — date: 2015-01
approved / approuvé — date
Tender / Soumission
PWGSC Project Manager / Administrateur de projets TPSGC

project number / no. du projet: R.069793.001

drawing no. / no. du dessin: H2 OF 2

E-DRM/GDD-E: 508077