



- NOTES:**
- REMOVALS.**
- REMOVE ANY / ALL CEILING MOUNTED / HUNG EQUIPMENT, SOUND BATT'S, ART PIECES, SUSPENDED MOBILES, ETC. AND STORE SAFE AND SECURE IN A CLEAN, DRY LOCATION READY FOR RE-INSTALLATION UPON COMPLETION OF WORK.
 - DISASSEMBLE SUSPENDED ACOUSTIC CEILING TILE ASSEMBLY. DO NOT BEND OR BREAK ANY ALUMINUM GRID COMPONENTS NOR LOSE ANY CONNECTING / MOUNTING HARDWARE PIECES. DO NOT LOSE OR DAMAGE ANY ACOUSTIC CEILING TILES. STORE ALL COMPONENTS SAFE AND SECURE IN A CLEAN, DRY LOCATION READY FOR RE-INSTALLATION UPON COMPLETION OF WORK.
 - CLEANLY CUT GYPSUM BOARD FINISH TO THE MINIMUM EXTENT SUFFICIENT TO PROVIDE UNOBSTRUCTED ACCESS TO STRUCTURAL MEMBERS TO BE REINFORCED, AS PER THE STRUCTURAL DRAWINGS. ENSURE MINIMUM DAMAGE TO METAL FRAMING / FURRING IN AFFECTED AREA AND ADJACENT. REPAIR / REPLACE ANY DAMAGED FRAMING MEMBERS TO RESTORE ORIGINAL CONSTRUCTION. PROVIDE NEW GYPSUM BOARD AND PAINT FINISH.
 - REMOVE / DEMOLISH GYPSUM BOARD. ENSURE MINIMUM DAMAGE TO METAL FRAMING / FURRING IN AFFECTED AREA AND ADJACENT. REPAIR / REPLACE ANY DAMAGED FRAMING MEMBERS TO RESTORE ORIGINAL CONSTRUCTION. PROVIDE NEW GYPSUM BOARD AND PAINT FINISH.

Public Works and Government Services Canada / Travaux Publics et Services gouvernementaux Canada

DFS architecture & design INC.

Saint John, NB / Saint John, New Brunswick E2L 2B2
Montréal, QC / Montréal, Québec H2T 1A4
T: (506) 634-8377 F: (506) 632-1741
www.dfsarch.com

key plan

94087
CERTIFICATE of PRACTICE
Richard R. Gradon
DFS INC.
ARCHITECTS ASSOCIATION of NEW BRUNSWICK

0	ISSUED FOR TENDER	01/20 2014
revisions		date
project	project	
CAMPUS ROOF REPLACEMENT CANADIAN COAST GUARD COLLEGE SYDNEY, NS		
drawing	design	
CABOT BUILDING PARTIAL REFLECTED CEILING PLANS - LEVEL 100, 200 AND 300		
designed RG	conçu	
date		
drawn BG, WC	dessiné	
date		
approved	approuvé	
date		
Tender	Soumission	
PWGC Project Manager	Administrateur de projets TP50C	
project number	no. du projet	
R.065476.500		
drawing no.	no. du dessin	
A6.1		

E-DRM/GDD-E: