

Part 1 General**1.1 DEFINITIONS**

- .1 For additional acronyms and definitions refer to Section 25 05 01 - EMCS: General Requirements.
- .2 AEL: ratio between total test period less any system downtime accumulated within that period and test period.
- .3 Downtime: results whenever EMCS is unable to fulfill required functions due to malfunction of equipment defined under responsibility of EMCS contractor. Downtime is measured by duration, in time, between time that Contractor is notified of failure and time system is restored to proper operating condition. Downtime not to include following:
 - .1 Outage of main power supply in excess of back-up power sources, provided that:
 - .1 Automatic initiation of back-up was accomplished.
 - .2 Automatic shut-down and re-start of components was as specified.
 - .2 Failure of communications link, provided that:
 - .1 Controller automatically and correctly operated in stand-alone mode.
 - .2 Failure was not due to failure of any specified EMCS equipment.
 - .3 Functional failure resulting from individual sensor inputs or output devices, provided that:
 - .1 System recorded said fault.
 - .2 Equipment defaulted to fail-safe mode.
 - .3 AEL of total of all input sensors and output devices is at least 99 ____ % during test period.

1.2 DESIGN REQUIREMENTS

- .1 Confirm with Consultant that Design Criteria and Design Intent are still applicable.
- .2 Commissioning personnel to be fully aware of and qualified to interpret Design Criteria and Design Intent.

1.3 SUBMITTALS

- .1 Submittals in accordance with Section 01330 - Submittal Procedures.
- .2 Final Report: submit report to Consultant.
 - .1 Include measurements, final settings and certified test results.
 - .2 Bear signature of commissioning technician and supervisor
 - .3 Report format to be approved by Consultant before commissioning is started.
 - .4 Revise "as-built" documentation, commissioning reports to reflect changes, adjustments and modifications to EMCS as set during commissioning and submit to Consultant in accordance with Section 01 78 00 - Closeout Submittals.

- .5 Recommend additional changes and/or modifications deemed advisable in order to improve performance, environmental conditions or energy consumption.

1.4 CLOSEOUT SUBMITTALS

- .1 Provide documentation, O&M Manuals, and training of O&M personnel for review of Consultant before interim acceptance in accordance with Section 01 78 00 - Closeout Submittals.

1.5 COMMISSIONING

- .1 Do commissioning in accordance with Section 01 91 13 - General Commissioning (Cx) Requirements.
- .2 Carry out commissioning under direction Consultant and in presence of Departmental Representative.
- .3 Inform, and obtain approval from, Departmental Representative and Consultant in writing at least 14 days prior to commissioning or each test. Indicate:
 - .1 Location and part of system to be tested or commissioned.
 - .2 Testing/commissioning procedures, anticipated results.
 - .3 Names of testing/commissioning personnel.
- .4 Correct deficiencies, re-test in presence of Departmental Representative until satisfactory performance is obtained.
- .5 Acceptance of tests will not relieve Contractor from responsibility for ensuring that complete systems meet every requirement of Contract.
- .6 Load system with project software.
- .7 Perform tests as required.

1.6 COMPLETION OF COMMISSIONING

- .1 Commissioning to be considered as satisfactorily completed when objectives of commissioning have been achieved and reviewed by Consultant.

1.7 ISSUANCE OF FINAL CERTIFICATE OF COMPLETION

- .1 Final Certificate of Completion will not be issued until receipt of written approval indicating successful completion of specified commissioning activities including receipt of commissioning documentation.

Part 2 Products

2.1 EQUIPMENT

- .1 Provide sufficient instrumentation to verify and commission the installed system. Provide two-way radios.

- .2 Instrumentation accuracy tolerances : higher order of magnitude than equipment or system being tested.
- .3 Independent testing laboratory to certify test equipment as accurate to within approved tolerances no more than 2 months prior to tests.
- .4 Locations to be approved, readily accessible and readable.
- .5 Application: to conform to normal industry standards.

Part 3 Execution

3.1 PROCEDURES

- .1 Test each system independently and then in unison with other related systems.
- .2 Commission each system using procedures prescribed by Consultant.
- .3 Commission integrated systems using procedures prescribed by Consultant.
- .4 Debug system software.
- .5 Optimize operation and performance of systems by fine-tuning PID values and modifying CDLs as required.
- .6 Test full scale emergency evacuation and life safety procedures including operation and integrity of smoke management systems under normal and emergency power conditions as applicable.

3.2 FIELD QUALITY CONTROL

- .1 Completion Testing.
 - .1 General: test after installation of each part of system and after completion of mechanical and electrical hook-ups, to verify correct installation and functioning.
 - .2 Include following activities:
 - .1 Test and calibrate field hardware including stand-alone capability of each controller.
 - .2 Verify each A-to-D convertor.
 - .3 Test and calibrate each AI using calibrated digital instruments.
 - .4 Test each DI to ensure proper settings and switching contacts.
 - .5 Test each DO to ensure proper operation and lag time.
 - .6 Test each AO to ensure proper operation of controlled devices. Verify tight closure and signals.
 - .7 Test operating software.
 - .8 Test application software and provide samples of logs and commands.
 - .9 Verify each CDL including energy optimization programs.
 - .10 Debug software.

- .11 Provide point verification list in table format including point identifier, point identifier expansion, point type and address, low and high limits and engineering units. Include space on document for commissioning technician and Consultant initializing.
- .3 Final Operational Testing: to demonstrate that EMCS functions in accordance with contract requirements.
 - .1 Prior to beginning of 30 day test demonstrate that operating parameters (setpoints, alarm limits, operating control software, sequences of operation, trends, graphics and CDL's) have been implemented to ensure proper operation and operator notification in event of off-normal operation.
 - .1 Repetitive alarm conditions to be resolved to minimize reporting of nuisance conditions.
 - .2 Test to last at least 30 consecutive 24 hour days.
 - .3 Tests to include:
 - .1 Demonstration of correct operation of monitored and controlled points.
 - .2 Operation and capabilities of sequences, reports, special control algorithms, diagnostics, software.
 - .4 System will be accepted when:
 - .1 EMCS equipment operates to meet overall performance requirements. Downtime as defined in this Section must not exceed allowable time calculated for this site.
 - .2 Requirements of Contract have been met.
 - .5 In event of failure to attain specified AEL during test period, extend test period on day-to-day basis until specified AEL is attained for test period.
 - .6 Correct defects when they occur and before resuming tests.
- .4 Consultant to verify reported results.

3.3

DEMONSTRATION

- .1 Demonstrate to Consultant operation of systems including sequence of operations in regular and emergency modes, under normal and emergency conditions, start-up, shut-down interlocks and lock-outs in accordance with Section 01 79 00 - Demonstration and Training.

END OF SECTION

Part 1 General

1.1 DEFINITIONS

- .1 CDL - Control Description Logic.
- .2 For additional acronyms and definitions refer to Section 25 05 01 - EMCS: General Requirements.

1.2 SUBMITTALS

- .1 Submittals in accordance with Section 01 33 00 - Submittal Procedures, supplemented and modified by requirements of this Section.
- .2 Submit training proposal complete with hour-by-hour schedule including brief overview of content of each segment to Departmental Representative and Consultant 30 days prior to anticipated date of beginning of training.
 - .1 List name of trainer, and type of visual and audio aids to be used.
 - .2 Show co-ordinated interface with other EMCS mechanical and electrical training programs.
- .3 Submit reports within one week after completion of training program that training has been satisfactorily completed.

1.3 QUALITY ASSURANCE

- .1 Provide bilingual, ____ competent instructors thoroughly familiar with aspects of EMCS installed in facility.
- .2 Departmental Representative and Consultant reserves right to approve instructors.

1.4 INSTRUCTIONS

- .1 Provide instruction to designated personnel in adjustment, operation, maintenance and pertinent safety requirements of EMCS installed.
- .2 Training to be project-specific.

1.5 TIME FOR INSTRUCTION

- .1 Number of days of instruction to be as specified in this section (1 day = 8 hours including two 15 minute breaks and excluding lunch time).

1.6 TRAINING MATERIALS

- .1 Provide equipment, visual and audio aids, and materials for classroom training.
- .2 Supply manual for each trainee, describing in detail data included in each training program.
 - .1 Review contents of manual in detail to explain aspects of operation and maintenance (O&M).

1.7 TRAINING PROGRAM

- .1 To be in a single (1) phase.
- .2 Phase 1: 1 day program to begin before 30 day test period at time mutually agreeable to Contractor, Departmental Representative and Consultant.
 - .1 Train O&M personnel in functional operations and procedures to be employed for system operation.
 - .2 Supplement with on-the-job training during 30 day test period.
 - .3 Include overview of system architecture, communications, operation of computer and peripherals, report generation, trouble shooting and prevention maintenance of EMCS components, maintenance and calibration of sensors and controls.
 - .4 Include detailed training on operator interface functions for control of mechanical systems, CDL's for each system, and elementary preventive maintenance.

1.8 ADDITIONAL TRAINING

- .1 List courses offered by name, duration and approximate cost per person per week. Note courses recommended for training supervisory personnel.

1.9 MONITORING OF TRAINING

- .1 Consultant to monitor training program and may modify schedule and content.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 American National Standards Institute (ANSI)/The Instrumentation, Systems and Automation Society (ISA).
 - .1 ANSI/ISA 5.5-1985, Graphic Symbols for Process Displays.
- .2 American National Standards Institute (ANSI)/ Institute of Electrical and Electronics Engineers (IEEE).
 - .1 ANSI/IEEE 260.1-1993, American National Standard Letter Symbols Units of Measurement (SI Units, Customary Inch-Pound Units, and Certain Other Units).
- .3 American Society of Heating, Refrigerating and Air-Conditioning Engineers, Inc. (ASHRAE).
 - .1 ASHRAE STD 135-R2001, BACNET - Data Communication Protocol for Building Automation and Control Network.
- .4 Canadian Standards Association (CSA International).
 - .1 CAN/CSA-Z234.1-89(R1995), Canadian Metric Practice Guide.
- .5 Consumer Electronics Association (CEA).
 - .1 CEA-709.1-B-2002, Control Network Protocol Specification.
- .6 Department of Justice Canada (Jus).
 - .1 Canadian Environmental Assessment Act (CEAA), 1995, c. 37.
 - .2 Canadian Environmental Protection Act (CEPA), 1999, c. 33.
- .7 Electrical and Electronic Manufacturers Association (EEMAC).
 - .1 EEMAC 2Y-1-1958, Light Gray Colour for Indoor Switch Gear.
- .8 Health Canada/Workplace Hazardous Materials Information System (WHMIS).
 - .1 Material Safety Data Sheets (MSDS).
- .9 Transport Canada (TC).
 - .1 Transportation of Dangerous Goods Act (TDGA), 1992, c. 34.

1.2 ACRONYMS AND ABBREVIATIONS

- .1 Acronyms used in EMCS:
 - .1 AEL - Average Effectiveness Level.
 - .2 AI - Analog Input.
 - .3 AIT - Agreement on International Trade.
 - .4 AO - Analog Output.
 - .5 BACnet - Building Automation and Control Network.
 - .6 BC(s) - Building Controller(s).

- .7 BECC - Building Environmental Control Center.
- .8 CAD - Computer Aided Design.
- .9 CDL - Control Description Logic.
- .10 CDS - Control Design Schematic.
- .11 COSV - Change of State or Value.
- .12 CPU - Central Processing Unit.
- .13 DI - Digital Input.
- .14 DO - Digital Output.
- .15 DP - Differential Pressure.
- .16 ECU - Equipment Control Unit.
- .17 EMCS - Energy Monitoring and Control System.
- .18 HVAC - Heating, Ventilation, Air Conditioning.
- .19 IDE - Interface Device Equipment.
- .20 I/O - Input/Output.
- .21 ISA - Industry Standard Architecture.
- .22 LAN - Local Area Network.
- .23 LCU - Local Control Unit.
- .24 MCU - Master Control Unit.
- .25 NAFTA - North American Free Trade Agreement.
- .26 NC - Normally Closed.
- .27 NO - Normally Open.
- .28 OS - Operating System.
- .29 O&M - Operation and Maintenance.
- .30 OWS - Operator Work Station.
- .31 PC - Personal Computer.
- .32 PCI - Peripheral Control Interface.
- .33 PCMCIA - Personal Computer Micro-Card Interface Adapter.
- .34 PID - Proportional, Integral and Derivative.
- .35 RAM - Random Access Memory.
- .36 SP - Static Pressure.
- .37 ROM - Read Only Memory.
- .38 TCU - Terminal Control Unit.
- .39 USB - Universal Serial Bus.
- .40 UPS - Uninterruptible Power Supply.
- .41 VAV - Variable Air Volume.

1.3 DEFINITIONS

- .1 Point: may be logical or physical.
 - .1 Logical points: values calculated by system such as setpoints, totals, counts, derived corrections and may include, but not limited to result of and statements in CDL's.

- .2 Physical points: inputs or outputs which have hardware wired to controllers which are measuring physical properties, or providing status conditions of contacts or relays which provide interaction with related equipment (stop, start) and valve or damper actuators.
- .2 Point Name: composed of two parts, point identifier and point expansion.
 - .1 Point identifier: comprised of three descriptors, "area" descriptor, "system" descriptor and "point" descriptor, for which database to provide 25 character field for each point identifier. "System" is system that point is located on.
 - .1 Area descriptor: building or part of building where point is located.
 - .2 System descriptor: system that point is located on.
 - .3 Point descriptor: physical or logical point description. For point identifier "area", "system" and "point" will be shortforms or acronyms. Database must provide 25 character field for each point identifier.
 - .2 Point expansion: comprised of three fields, one for each descriptor. Expanded form of shortform or acronym used in "area", "system" and "point" descriptors is placed into appropriate point expansion field. Database must provide 32 character field for each point expansion.
 - .3 Bilingual systems to include additional point identifier expansion fields of equal capacity for each point name for second language.
 - .1 System to support use of numbers and readable characters including blanks, periods or underscores to enhance user readability for each of the above strings.
- .3 Point Object Type: points fall into following object types:
 - .1 AI (analog input).
 - .2 AO (analog output).
 - .3 DI (digital input).
 - .4 DO (digital output).
 - .5 Pulse inputs.
- .4 Symbols and engineering unit abbreviations utilized in displays: to ANSI/ISA S5.5.
 - .1 Printouts: to ANSI/IEEE 260.1.
 - .2 Refer also to Section 25 05 54- EMCS: Identification.

1.4 SYSTEM DESCRIPTION

- .1 Refer to control schematics for system architecture.
- .2 Work covered by sections referred to above consists of fully operational EMCS, including, but not limited to, following:
 - .1 Modification/Addition to existing JCI Metasys building controllers.
 - .2 Control devices as listed in I/O point summary tables.
 - .3 Field control devices.
 - .4 Software/Hardware complete with full documentation.
 - .5 Complete operating and maintenance manuals.

- .6 Training of personnel.
- .7 Acceptance tests, technical support during commissioning, full documentation.
- .8 Wiring interface co-ordination of equipment supplied by others.
- .9 Miscellaneous work as specified in these sections and as indicated.
- .3 Design Requirements:
 - .1 Design and provide conduit and wiring linking elements of system.
 - .2 Supply sufficient programmable controllers of types to meet project requirements. Quantity and points contents as reviewed Consultant prior to installation.
 - .3 Location of is the existing EMCS boiler controller.
 - .4 Metric references: in accordance with CAN/CSA Z234.1.
- .4 Language Operating Requirements:
 - .1 Provide English operator selectable access codes.
 - .2 Use non-linguistic symbols for displays on graphic terminals wherever possible. Other information to be in English.
 - .3 Operating system executive: reuse existing JCI Metasys.
 - .4 System manager software: Re-use existing JCI Metasys.
 - .5 Include, in English:
 - .1 Graphic "display" functions, point commands to turn systems on or off, manually override automatic control of specified hardware points. To be in English at specified OWS and to be able to operate one terminal in English and second in French. Point name expansions in both languages.
 - .2 Reporting function such as trend log, trend graphics, alarm report logs, energy report logs, maintenance generated logs.

1.5 SUBMITTALS

- .1 Make submittals in accordance with Section 01 33 00 - Submittal Procedures and 25 05 02 - EMCS: Shop Drawings, Product Data and Review Process.
- .2 Quality Control:
 - .1 Provide equipment and material from manufacturer's regular production, CSA certified, manufactured to standard quoted plus additional specified requirements.
 - .2 Where CSA certified equipment is not available submit such equipment to inspection authorities for special inspection and approval before delivery to site.
 - .3 Submit proof of compliance to specified standards with shop drawings and product data in accordance with Section 25 05 02 - EMCS: Shop Drawings, Product Data and Review Process. Label or listing of specified organization is acceptable evidence.
 - .4 Existing devices intended for re-use: submit test report.

1.6 QUALITY ASSURANCE

- .1 Have local office within 50 km of project staffed by trained personnel capable of providing instruction, routine maintenance and emergency service on systems,

- .2 Have access to local supplies of essential parts and provide 7 year guarantee of availability of spare parts after obsolescence.
- .3 Ensure qualified supervisory personnel continuously direct and monitor Work and attend site meetings.
- .4 Health and Safety:
 - .1 Do construction occupational health and safety in accordance with Section 01 35 29.06 - Health and Safety Requirements.

1.7 DELIVERY, STORAGE AND HANDLING

- .1 Material Delivery Schedule: provide Departmental Representative Engineer Consultant ____ with schedule within 2 ____ weeks after award of Contract.
- .2 Waste Management and Disposal:
 - .1 Separate waste materials for reuse and recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
 - .2 Remove from site and dispose of packaging materials at appropriate recycling facilities.

1.8 EXISTING CONDITIONS - CONTROL COMPONENTS

- .1 Utilize existing control wiring and piping as indicated.
- .2 Re-use field control devices that are usable in their original configuration provided that they conform to applicable codes, standards specifications.
 - .1 Provide for new, properly designed device where re-usability of components is uncertain.
- .3 Inspect and test existing devices intended for re-use within 30 days of award of contract, and prior to installation of new devices.
 - .1 Furnish test report within 40 days of award of contract listing each component to be re-used and indicating whether it is in good order or requires repair by Departmental Representative.
 - .2 Failure to produce test report will constitute acceptance of existing devices by contractor.
- .4 Non-functioning items:
 - .1 Provide with report specification sheets or written functional requirements to support findings.
 - .2 Departmental Representative will repair or replace existing items judged defective yet deemed necessary for EMCS.
- .5 Submit written request for permission to disconnect controls and to obtain equipment downtime before proceeding with Work.
- .6 Assume responsibility for controls to be incorporated into EMCS after written receipt of approval from Consultant.

- .1 Be responsible for items repaired or replaced by Departmental Representative.
- .2 Be responsible for repair costs due to negligence or abuse of equipment.
- .3 Responsibility for existing devices terminates upon final acceptance of EMCS.
- .7 Remove existing controls not re-used or not required. Place in approved storage for disposition as directed.

END OF SECTION

Part 1 General

1.1 DEFINITIONS

- .1 Acronyms and definitions: refer to Section 25 05 01 - EMCS: General Requirements

1.2 DESIGN REQUIREMENTS

- .1 Preliminary Design Review: to contain following contractor and systems information.
 - .1 Location of local office.
 - .2 Description and location of installing and servicing technical staff.
 - .3 Location and qualifications of programming design and programming support staff.
 - .4 List of spare parts.
 - .5 Location of spare parts stock.
 - .6 Names of sub-contractors and site-specific key personnel.
 - .7 Sketch of site-specific system architecture.
 - .8 Specification sheets for each item including memory provided, programming language, speed, type of data transmission.
 - .9 Descriptive brochures.
 - .10 Sample CDL and graphics (systems schematics).
 - .11 Response time for each type of command and report.

1.3 SUBMITTALS

- .1 Submittals in accordance with Section 01 33 00 - Submittal Procedures and coordinate with requirements in this Section.
- .2 Submit preliminary design document within 30 working days after tender closing, for review by Consultant.
- .3 Shop Drawings to consist of 1 hard copies and 1 soft copy of design documents, shop drawings, product data and software.
- .4 Hard copy to be completely indexed and coordinated package to assure compliance with contract requirements and arranged in same sequence as specification and cross-referenced to specification section and paragraph number.
- .5 Soft copy to be in Microsoft Word latest version format, structured using menu format for easy loading and retrieval on OWS.

1.4 SHOP DRAWING REVIEW

- .1 Submit preliminary shop drawings within 60 working days of award of contract and include following:
 - .1 Specification sheets for each item. To include manufacturer's descriptive literature, manufacturer's installation recommendations, specifications, drawings,

- diagrams, performance and characteristic curves, catalogue cuts, manufacturer's name, trade name, catalogue or model number, nameplate data, size, layout, dimensions, capacity, other data to establish compliance.
- .2 Detailed system architecture showing all points associated with each controller including network and signal levels, where new EMCS ties into existing control equipment.
- .3 Spare point capacity of each controller by number and type.
- .4 Controller locations.
- .5 Auxiliary control cabinet locations.
- .6 Single line diagrams showing cable routings, conduit sizes, spare conduit capacity between control centre, field controllers and systems being controlled.
- .7 Interface wiring diagrams showing termination connections and signal levels for equipment to be supplied by others.
- .8 Shop drawings for each input/output point, sensors, transmitters, showing information associated with each particular point including:
 - .1 Sensing element type and location.
 - .2 Transmitter type and range.
 - .3 Associated field wiring schematics, schedules and terminations.
 - .4 Complete Point Name Lists.
 - .5 Software and programming details associated with each point.
 - .6 Manufacturer's recommended installation instructions and procedures.
 - .7 Input and output signal levels or pressures where new system ties into existing control equipment.
- .9 Control schematics, narrative description, CDL's fully showing and describing automatic and manual procedure required to achieve proper operation of project, including under complete failure of EMCS.
- .10 Graphic system schematic displays of water systems with point identifiers and textual description of system, as specified.
- .11 Sample of "Operating Instructions Manual" to be used for training purposes.
- .12 Outline of proposed start-up and verification procedures. Refer to Section [25 01 11 - EMCS: Start-up, Verification and Commissioning].

1.5 QUALITY ASSURANCE

- .1 Preliminary Design Review Meeting: Convene meeting within 45 working days of award of contract to:
 - .1 Undertake functional review of preliminary design documents, resolve inconsistencies.
 - .2 Resolve conflicts between contract document requirements and actual items (e.g.: points list inconsistencies).
 - .3 Review interface requirements of materials supplied by others.
 - .4 Review "Sequence of Operations".
- .2 Contractor's programmer to attend meeting.

- .3 Consultant retains right to revise sequence or subsequent CDL prior to software finalization without cost to Departmental Representative.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 DEFINITIONS

- .1 BECC - Building Environmental Control Centre.
- .2 OWS - Operator Work Station.
- .3 For additional acryonyms and definitions refer to Section 25 05 01 - EMCS: General Requirements.

1.2 SUBMITTALS

- .1 Submittals in accordance with Section 01 78 00 - Closeout Procedures, supplemented and modified by requirements of this Section.
- .2 Submit As-built drawings and Operation and Maintenance Manual to Consultant in English.
- .3 Provide soft copies and hard copies in hard-back, 50 mm 3 ring, D-ring binder.
 - .1 Binders to be 2/3 maximum full.
 - .2 Provide index to full volume in each binder.
 - .3 Identify contents of each manual on cover and spine.
 - .4 Provide Table of Contents in each manual.
 - .5 Assemble each manual to conform to Table of Contents with tab sheets placed before instructions covering subject.

1.3 AS-BUILTS

- .1 Provide 1 copy of detailed shop drawings generated in Section 25 05 02 - EMCS: Submittals and Review Process and include:
 - .1 Changes to contract documents as well as addenda and contract extras.
 - .2 Changes to interface wiring.
 - .3 Routing of conduit, wiring and control air lines associated with EMCS installation.
 - .4 Locations of obscure devices to be indicated on drawings.
 - .5 Listing of alarm messages.
 - .6 Panel/circuit breaker number for sources of normal/emergency power.
 - .7 Names, addresses, telephone numbers of each sub-contractor having installed equipment, local representative for each item of equipment, each system.
 - .8 Test procedures and reports: provide records of start-up procedures, test procedures, checkout tests and final commissioning reports as specified in Section 25 01 11 - EMCS: Start-up, Verification and Commissioning.
 - .9 Basic system design and full documentation on system configuration.
- .2 Submit for final review by Consultant.

- .3 Provide before acceptance 1 Hard and 1 soft copy incorporating changes made during final review.

1.4 O&M MANUALS

- .1 Custom design O&M Manuals (both hard and soft copy) to contain material pertinent to this project only, and to provide full and complete coverage of subjects referred to in this Section.
- .2 Provide 2 complete sets of hard and soft copies prior to system or equipment tests
- .3 Include complete coverage in concise language, readily understood by operating personnel using common terminology of functional and operational requirements of system. Do not presume knowledge of computers, electronics or in-depth control theory.
- .4 Functional description to include:
 - .1 Functional description of theory of operation.
 - .2 Design philosophy.
 - .3 Specific functions of design philosophy and system.
 - .4 Full details of data communications, including data types and formats, data processing and disposition data link components, interfaces and operator tests or self-test of data link integrity.
 - .5 Explicit description of hardware and software functions, interfaces and requirements for components in functions and operating modes.
 - .6 Description of person-machine interactions required to supplement system description, known or established constraints on system operation, operating procedures currently implemented or planned for implementation in automatic mode.
- .5 System operation to include:
 - .1 Complete step-by-step procedures for operation of system including required actions at each OWS.
 - .2 Operation of computer peripherals, input and output formats.
 - .3 Emergency, alarm and failure recovery.
 - .4 Step-by-step instructions for start-up, back-up equipment operation, execution of systems functions and operating modes, including key strokes for each command so that operator need only refer to these pages for keystroke entries required to call up display or to input command.
- .6 Software to include:
 - .1 Documentation of theory, design, interface requirements, functions, including test and verification procedures.
 - .2 Detailed descriptions of program requirements and capabilities.
 - .3 Data necessary to permit modification, relocation, reprogramming and to permit new and existing software modules to respond to changing system functional requirements without disrupting normal operation.
 - .4 Software modules, fully annotated source code listings, error free object code files ready for loading via peripheral device

- .5 Complete program cross reference plus linking requirements, data exchange requirements, necessary subroutine lists, data file requirements, other information necessary for proper loading, integration, interfacing, program execution.
- .6 Software for each Controller and single section referencing Controller common parameters and functions.
- .7 Maintenance: document maintenance procedures including inspection, periodic preventive maintenance, fault diagnosis, repair or replacement of defective components, including calibration, maintenance, repair of sensors, transmitters, transducers, controller and interface firmware's, plus diagnostics and repair/replacement of system hardware.
- .8 System configuration document:
 - .1 Provisions and procedures for planning, implementing and recording hardware and software modifications required during operating lifetime of system.
 - .2 Information to ensure co-ordination of hardware and software changes, data link or message format/content changes, sensor or control changes in event that system modifications are required.
- .9 Programmer control panel documentation: provide where panels are independently interfaced with BECC, including interfacing schematics, signal identification, timing diagrams, fully commented source listing of applicable driver/handler.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 Canadian Standards Association (CSA International).
 - .1 CSA C22.1-[02], The Canadian Electrical Code, Part I (19th Edition), Safety Standard for Electrical Installations.

1.2 DEFINITIONS

- .1 For acronyms and definitions refer to Section 25 05 01 - EMCS: General Requirements.

1.3 SYSTEM DESCRIPTION

- .1 Language Operating Requirements: provide identification for control items in English.

1.4 SUBMITTALS

- .1 Submittals in accordance with Section 01 33 00 - Submittal Procedures supplemented and modified by requirements of this Section.
- .2 Submit to Consultant for approval samples of nameplates, identification tags and list of proposed wording.

Part 2 Products

2.1 NAMEPLATES FOR PANELS

- .1 Identify by Plastic laminate, 3 mm thick Melamine, matt white finish, black core, square corners, lettering accurately aligned and engraved into core.
- .2 Sizes: 25 x 67 mm minimum.
- .3 Lettering: minimum 7 mm high, black.
- .4 Inscriptions: machine engraved to identify function.

2.2 NAMEPLATES FOR FIELD DEVICES

- .1 Identify by plastic encased cards attached by plastic tie.
- .2 Sizes: 50 x 100 mm minimum.
- .3 Lettering: minimum 5 mm high produced from laser printer in black.
- .4 Data to include: point name and point address.
- .5 Companion cabinet: identify interior components using plastic enclosed cards with point name and point address.

2.3 WARNING SIGNS

- .1 Equipment including motors, starters under remote automatic control: supply and install [orange] coloured signs warning of automatic starting under control of EMCS.
- .2 Sign to read: "Caution: This equipment is under automatic remote control of EMCS" as reviewed by Consultant's.

2.4 WIRING

- .1 Supply and install numbered tape markings on wiring at panels, junction boxes, splitters, cabinets and outlet boxes.
- .2 Colour coding: to CSA C22.1. Use colour coded wiring in communications cables, matched throughout system.
- .3 Power wiring: identify circuit breaker panel/circuit breaker number inside each EMCS panel.

2.5 CONDUIT

- .1 Colour code EMCS conduit.
- .2 Pre-paint box covers and conduit fittings.
- .3 Coding: use fluorescent orange paint and confirm colour with Consultant during "Preliminary Design Review".

Part 3 Execution

3.1 NAMEPLATES AND LABELS

- .1 Ensure that manufacturer's nameplates, CSA labels and identification nameplates are visible and legible at all times.

3.2 EXISTING PANELS

- .1 Correct existing nameplates and legends to reflect changes made during Work.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 References.
 - .1 Canada Labour Code (R.S. 1985, c. L-2)/Part I - Industrial Relations.
 - .2 Canadian Standards Association (CSA International).
 - .1 CSA Z204-94(R1999), Guidelines for Managing Indoor Air Quality in Office Buildings.

1.2 DEFINITIONS

- .1 BC(s) - Building Controller(s).
- .2 OWS - Operator Work Station.
- .3 For additional acronyms and definitions refer to Section 25 05 01 - EMCS: General Requirements.

1.3 SUBMITTALS

- .1 Submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Submit detailed preventative maintenance schedule for system components to Consultant.
- .3 Submit detailed inspection reports to Consultant.
- .4 Submit dated, maintenance task lists to Consultant and include the following sensor and output point detail, as proof of system verification:
 - .1 Point name and location.
 - .2 Device type and range.
 - .3 Measured value.
 - .4 System displayed value.
 - .5 Calibration detail
 - .6 Indication if adjustment required,
 - .7 Other action taken or recommended.
- .5 Submit network analysis report showing results with detailed recommendations to correct problems found.
- .6 Records and logs: in accordance with Section 01 78 00 - Closeout Submittals.
 - .1 Maintain records and logs of each maintenance task on site.
 - .2 Organize cumulative records for each major component and for entire EMCS chronologically.
 - .3 Submit records to Consultant, after inspection indicating that planned and systematic maintenance have been accomplished.

- .7 Revise and submit Consultant in accordance with Section 01 78 00 - Closeout Submittals "As-built drawings" documentation and commissioning reports to reflect changes, adjustments and modifications to EMCS made during warranty period.

1.4 MAINTENANCE SERVICE DURING WARRANTY PERIOD

- .1 Provide services, materials, and equipment to maintain EMCS for specified warranty period. Provide detailed preventative maintenance schedule for system components as described in Submittal article.
- .2 Emergency Service Calls:
 - .1 Initiate service calls when EMCS is not functioning correctly.
 - .2 Qualified control personnel to be available during warranty period to provide service to "CRITICAL" components whenever required at no extra cost.
 - .3 Furnish Departmental Representative with telephone number where service personnel may be reached at any time.
 - .4 Service personnel to be on site ready to service EMCS within 2 hours after receiving request for service.
 - .5 Perform Work continuously until EMCS restored to reliable operating condition.
- .3 Operation: foregoing and other servicing to provide proper sequencing of equipment and satisfactory operation of EMCS based on original design conditions and as recommended by manufacturer.
- .4 Work requests: record each service call request, when received separately on approved form and include:
 - .1 Serial number identifying component involved.
 - .2 Location, date and time call received.
 - .3 Nature of trouble.
 - .4 Names of personnel assigned.
 - .5 Instructions of work to be done.
 - .6 Amount and nature of materials used.
 - .7 Time and date work started.
 - .8 Time and date of completion.
- .5 Provide system modifications in writing.
 - .1 No system modification, including operating parameters and control settings, to be made without prior written approval of Consultant.

1.5 SERVICE CONTRACTS

- .1 Provide in-depth technical expertise and assistance to Departmental Representative, Consultant and Commissioning Manager in preparation and implementation of service contracts and in-house preventive maintenance procedures.
- .2 Service Contracts to be an extension to the existing system service contract (if any exists) to incorporate the upgrade in this contract.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 FIELD QUALITY CONTROL

- .1 Perform as minimum (the inspections detailed in the existing service contract (if any exists). Provide detailed written report to Departmental Representative as described in Submittal article.
- .2 Perform inspections during regular working hours, 0800 to 1630 h, Monday through Friday, excluding statutory holidays.
- .3 Following inspections are minimum requirements and should not be interpreted to mean satisfactory performance:
 - .1 Perform calibrations using test equipment having traceable, certifiable accuracy at minimum 50% greater than accuracy of system displaying or logging value.
 - .2 Check and Calibrate each field input/output device in accordance with Canada Labour Code - Part I and CSA Z204.
 - .3 Provide dated, maintenance task lists, as described in Submittal article, as proof of execution of complete system verification.
- .4 Minor inspections to include, but not limited to:
 - .1 Perform visual, operational checks to BC's, peripheral equipment, interface equipment and other panels.
 - .2 Check equipment cooling fans as required.
 - .3 Visually check for mechanical faults, air leaks and proper pressure settings on pneumatic components.
 - .4 Review system performance with Departmental Representative to discuss suggested or required changes.
- .5 Major inspections to include, but not limited to:
 - .1 Minor inspection.
 - .2 Clean OWS(s) peripheral equipment, BC(s), interface and other panels, micro-processor interior and exterior surfaces.
 - .3 Check signal, voltage and system isolation of BC(s), peripherals, interface and other panels.
 - .4 Verify calibration/accuracy of each input and output device and recalibrate or replace as required.
 - .5 Provide mechanical adjustments, and necessary maintenance on printers.
 - .6 Run system software diagnostics as required.
 - .7 Install software and firmware enhancements to ensure components are operating at most current revision for maximum capability and reliability.

- .1 Perform network analysis and provide report as described in Submittal article.
- .6 Rectify deficiencies revealed by maintenance inspections and environmental checks.
- .7 Continue system debugging and optimization.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 Canadian Standards Association (CSA International).
 - .1 CSA T529-95(R2000), Telecommunications Cabling Systems in Commercial Buildings (Adopted ANSI/TIA/EIA-568-A with modifications).
 - .2 CSA T530-99(R2004), Commercial Building Standard for Telecommunications Pathways and Spaces (Adopted ANSI/TIA/EIA-569-A with modifications).
- .2 Institute of Electrical and Electronics Engineers (IEEE)/Standard for Information technology - Telecommunications and information exchange between systems - Local and metropolitan area networks - Specific requirements.
 - .1 IEEE Std 802.3TM-2002, Part 3: Carrier sense multiple access with collision
- .3 Telecommunications Industries Association (TIA)/Electronic Industries Alliance (EIA)
 - .1 TIA/EIA-568-[March 2004], Commercial Building Telecommunications Cabling Standards Set, Part 1 General Requirements Part 2 Balanced Twisted-Pair Cabling Components Part 3 Optical Fiber Cabling Components Standard.
 - .2 TIA/EIA-569-A-December 2001. Commercial Building Standard for Telecommunications Pathways and Spaces.
- .4 Treasury Board Information Technology Standard (TBITS).
 - .1 TBITS 6.9-2000, Profile for the Telecommunications Wiring System in Government Owned and Leased Buildings - Technical Specifications.

1.2 DEFINITIONS

- .1 Acronyms and definitions: refer to Section 25 05 01 - EMCS - General Requirements.

1.3 SYSTEM DESCRIPTION

- .1 Re-use existing JCI Metasys Data Communication Network.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 DEFINITIONS

- .1 Acronyms and definitions: refer to Section 25 05 01 - EMCS: General Requirements.

1.2 OWS SYSTEM DESCRIPTION

- .1 Re-use existing JCI Metasys OWS.
- .2 Provide new graphics of the main heating plant and incorporate all existing graphic functionality including but not limited to display, event, alarm, archiving and auto restoration.

Part 2 Products

2.1 Not used.

Part 3 Execution

3.1 Not used.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 American Society of Heating, Refrigeration and Air-Conditioning Engineers, Inc. (ASHRAE).
 - .1 ASHRAE 2003, Applications Handbook, SI Edition.
- .2 Canadian Standards Association (CSA International).
 - .1 C22.2 No.205-M1983(R1999), Signal Equipment.
- .3 Institute of Electrical and Electronics Engineers (IEEE).
 - .1 IEEE C37.90.1-02, Surge Withstand Capabilities (SWC) Tests for Relays and Relay Systems Associated with Electric Power Apparatus.
- .4 Public Works and Government Services Canada (PWGSC)/Real Property Branch/Architectural and Engineering Services.
 - .1 MD13800-September 2000, Energy Management and Control Systems (EMCS) Design Manual. English: <ftp://ftp.pwgsc.gc.ca/rps/docentre/mechanical/me214-e.pdf>

1.2 DEFINITIONS

- .1 Acronyms and definitions: refer to Section 25 05 01 - EMCS: General Requirements.
- .2 Existing JCI Metasys boiler plant controller to be re-used with appropriate point expansion module as/if required.

Part 2 Products

- .1 Not used.

Part 3 Execution

- .1 Not used.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 American National Standards Institute (ANSI).
 - .1 ANSI C12.7-1993(R1999), Requirements for Watthour Meter Sockets.
 - .2 ANSI/IEEE C57.13-1993, Standard Requirements for Instrument Transformers.
- .2 American Society for Testing and Materials International, (ASTM).
 - .1 ASTM B148-97(03), Standard Specification for Aluminum-Bronze Sand Castings.
- .3 National Electrical Manufacturer's Association (NEMA).
 - .1 NEMA 250-03, Enclosures for Electrical Equipment (1000 Volts Maximum).
- .4 Air Movement and Control Association, Inc. (AMCA).
 - .1 AMCA Standard 500-D-98, Laboratory Method of Testing Dampers For Rating.
- .5 Canadian Standards Association (CSA International).
 - .1 CSA-C22.1-02, Canadian Electrical Code, Part 1 (19th Edition), Safety Standard for Electrical Installations.

1.2 DEFINITIONS

- .1 Acronyms and Definitions: refer to Section 25 05 01 - EMCS: General Requirements.

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit shop drawings and manufacturer's installation instructions in accordance with Section 25 05 02 - EMCS: Submittals and Review Process.
- .2 Pre-Installation Tests.
 - .1 Submit samples at random from equipment shipped, as requested by Consultant, for testing before installation. Replace devices not meeting specified performance and accuracy.
- .3 Manufacturer's Instructions:
 - .1 Submit manufacturer's installation instructions for specified equipment and devices.

1.4 EXISTING CONDITIONS

- .1 Cutting and Patching: in accordance with Section 01 73 00 - Execution Requirements supplemented as specified herein.
- .2 Repair surfaces damaged during execution of Work. Turn over to Department Representative existing materials removed from Work not identified for re-use.

Part 2 Products

2.1 GENERAL

- .1 Control devices of each category to be of same type and manufacturer.
- .2 External trim materials to be corrosion resistant. Internal parts to be assembled in watertight, heat resistant, assembly.
- .3 Operating conditions: 0 - 32 degrees C with 10 - 90% RH (non-condensing) unless otherwise specified.
- .4 Terminations: use standard conduit box with slot screwdriver compression connector block unless otherwise specified.
- .5 Transmitters and sensors to be unaffected by external transmitters including walkie talkies.
- .6 Account for hysteresis, relaxation time, maximum and minimum limits in applications of sensors and controls.
- .7 Devices installed in user occupied space not exceed Noise Criteria (NC) of 35. Noise generated by any device must not be detectable above space ambient conditions.

2.2 TEMPERATURE TRANSMITTERS

- .1 Requirements:
 - .1 Input circuit: to accept 3-lead, 100 or 1000 ohm at 0 degrees C, platinum resistance detector type sensors.
 - .2 Power supply: 24 V DC into load of 575 ohms. Power supply effect less than 0.01 degrees C per volt change.
 - .3 Output signal: 4 - 20 mA into 500 ohm maximum load.
 - .4 Input and output short circuit and open circuit protection.
 - .5 Output variation: less than 0.2 % of full scale for supply voltage variation of plus or minus 10 %.
 - .6 Combined non-linearity, repeatability, hysteresis effects: not to exceed plus or minus 0.5 % of full scale output.
 - .7 Maximum current to 100 or 1000 ohm RTD sensor: not to exceed 25 mA.
 - .8 Integral zero and span adjustments.
 - .9 Temperature effects: not to exceed plus or minus 1.0 % of full scale/ 50degrees C.
 - .10 Long term output drift: not to exceed 0.25 % of full scale/ 6 months.
 - .11 Transmitter ranges: select narrowest range to suit application from following:
 - .1 0 to 100 degrees C, plus or minus 0.5 degrees C.

2.3 DIFFERENTIAL PRESSURE TRANSMITTERS

- .1 Requirements:
 - .1 Internal materials: suitable for continuous contact with industrial standard instrument air, compressed air, water, steam, as applicable.
 - .2 Output signal: 4 - 20 mA into 500 ohm maximum load.

- .3 Output variations: less than 0.2 % full scale for supply voltage variations of plus or minus 10 %.
- .4 Combined non-linearity, repeatability, and hysteresis effects: not to exceed plus or minus 0.5 % of full scale output over entire range.
- .5 Integral zero and span adjustment.
- .6 Temperature effects: not to exceed plus or minus 1.5 % full scale/ 50 degrees C.
- .7 Over-pressure input protection to at least twice rated input pressure.
- .8 Output short circuit and open circuit protection.
- .9 Unit to have 12.5 mm N.P.T. conduit connection. Enclosure to be integral part of unit.

2.4 ELECTROMECHANICAL RELAYS

- .1 Requirements:
 - .1 Double voltage, DPDT, plug-in type with termination base.
 - .2 Coils: rated for 120V AC or 24V DC. Other voltage: provide transformer.
 - .3 Contacts: rated at 5 amps at 120 V AC.
 - .4 Relay to have visual status indication

2.5 SOLID STATE RELAYS

- .1 General:
 - .1 Relays to be socket or rail mounted.
 - .2 Relays to have LED Indicator
 - .3 Input and output Barrier Strips to accept 14 to 28 AWG wire.
 - .4 Operating temperature range to be -20 degrees C to 70 degrees C.
 - .5 Relays to be CSA Certified.
 - .6 Input/output Isolation Voltage to be 4000 VAC at 25 degrees C for 1 second maximum duration.
 - .7 Operational frequency range, 45 to 65 HZ.
- .2 Input:
 - .1 Control voltage, 3 to 32 VDC.
 - .2 Drop out voltage, 1.2 VDC.
 - .3 Maximum input current to match AO (Analog Output) board.
- .3 Output:
 - .1 AC or DC Output Model to suit application.

2.6 CURRENT TRANSDUCERS

- .1 Requirements:
- .2 Purpose: combined sensor/transducer, to measure line current and produce proportional signal in one of following ranges:
 - .1 4-20 mA DC.
 - .2 0-1 volt DC.

- .3 0-10 volts DC.
- .4 0-20 volts DC.
- .3 Frequency insensitive from 10 - 80 hz.
- .4 Accuracy to 0.5% full scale.
- .5 Zero and span adjustments. Field adjustable range to suit motor applications.
- .6 Adjustable mounting bracket to allow for secure/safe mounting inside MCC.

2.7 CONTROL DAMPERS

- .1 Construction: blade, 152 mm wide, 1219 mm long, maximum. Modular maximum size, 1219 mm wide x 1219 mm high. Three or more sections to be operated by jack shafts.
- .2 Materials:
 - .1 Frame: 2.03 mm minimum thickness extruded aluminum. For outdoor air and exhaust air applications, frames to be insulated.
 - .2 Blades: extruded aluminum.
 - .3 Bearings: maintenance free, synthetic type of material.
 - .4 Linkage and shafts: aluminum, zinc and nickel plated steel.
 - .5 Seals: synthetic type, EPDM, mechanically locked into blade edges.
 - .1 Frame seals: synthetic type, TPE edge seals, mechanically locked into frame sides.
- .3 Performance: minimum damper leakages meet or exceed AMCA Standard 500-D ratings.
 - .1 Size/Capacity: refer to drawings.
 - .2 25 L/s/m² maximum allowable leakage against 1000 Pa static pressure for outdoor air and exhaust air applications.
 - .3 Temperature range: - 40° C to +100° C.
- .4 Arrangements: dampers mixing warm and cold air to be parallel blade, mounted at right angles to each other, with blades opening to mix air stream.
- .5 Jack shafts: 25 mm diameter solid shaft, constructed of corrosion resistant metal complete with required number of pillow block bearings to support jack shaft and operate dampers throughout their range.
 - .1 Include corrosion resistant connecting hardware to accommodate connection to damper actuating device.
 - .2 Install using manufacturer's installation guidelines.
 - .3 Use same manufacturer as damper sections.

2.8 ELECTRONIC CONTROL ACTUATORS

- .1 Requirements:
 - .1 Direct mount, direct coupled, proportional type as indicated.
 - .2 Spring return for "fail-safe" in Normally Open or Normally closed position as indicated.

- .3 Operator: size to control against maximum pressure and dynamic closing/opening pressure, whichever is great.
- .4 Power requirements: 5 VA maximum at 24 V AC.
- .5 Operation range: 0 – 10 V DC or 4 – 20 mV DC.
- .6 Actuator to drive damper from full open to full closed in less than 120 seconds.

2.9 CONTROL VAVLES

- .1 Body: characterized ball.
 - .1 Flow characteristic as indicated on control valve schedule: linear or equal percentage.
 - .2 Size for minimal 21 kPa pressure drop.
 - .3 Normally open, Normally closed, as indicated.
 - .4 Two (2) port, as indicated.
 - .5 Leakage rate ANSI class IV, 0.01% of full open valve capacity.
 - .6 Packing easily replaceable.
 - .7 Stem, stainless steel.
 - .8 NPS 2 and under: Screwed National Pipe Thread (NPT) tapered female connections.
 - .1 Valves to ANSI Class 250, valves to bear ANSI mark.
 - .2 Rangeability: 50:1 minimum

2.10 WIRING

- .1 In accordance with Section 26 27 10 - Modular Wiring System 26 27 26 - Wiring Devices.
- .2 For wiring under 70 volts use FT6 rated wiring where wiring is not run in conduit. Other cases use FT4 wiring.
- .3 Wiring must be continuous without joints.
- .4 Sizes:
 - .1 Field wiring to digital device: #18AWG 20AWG stranded twisted pair.
 - .2 Analog input and output: shielded #18 minimum solid copper #20 minimum stranded twisted pair.

Part 3 Execution

3.1 INSTALLATION

- .1 Install equipment, components so that manufacturer's and CSA labels are visible and legible after commissioning is complete.
- .2 Install field control devices in accordance with manufacturers recommended methods, procedures and instructions.
- .3 Temperature transmitters, humidity transmitters, current-to-pneumatic transducers, solenoid air valves, controllers, relays: install in NEMA I enclosure or as required for

specific applications. Provide for electrolytic isolation in cases when dissimilar metals make contact.

- .4 Support field-mounted panels, transmitters and sensors on pipe stands or channel brackets.
- .5 Fire stopping: provide space for fire stopping in accordance with Section 07 84 00 - Firestopping. Maintain fire rating integrity.
- .6 Electrical:
 - .1 Complete installation in accordance with Section 26 05 00 - Common Work Results for Electrical.
 - .2 Modify existing starters to provide for EMCS as indicated in I/O Summaries and as indicated.
 - .3 Refer to electrical control schematics included as part of control design schematics in Section 25 90 01 - EMCS: Site Requirements Applications and Systems Sequences of Operation on drawings. Trace existing control wiring installation and provide updated wiring schematics including additions, deletions to control circuits for review by Departmental Representative DCC Representative Consultant before beginning Work.
 - .4 Terminate wires with screw terminal type connectors suitable for wire size, and number of terminations.
 - .5 Install communication wiring in conduit.
 - .1 Provide complete conduit system to link Building Controllers, field panels and OWS(s).
 - .2 Conduit sizes to suit wiring requirements and to allow for future expansion capabilities specified for systems.
 - .3 Maximum conduit fill not to exceed 40%.
 - .4 Design drawings do not show conduit layout.
 - .6 Do not run exposed conduits in normally occupied spaces unless otherwise indicated or unless impossible to do otherwise. Wiring in mechanical rooms, wiring in service rooms and exposed wiring must be in conduit.

3.2 TEMPERATURE SENSORS

- .1 Stabilize to ensure minimum field adjustments or calibrations.
- .2 Readily accessible and adaptable to each type of application to allow for quick easy replacement and servicing without special tools or skills.
- .3 Thermowells: install for piping installations.
 - .1 Locate well in elbow where pipe diameter is less than well insertion length.
 - .2 Thermowell to restrict flow by less than 30%.
 - .3 Use thermal conducting paste inside wells.

3.3 PRESSURE AND DIFFERENTIAL PRESSURE SWITCHES AND SENSORS

- .1 Install isolation valve and snubber on sensors between sensor and pressure source where code allows.

- .1 Protect sensing elements on steam and high temperature hot water service with pigtail syphon between valve and sensor.

3.4 IDENTIFICATION

- .1 Identify field devices in accordance with Section 25 05 54 - EMCS: Identification.

3.5 TESTING AND COMMISSIONING

- .1 Calibrate and test field devices for accuracy and performance in accordance with Section 25 01 11 - EMCS: Start-up, Verification and Commissioning.

END OF SECTION

Part 1 General**1.1 REFERENCES**

- .1 Public Works and Government Services Canada (PWGSC) / Real Property Branch / Architectural and Engineering Services.
 - .1 MD13800-September 2000, Energy Management and Control Systems (EMCS) Design Manual. English: <ftp://ftp.pwgsc.gc.ca/rps/docentre/mechanical/me214-e.pdf>

1.2 SEQUENCING

- .1 Present sequencing of operations for systems, in accordance with MD13800 - Energy Management and Control Systems (EMCS) Design Manual.
- .2 Sequencing of operations for system as follows:

1.3 CONTROL WIRING

- .1 Provide all wiring and control components necessary to complete the sequences detailed below.

1.4 CONTROL SEQUENCES

- .1 Upgraded Hot Water Boiler Plant:
 - .1 The hot water boiler plant consist of two boilers (50% load each) each with circulating pumps, two main VFD heating (100% standby) pumps, expansion tank and differential pressure system.
 - .2 The heating system will be enabled at 18°C (adjustable) outside air temperature or lower. The system will shut down and disable all associated heating alarms at 20°C (adjustable) or higher outside air.
 - .3 When the heating system is enabled:
 - .1 The boiler and individual boiler pumps will operate on a lead/lag basis with switchover occurring every 200 operating hours. The lead boiler pump will start immediately. The heating water supply sensor will cycle the lead/lag boilers modulating fire to maintain the outdoor reset schedule (adjustable) of:

Outside Temperature	System Supply Temperature
-30°C	90°C
+18°C	60°C
 - .2 If the lead boiler fails to start, the lag boiler will start and an alarm will be generated.

- .3 Safety points of low water cut off and no flow will be wired into each boiler to shut down burner control. If either safety condition is not met, an alarm will be generated.
- .4 Whenever the outdoor temperature falls below 5°C regardless of load, the lag boiler pump will start.
- .5 Main VFD heating pumps P-1 and P-2 will operate on a lead/lag basis with switchover occurring every 200 operating hours. Monitor the temperature differential between supply and return and ramp the pump to maintain 10°C differential. Monitor the system differential pressure. Maintain a minimum of 45 kPa (adjustable) to ensure proper system flow.
- .6 The pressure bypass control will maintain supply/return pressure by fine tuning pump speed. When the lead heating pump reaches minimum speed, a 2-way bypass valve will modulate open to prevent excess pressure in the supply main.
- .7 The existing outdoor air sensor shall be re-used.
- .4 Alarms: Boiler failure, pump failure, low and high heating water and glycol temperature alarms will be indicated. Override alarms when system is not enabled.
- .2 Upgraded Air Handling Unit
 - .1 A new heating coil is being provided for the existing air handling unit. Provide a new 2-way control valve complete with digital actuator to be modulated by the existing supply air temperature algorithm to maintain set point.
 - .2 The motorized dampers are to be replaced with new motorized dampers. Provide new digital actuators to be controlled by the existing mixed air temperature algorithm to maintain set point.

Control Sequences and Points Database

SYSTEM: HOT WATER HEATING									
<i>Point Identification</i>		<i>Inputs</i>		<i>Outputs</i>		Failsafe / De-energized	Alarm	Alarm Remarks	Notes
Description	Point Label	Digital	Analog	Digital	Analog				
B1 Failure	Dc	X					X	Failure	
B2 Failure	Dc	X					X	Failure	
B1 Enable	Ry			X				Re-connect existing	
B2 Enable	Ry			X					
B1 Circ Pump On/Off	Ry			X				Re-connect existing	
B1 Circ Pump Status	Cr	X					X	Pump failure	
B2 Circ Pump On/Off	Ry			X					
B2 Circ Pump Status	Cr	X					X	Pump failure	
Supply Water Temperature	Tw		X				X	Low and high temp	
Return Water Temperature	Tw		X					Re-Use Existing	
Differential Pressure Water	Ps		X						
B1 Supply Temperature	Tw		X				X	Low and high temp	
B2 Supply Temperature	Tw		X				X	Low and high temp	
Outdoor Air Temperature	To		X					Re-use existing	
Heating Pump 1 VFD Enable	Ry			X					

Control Sequences and Points Database

SYSTEM: HOT WATER HEATING – Cont'd									
<i>Point Identification</i>		<i>Inputs</i>		<i>Outputs</i>		Failsafe / De-energized	Alarm	Alarm Remarks	Notes
Description	Point Label	Digital	Analog	Digital	Analog				
Heating Pump 1 VFD Status	Ct		X						
Heating Pump 1 VFD Drive	El				X				
Heating Pump 1 VFD Fail	Dc	X							
Heating Pump 2 VFD Enable	Ry			X					
Heating Pump 2 VFD Status	Ct		X						
Heating Pump 2 VFD Drive	El				X				
Heating Pump 2 VFD Fail	Dc	X							
Water Expansion Tank Level Low	Dc	X							

Pressure Bypass Valve	Vm				X				
-----------------------	----	--	--	--	---	--	--	--	--

Part 2 Products

2.1 NOT USED

.1 Not Used.

Part 3 Execution

3.1 NOT USED

.1 Not Used.

END OF SECTION