

RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:
Bid Receiving Public Works and Government
Services Canada/Réception des soumissions Travaux
publics et Services gouvernementaux Canada
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British Columbia
V6Z 0B9
Bid Fax: (604) 775-9381

SOLICITATION AMENDMENT
MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise
indicated, all other terms and conditions of the Solicitation
remain the same.

Ce document est par la présente révisé; sauf indication contraire,
les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Public Works and Government Services Canada -
Pacific Region
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British C
V6Z 0B9

Title - Sujet Security Fence Replacement	
Solicitation No. - N° de l'invitation EZ108-151489/A	Amendment No. - N° modif. 001
Client Reference No. - N° de référence du client	Date 2015-02-18
GETS Reference No. - N° de référence de SEAG PW-\$PWY-019-7448	
File No. - N° de dossier PWY-4-37310 (019)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2015-02-26	
Time Zone Fuseau horaire Pacific Standard Time PST	
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Ngan, Ken (PWY)	Buyer Id - Id de l'acheteur pwy019
Telephone No. - N° de téléphone (604) 658-2755 ()	FAX No. - N° de FAX (604) 775-6633
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction: PWGSC - Esquimalt Graving Dock - Victoria, BC	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

This Solicitation Amendment 001 is raised to provide the list of attendees at the Site Visit and to provide responses to questions asked at the Site Visit.

Companies that attended the Site Visit

Forbes Industrial Contractors

Pro-Line Fencing

Tower Fence Products

Responses to questions from Tender Site Visit on Thursday February 12, 2015

Q1.) If the fence is to be put back in the existing location is the survey work required?

A1.) As-built site survey work is required per Section 01 11 55 and per Appendix D.

Q2.) What is to happen with all of the suspected contaminated soils once excavated?

A2.) Soils are presumed to be potentially contaminated. Excavated soils are to be stockpiled and stored on site by the Contractor per Drawings and Specifications. Soil testing will be completed by the Crown per Section 31 23 11. The Contractor is to presume that granular backfill material per Section 31 00 90 will be installed where required to bury fence fabric 300mm and reinstate disturbed ground or holes that remain after removal of existing fencing and installation of new security fence per Drawings and Specifications.

Q3.) How is the height of fence calculated?

A3.) The minimum height of fence is calculated by the adjacent grade (measured 3.048m back from the fence) where the minimum requirement for height of fence is affected by the adjacent grade. The minimum height of fence is shown on the Drawings.

Q4.) How much of the brush/shrubs/trees are to be cut back or removed during the Work?

A4.) The Contractor is to complete clearing and grubbing as required to complete the installation of the security fence per Drawings and Specifications. This Work will also include pruning or cutting back overhanging limbs and branches where required to complete installation of the security fence. PWGSC has not specified a minimum or maximum volume or width of removals as this activity forms part of the Contractor's

“means and methods” of completing the work. Please refer to Drawings and Specifications.

Q5.) Are as-builts of buried (underground) services available?

A5.) Site as-builts are available showing approximate locations of buried services, where not already identified on the Drawings. The Contractor is to field locate all site utilities that affect the Work prior to any excavation work proceeding per Drawings and Specifications. Public Works and Government Services Canada (PWGSC) can confirm there are no buried or above grade gas lines within the Esquimalt Graving Dock (EGD) facility.

Q6.) How critical is the alignment or location of the fence?

A6.) The fence must be installed on PWGSC/EGD side of the property line (P/L) along the alignment per Drawings and Specifications. The Contractor will survey the fence per Section 01 11 55 and per Appendix D to confirm required location and alignment.

All other terms and conditions remain unchanged.