
PART 1 - GENERAL

1.1 SECTION INCLUDES

- .1 Connection to existing systems.
- .2 Special scheduling requirements.

1.2 RELATED SECTIONS

- .1 01 32 16.07 - Construction Progress Schedule - Bar (GANNTT) Chart.

1.3 ACCESS AND EGRESS

- .1 Design, construct and maintain temporary “access to” and “egress from “ work areas, including stairs, runways, ramps or ladders and scaffolding, independent of finished surfaces and in accordance with relevant municipal, provincial and other regulations.

1.4 USE OF SITE AND FACILITIES

- .1 Execute work with least possible interference or disturbance to normal use of premises. Make arrangements with Departmental Representative to facilitate work as stated.
- .2 Maintain existing services to building and provide for personnel and vehicle access.
- .3 Where security is reduced by work provide temporary means to maintain security.
- .4 Closures: protect work temporarily until permanent enclosures are completed.

1.5 ALTERATIONS, ADDITIONS OR REPAIRS TO EXISTING SITE

- .1 Execute work with least possible interference or disturbance to building operations and normal use of premises. Arrange with Departmental Representative to facilitate execution of work.

1.6 EXISTING SERVICES

- .1 Contractor shall execute work in a manner that facilitates continuous.
 - .2 Should be as follows:
 - .1 Interruption of mechanical or electrical service is not permitted.
-

- .2 Further changeover to new services, the Contractor shall submit a shut-down schedule to Departmental Representative for review and approval a minimum of five (5) days prior to service interruption.
- .4 Departmental Representative shall have authority over all service interruption lengths and schedule.
- .3 Extreme caution is to be taken during excavation so as not to damage existing buried utilities in any way. Any damage shall be repaired by the Contractor, at no additional cost to the Departmental Representative. Excavation operations shall be coordinated with the Departmental Representative.

1.7 CONTINGENCY PLAN

- .1 Contractor must submit a written Contingency Plan prior to start of ANY work.
- .2 Contingency plan must include the following information:
 - .1 Schedule of work.
 - .2 Method of repair should the storm system or underground electrical or communication lines become damaged.
 - .3 Proof that materials required to complete the work and/or make repairs are readily available.
 - .4 Any additional information deemed necessary by Departmental Representative.
- .3 Contractor must receive written approval from Departmental Representative before proceeding with any work relating to the Contingency Plan.

1.8 SPECIAL REQUIREMENTS

- .1 Submit schedule in accordance with Section 01 32 16.07 - Construction Progress Schedule - Bar (GANTT) Chart.
 - .2 This contract shall be planned and implemented by the Contractor, such that all work is carried out and completed by March 31st, 2016. All measures necessary to meet this deadline shall be considered when bidding for this project.
 - .3 Ensure that Contractor personnel employed on site become familiar with and obey regulations including safety, fire, traffic and security regulations.
-

1.9 SECURITY CLEARANCES

- .1 Personnel employed on this project will be subject to a security check. Obtain clearance, as instructed, for each individual who will require to enter premises.
- .2 Personnel will be check daily at start of work shift and provided with a pass which must be worn at all times. Pass must be returned at end of work shift and personnel checked out.

1.10 MEASUREMENT FOR PAYMENT

- .1 No separate measurement for payment shall be made for items under this section. Include costs for Work Restrictions in the lump sum portion of work on the Bid and Acceptance Form.

PART 2 - PRODUCTS

Not applicable

PART 3 - EXECUTION

Not applicable