

## **PART 1 - GENERAL**

### **1.1 SECTION INCLUDES**

- .1 Barriers.
- .2 Traffic Controls.

### **1.2 INSTALLATION AND REMOVAL**

- .1 Provide temporary controls in order to execute work expeditiously.
- .2 Remove from site all such work after use.

### **1.3 GUARD RAILS AND BARRICADES**

- .1 Provide secure, rigid guard rails and barricades around open excavations.
- .2 Provide as required by governing authorities.

### **1.4 ACCESS TO SITE**

- .1 Provide and maintain access roads, crossings, ramps and construct runways as may be required for site access including snow clearing of work areas.

### **1.5 PUBLIC TRAFFIC FLOW**

- .1 Provide and maintain competent signal flag operators, traffic signals, barricades and flares, lights, or lanterns as required to perform work and protect the public.

### **1.6 FIRE ROUTES**

- .1 Maintain access to property including overhead clearances for use by emergency response vehicles.

### **1.7 PROTECTION FOR OFF-SITE AND PUBLIC PROPERTY**

- .1 Protect surrounding private and public property from damage during performance of work.
  - .2 Be responsible for damage incurred.
-

## **1.8 PROTECTION OF BUILDING FINISHES**

- .1 Provide protection for finished and partially finished building finishes and equipment during performance of Work.
- .2 Provide necessary screens, covers, and hoardings.
- .3 Confirm with Departmental Representative locations and installation schedule 3 days prior to installation.
- .4 Be responsible for damage incurred due to lack of or improper protection.

## **PART 2 - PRODUCTS**

Not applicable

## **PART 3 - EXECUTION**

Not applicable