

PART 1 - GENERAL

1.1 RELATED WORK

- .1 Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
- .2 Section 02 61 00.01 - Contaminated Soil Managements

1.2 DEFINITIONS

- .1 Hazardous Material: Product, substance, or organism that is used for its original purpose; and that is either dangerous goods or a material that may cause adverse impact to the environment or adversely affect health of persons, animals or plant life when released into the environment.
- .2 Environmental Protection: prevention/control of pollution and habitat or environment disruption during construction. Control of environmental pollution and damage requires consideration of land, water, and air; biological and cultural resources; and includes management of visual aesthetics; noise; solid, chemical, gaseous, and liquid waste; radiant energy and radioactive material as well as other pollutants.

1.3 SUBMITTALS

- .1 Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
 - .2 Prior to commencing construction activities or delivery of materials to site, submit Environmental Protection Plan for review and approval by Departmental Representative. Environmental Protection Plan is to present comprehensive overview of known or potential environmental issues which must be addressed during construction.
 - .3 Address topics at level of detail commensurate with environmental issue and required construction tasks.
 - .4 Environmental protection plan: include:
 - .1 Names of persons responsible for ensuring adherence to Environmental Protection Plan.
 - .2 Names and qualifications of persons responsible for manifesting hazardous waste to be removed from site.
 - .3 Names and qualifications of persons responsible for training site personnel.
 - .4 Descriptions of environmental protection personnel training program.
-

- .5 Erosion and sediment control plan which identifies type and location of erosion and sediment controls to be provided including monitoring and reporting requirements to assure that control measures are in compliance with erosion and sediment control plan, Federal, Provincial, and Municipal laws and regulations.
- .6 Drawings showing locations of proposed temporary excavations or embankments for haul roads, stream crossings, material storage areas, structures, sanitary facilities, and stockpiles of excess or spoil materials including methods to control runoff and to contain materials on site.
- .7 Spill Control Plan: including procedures, instructions, and reports to be used in event of unforeseen spill of regulated substance.
- .8 Non-Hazardous solid waste disposal plan identifying methods and locations for solid waste disposal including clearing debris.
- .9 Air pollution control plan detailing provisions to assure that dust, debris, materials, and trash, do not become air borne and travel off project site.
- .10 Contaminant prevention plan that: identifies potentially hazardous substances to be used on job site; identifies intended actions to prevent introduction of such materials into air, water, or ground; and details provisions for compliance with Federal, Provincial, and Municipal laws and regulations for storage and handling of these materials.
- .11 Wastewater management plan that identifies methods and procedures for management and/or discharge of waste waters which are directly derived from construction activities, such as concrete curing water, clean-up water, dewatering of ground water, disinfection water, hydrostatic test water, and water used in flushing of lines.

1.4 FIRES

- .1 Fires and burning of rubbish on site not permitted.

1.5 DISPOSAL OF WASTES AND HAZARDOUS MATERIALS

- .1 Do not bury rubbish and waste materials on site. Dispose at approved landfill sites as specified in Section 01 74 21.
 - .2 Do not dispose of hazardous waste or volatile materials such as mineral spirits, paint thinner, oil or fuel into waterways, storm or sanitary sewers or waste landfill sites.
-

- .3 Store, handle and dispose of hazardous materials and hazardous waste in accordance with applicable federal and provincial laws, regulations, codes and guidelines.
- .4 Dispose of construction waste materials and demolition debris, resulting from work, at approved landfill sites only. Carry out such disposal in strict accordance with provincial and municipal rules and regulations. Separate out and prevent improper disposal of items banned from landfills.
- .5 Establish methods and undertake construction practices which will minimize waste and optimize use of construction materials. Separate at source all construction waste materials, demolition debris and product packaging and delivery containers into various recycling abilities of various materials and avoid disposal of debris at landfill site(s) in a "mixed state". Where recycling firms specializing in recycling of specific materials exist, transport such materials to the recycling facility and avoid disposal at landfill sites.
- .6 Communicate with landfill operator prior to commencement of work, to determine what specific construction, demolition and renovation waste materials have been banned from disposal at the landfill and at transfer stations.

1.6 DRAINAGE

- .1 Provide temporary drainage and pumping as necessary to keep excavations and site free from water.
 - .2 Do not pump water containing suspended materials into waterways, sewer or drainage systems.
 - .3 Control disposal or runoff of water containing suspended materials or other harmful substances in accordance with governing regulations and requirements.
 - .4 Pumped water must meet applicable federal, provincial and municipal standards before it can be discharged to a surface water body. If regulatory guidelines exceedances are noted, the Departmental Representative has the right to issue stop pumping instructions to the Contractor. Contractor will not be compensated for any delays associated with retrofitting equipment to meet guidelines.
 - .5 Provide control devices such as filter fabrics, sediment traps and settling ponds to control drainage and prevent erosion of adjacent lands. Maintain in good order for duration of work.
 - .6 Any water from the site that is contaminated is to be collected and disposed of properly.
-

1.7 PERMITS

- .1 All guidelines and instructions stated on permits must be strictly adhered to.

1.8 WORK ADJACENT TO WATERWAYS

- .1 Do not operate construction equipment in waterways.
- .2 Do not use waterway beds for borrow material.
- .3 Do not dump excavated fill, waste material or debris in waterways.
- .4 At borrow sites, design and construct temporary crossings to minimize erosion to waterways in strict conformance with provincial and federal environmental regulations.
- .5 Do not skid logs or construction materials across waterways.
- .6 Do not refuel any type of equipment within 100 m of a water body. Maintain equipment in good working condition with no fluid leaks, loose hoses or fittings.
- .7 Temporary diversion ditches, approved by the Departmental Representative are to be plastic lined.

1.9 POLLUTION CONTROL

- .1 Maintain temporary erosion and pollution control features installed under this contract.
 - .2 Control emissions from equipment and plant to local authorities emission requirements.
 - .3 Prevent sandblasting and other extraneous materials from contaminating air beyond application area, by providing temporary enclosures.
 - .4 Cover or wet down dry materials and rubbish to prevent blowing dust and debris. Provide dust control for temporary roads and around entire construction site.
 - .5 Maintain inventory of hazardous materials and hazardous waste stored on site. List items by product name, quantity and date when storage began.
 - .6 Have emergency spill response equipment and rapid clean-up kit, appropriate to work, at site. Locate adjacent to work and where hazardous materials are stored. Provide personal protective equipment as required for clean-up.
-

- .7 Report, to Federal and Provincial Department of the Environment, spills of petroleum and other hazardous materials as well as accidents having potential of polluting the environment. Also notify Departmental Representative and submit a written spill report to Departmental Representative within 24 hours of occurrence.
- .8 Provide a floating debris containment boom whenever any of the Contractors methods of work allow for the potential of floating debris.

1.10 WILDLIFE PROTECTION

- .1 Should nests of migratory birds in wetlands be encountered during work, immediately notify Departmental Representative for directives to be followed.
 - .1 Do not disturb nest site and neighbouring vegetation until nesting is completed.
 - .2 Minimize work immediately adjacent to such areas until nesting is completed.
 - .3 Protect these areas by following recommendations of Canadian Wildlife Service.

PART 2 - PRODUCTS

Not applicable

PART 3 - EXECUTION

Not applicable