

## **PART 1 - GENERAL**

### **1.1 SECTION INCLUDES**

- .1 Barriers.
- .2 Traffic Controls.

### **1.2 INSTALLATION AND REMOVAL**

- .1 Provide temporary controls in order to execute work expeditiously.
- .2 Remove from site all such work after use.

### **1.3 HOARDING**

- .1 Erect temporary site enclosure using new 1.2 m high snow fence wired to rolled steel “T” bar fence posts spaced at 2.4 m centres. Provide one lockable truck gate. Maintain fence in good repair.

### **1.4 GUARD RAILS AND BARRICADES**

- .1 Provide secure, rigid guard rails and barricades around open excavations.
- .2 Provide barricades along wharf structure when wheelguard is removed.
- .3 Provide as required by governing authorities.

### **1.5 ACCESS TO SITE**

- .1 Provide and maintain access to adjacent harbour facilities.

### **1.6 PUBLIC TRAFFIC FLOW**

- .1 Provide and maintain competent signal flag operators, traffic signals, barricades and flares, lights, or lanterns as required to perform work and protect the public.

**PART 1 - GENERAL**  
**(CONT'D)**

**1.7     FIRE ROUTES**

- .1     Maintain access to property including overhead clearances for use by emergency response vehicles.

**1.8     PROTECTION FOR OFF-SITE AND PUBLIC PROPERTY**

- .1     Protect surrounding private and public property from damage during performance of work.
- .2     Be responsible for damage incurred.