


1 PARTIAL SEVENTH FLOOR RCP  
Scale 1:100



2 FOURTH FLOOR RCP  
Scale 1:100

#### LEGEND

- EXISTING LIGHTS TO BE REMOVED, STORED AND PREPARED FOR RE-INSTALLATION IN RENOVATION. REFER TO ELECT.
- EXISTING RE-INSTALLED LIGHTS. REFER TO ELECT.
- EXISTING LIGHTS TO REMAIN. REFER TO ELECT.
- EXISTING MECHANICAL LINEAR GRILL/LOUVER TO REMAIN
- NEW GYPSUM WALLBOARD
- EXISTING ACoustic CEILING TILE AND GRID TO BE DEMOLISHED. SALVAGE A.C.T. SUITABLE FOR RENOVATION FOR INSTALL IN RENOVATION.
- EXISTING ACoustic CEILING TILE AND GRID TO REMAIN. CONTRACTOR TO REMOVE AND REINSTALL TILE AS REQUIRED FOR CONSTRUCTION.
- NEW ACoustic CEILING TILE AND GRID
- 1 HR FIRE RESISTANCE RATING
- NEW MECHANICAL DIFFUSER - REFER TO MECH
- NEW MECHANICAL RETURN - REFER TO MECH
- LIGHT LEVEL SENSOR / OCCUPANCY SENSOR - REFER TO ELECT.
- EXISTING SPRINKLER - REFER TO MECH.
- NEW/REVISED SPRINKLER - REFER TO MECH. FOR ALL NEW/REVISED LOCATIONS

#### GENERAL NOTES

- CONTRACTOR TO REVISE SPRINKLER LINES TO ACCOMMODATE NEW LAYOUT. REFER TO MECH.
- CONTRACTOR TO PROVIDE FIRESTOPPING IN ALL NEW AND EXISTING PENETRATIONS IN FIRE RATED WALLS AND FLOOR ASSEMBLIES
- REFER TO A3.2 FOR FINISHES OF GWB CEILING

#### EXISTING EQUIPMENT GENERAL NOTES

GENERAL CONTRACTOR TO ASSUME RESPONSIBILITY FOR THE REMOVAL, RELOCATION AND RE-INSTALLATION OF THE FOLLOWING EQUIPMENT CURRENTLY LOCATED AT 25 FORKS MARKET ROAD, 4TH FLOOR.

**FOR PROJECTORS:** GENERAL CONTRACTOR TO ASSUME RESPONSIBILITY FOR THE REMOVAL, RELOCATION AND RE-INSTALLATION OF EXISTING CEILING-MOUNTED DATA PROJECTORS (THREE UNITS) CURRENTLY LOCATED AT 25 FORKS MARKET ROAD, 4TH FLOOR. CONTRACTOR TO ASSUME NEW MOUNTING BRACKETS WILL BE REQUIRED FOR INSTALLATION. PHOTOS OF THE EXISTING PROJECTORS AND MOUNTING BRACKETS CAN BE FOUND IN THE APPENDIX OF THE SPECIFICATION MANUAL. SHOP DRAWINGS TO BE SUBMITTED FOR THE NEW MOUNTING BRACKETS.

**FOR PROJECTOR SCREENS:** GENERAL CONTRACTOR TO ASSUME RESPONSIBILITY FOR THE REMOVAL, RELOCATION AND RE-INSTALLATION OF EXISTING MANUAL PULL-DOWN PROJECTOR SCREENS (TWO UNITS) CURRENTLY LOCATED AT 25 FORKS MARKET ROAD, 4TH FLOOR. CONTRACTOR TO ASSUME NEW MOUNTING BRACKETS WILL BE REQUIRED FOR INSTALLATION. PHOTOS OF THE EXISTING PROJECTOR SCREENS CAN BE FOUND IN THE APPENDIX OF THE SPECIFICATION MANUAL. SHOP DRAWINGS TO BE SUBMITTED FOR THE MOUNTING OF THE SCREENS.

**FOR EXISTING WALL-MOUNTED SPEAKERS:** GENERAL CONTRACTOR TO ASSUME RESPONSIBILITY FOR THE REMOVAL, RELOCATION AND RE-INSTALLATION OF EXISTING WALL-MOUNTED AUDIO SPEAKER MONITORS (THREE PAIRS) CURRENTLY LOCATED AT 25 FORKS MARKET ROAD, 4TH FLOOR. SPEAKERS TO BE CEILING MOUNTED AT NEW LOCATION. CONTRACTOR TO ASSUME NEW MOUNTING BRACKETS WILL BE REQUIRED FOR INSTALLATION. PHOTOS OF THE EXISTING SPEAKERS CAN BE FOUND IN THE APPENDIX OF THE SPECIFICATION MANUAL.

**FOR EXISTING CEILING CCTV CAMERA:** GENERAL CONTRACTOR TO ASSUME RESPONSIBILITY FOR THE REMOVAL, RELOCATION AND RE-INSTALLATION OF EXISTING CEILING MOUNTED CCTV CAMERAS (SIX UNITS) CURRENTLY LOCATED AT 25 FORKS MARKET ROAD, 4TH FLOOR. CAMERAS TO BE CEILING MOUNTED AT NEW LOCATION. CONTRACTOR TO ASSUME NEW MOUNTING BRACKETS WILL BE REQUIRED FOR INSTALLATION.

**FOR EXISTING WALL MOUNTED CCTV TELEVISIONS:** GENERAL CONTRACTOR TO ASSUME RESPONSIBILITY FOR THE REMOVAL, RELOCATION AND RE-INSTALLATION OF EXISTING CEILING MOUNTED CCTV TELEVISIONS (FIVE UNITS) CURRENTLY LOCATED AT 25 FORKS MARKET ROAD, 4TH FLOOR. TELEVISIONS TO BE WALL MOUNTED AT NEW LOCATION. CONTRACTOR TO ASSUME NEW MOUNTING BRACKETS WILL BE REQUIRED FOR INSTALLATION.


**FOR EXISTING CEILING AND WALL MOUNTED STROBE LIGHTS:** GENERAL CONTRACTOR TO ASSUME RESPONSIBILITY FOR THE REMOVAL, RELOCATION AND RE-INSTALLATION OF EXISTING CEILING MOUNTED STROBE LIGHTS (TWO UNITS) CURRENTLY LOCATED AT 25 FORKS MARKET ROAD, 4TH FLOOR. STROBE LIGHTS TO BE WALL MOUNTED AT NEW LOCATION. CONTRACTOR TO ASSUME NEW MOUNTING BRACKETS WILL BE REQUIRED FOR INSTALLATION.

**NOTE:**  
1. GENERAL CONTRACTOR TO SUPPLY NEW CCTV CAMERAS, TELEVISIONS AND STROBE LIGHTS TO MATCH EXISTING TO MEET TOTAL QUANTITY (EXISTING RELOCATED AND NEW SHOWN ON DRAWINGS - REFER TO A1.2, A2.1 AND ELECTRICAL).  
2. AT 25 FORKS MARKET, CAP OR INSTALL BLANK PLATES TO WIRE OR JUNCTION BOX; ENSURE NO WIRES ARE HANGING OR EXPOSED - REFER TO ELECT.  
3. ENSURE TO PROTECT EQUIPMENT DURING TRANSPORT

#### KEYNOTES

- NOT USED
- NOT USED
- EXISTING POTLIGHTS TO REMAIN
- NEW ACoustic CEILING TILE AND GRID - REFER TO SPEC
- NOT USED
- REINSTALLED EXISTING MECHANICAL DIFFUSER - REFER TO MECH
- NEW WALL MOUNTED STROBE LIGHT. SUPPLY AND INSTALL IN CONTRACT. REFER TO ELECT. CONFIRM EXACT LOCATION AND HEIGHT WITH DEPARTMENTAL REPRESENTATIVE. REFER TO EXISTING EQUIPMENT GENERAL NOTES
- EXISTING CEILING IN WASHROOM TO REMAIN
- EXISTING CEILING IN LOBBY, STAIR AND VESTIBULE TO REMAIN
- EXISTING GWB CEILING TO REMAIN. PATCH AND MAKE GOOD. PAINT
- PROVIDE NEW ACoustic CEILING TILES IN LOCATION OF DAMAGED PANEL DUE TO DEMOLISHED LIGHT FIXTURE
- NEW EXHAUST DUCT - REFER TO MECH.
- NEW ACoustic CEILING TILE AND GRID AS REQUIRED FROM DEMOLITION TO NEW WALL IN ROOM 708
- NEW OR OWNER SUPPLIED CEILING MOUNTED STROBE LIGHT. REFER TO ELECT.
- NEW OR OWNER SUPPLIED CCTV CAMERA. SUPPLY AND INSTALL IN CONTRACT. REFER TO ELECT. CONFIRM EXACT LOCATION AND HEIGHT WITH DEPARTMENTAL REPRESENTATIVE. REFER TO EXISTING EQUIPMENT GENERAL NOTES

- NEW SPEAKER - REFER TO ELECT.
- EXISTING CEILING TILES TO REMAIN. CONTRACTOR TO REPLACE EXISTING DAMAGED TILES WITH EXISTING REMOVED CEILING TILES CALLED UP AS NOTE. 14 ON 1 AND 2A2.1. CONTRACTOR TO REPLACE CEILING GRID AS REQUIRED.
- NOT USED
- OWNER SUPPLIED PROJECTOR. INSTALLATION IN CONTRACT. REFER TO ELECT. CONFIRM EXACT LOCATION WITH DEPARTMENTAL REPRESENTATIVE. REFER TO EXISTING EQUIPMENT GENERAL NOTES
- OWNER SUPPLIED PROJECTOR SCREEN. INSTALLATION IN CONTRACT. CONFIRM EXACT LOCATION WITH DEPARTMENTAL REPRESENTATIVE. REFER TO EXISTING EQUIPMENT GENERAL NOTES



3 BULKHEAD DETAIL  
Scale 1:10

5		
4		
3	ISSUED FOR CONSTRUCTION	FEB. 3, 2015
2	99% SUBMISSION	DEC. 18, 2014
1	DESIGN DEVELOPMENT SUBMISSION	NOV. 6, 2014
0	SCHEMATIC DESIGN SUBMISSION	SEPT. 25, 2014
Revision	Description	Date
Client		client

### PUBLIC WORKS AND GOVERNMENT SERVICES CANADA

Project  
**INTERIOR LEASE FIT-UP FOR  
CIC RELOCATION TO  
VICTORY BUILDING, WINNIPEG**  
**269 MAIN STREET  
WINNIPEG, MANITOBA**

Designed by  
**TC**  
Compu par

Drawn by  
**TC**  
Dessiné par

Approved by  
**GG**  
Approuvé par

PWGSC Project Manager  
**John Allbin**  
Administrateur de Projets TPSGC

Drawing title  
**FOURTH FLOOR RCP  
SEVENTH FLOOR RCP**  
Titre du dessin

Project no./No. du projet	Drawing no./No. du dessin	Revision no.
<b>R.055488.006</b>	<b>A2.2</b> OF	<b>3</b>