



1. THE CONTRACTOR SHALL IMPLEMENT BEST MANAGEMENT PRACTICES, TO PROVIDE FOR PROTECTION OF THE AREA DRAINAGE SYSTEM AND TO PREVENT EROSION DURING CONSTRUCTION ACTIVITIES. THE CONTRACTOR ACKNOWLEDGES THAT FAILURE TO IMPLEMENT APPROPRIATE EROSION AND SEDIMENT CONTROL MEASURES MAY BE SUBJECT TO PENALTIES IMPOSED BY ANY APPLICABLE REGULATORY AGENCY.
2. THE CONTRACTOR SHALL SUPPLY, INSTALL AND MAINTAIN A FILTER CLOTH "CATCH" ACROSS ALL HW/CB LIDS TO PREVENT SEDIMENTATION AND CLOGGING OF THE DRAINAGE STRUCTURES. ANY SEDIMENTS/GRANULARS ENTERING THE STRUCTURES AND SEWERS SHALL BE IMMEDIATELY REMOVED.
3. THE CONTRACTOR SHALL SUPPLY, INSTALL AND MAINTAIN SILT FENCING AND ROCK CATCHMENT FENCE AND AS SHOWN ON THE EROSION AND SEDIMENT CONTROL PLAN DRAWING, TO PREVENT SEDIMENT AND/OR ROCK FROM AREAS DISTURBED BY CONSTRUCTION FROM ENTERING INTO THE RIVER OR LEAVING THE SILT AND ROCK CATCHMENT FENCE. THE CONTRACTOR SHALL, PER DETAILS, ALL EROSION PROTECTION ALL SEDIMENT AND ROCK PROTECTION MEASURES SHALL BE INSPECTED DAILY AND AFTER EVERY RAINFALL. THEY SHALL BE MAINTAINED, CLEANED, CUT AND REPLACED AS REQUIRED. ANY DAMAGE, BUILD UP OR INCORRECT INSTALLATION IS OBSERVED BY THE CONTRACTOR OR AS REQUIRED BY THE DEPARTMENT REPRESENTATIVE, OR CONSERVATION AUTHORITY, CLEAN OUT AND REPAIRS SHALL BE MAINTAINED UNTIL CONSTRUCTION IS COMPLETE.