

**RETURN BIDS TO:**  
**RETOURNER LES SOUMISSIONS À:**  
**Bid Receiving - PWGSC / Réception des soumissions**  
**- TPSGC**  
**11 Laurier St./11 rue Laurier**  
**Place du Portage, Phase III**  
**Core 0B2 / Noyau 0B2**  
**Gatineau, Québec K1A 0S5**

**SOLICITATION AMENDMENT**  
**MODIFICATION DE L'INVITATION**

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

**Comments - Commentaires**  
Ce document comporte une exigence en matières de sécurité.  
This document contains a Security Requirement.

**Vendor/Firm Name and Address**  
**Raison sociale et adresse du**  
**fournisseur/de l'entrepreneur**

**Issuing Office - Bureau de distribution**  
Construction Services Division/Division des services  
de construction  
11 Laurier St./11 Rue Laurier  
3C2, Place du Portage  
Phase III  
Gatineau, Québec K1A 0S5

<b>Title - Sujet</b> North Perimeter Wall Rehabilitation	
<b>Solicitation No. - N° de l'invitation</b> EP750-151857/A	<b>Amendment No. - N° modif.</b> 001
<b>Client Reference No. - N° de référence du client</b> 20151857	<b>Date</b> 2015-04-09
<b>GETS Reference No. - N° de référence de SEAG</b> PW-\$\$\$FG-350-67051	
<b>File No. - N° de dossier</b> fg350.EP750-151857	<b>CCC No./N° CCC - FMS No./N° VME</b>
<b>Solicitation Closes - L'invitation prend fin</b> <b>at - à 02:00 PM</b> <b>on - le 2015-04-23</b>	<b>Time Zone</b> <b>Fuseau horaire</b> Eastern Daylight Saving Time EDT
<b>F.O.B. - F.A.B.</b> <b>Plant-Usine:</b> <input type="checkbox"/> <b>Destination:</b> <input type="checkbox"/> <b>Other-Autre:</b> <input type="checkbox"/>	
<b>Address Enquiries to: - Adresser toutes questions à:</b> Séguin, Martine	<b>Buyer Id - Id de l'acheteur</b> fg350
<b>Telephone No. - N° de téléphone</b> (819) 956-4975 ( )	<b>FAX No. - N° de FAX</b> (819) 956-8335
<b>Destination - of Goods, Services, and Construction:</b> <b>Destination - des biens, services et construction:</b> Colline parlementaire - Parliament Hill Mur du périmètre nord- North Perimeter Wall 111 rue Wellington Street Ottawa, Ontario	

**Instructions: See Herein**

**Instructions: Voir aux présentes**

<b>Delivery Required - Livraison exigée</b>	<b>Delivery Offered - Livraison proposée</b>
<b>Vendor/Firm Name and Address</b> <b>Raison sociale et adresse du fournisseur/de l'entrepreneur</b>	
<b>Telephone No. - N° de téléphone</b> <b>Facsimile No. - N° de télécopieur</b>	
<b>Name and title of person authorized to sign on behalf of Vendor/Firm</b> <b>(type or print)</b> <b>Nom et titre de la personne autorisée à signer au nom du fournisseur/</b> <b>de l'entrepreneur (taper ou écrire en caractères d'imprimerie)</b>	
<b>Signature</b>	<b>Date</b>

Solicitation No. - N° de l'invitation

EP750-151857/A

Amd. No. - N° de la modif.

001

Buyer ID - Id de l'acheteur

fg350

Client Ref. No. - N° de réf. du client

20151857

File No. - N° du dossier

fg350EP750-151857

CCC No./N° CCC - FMS No/ N° VME

---

**THIS AMENDMENT NUMBER 001 IS BEING ISSUED FOR THE FOLLOWING:**

**1. Delete in its entirety:**

Bid and Acceptance Form including Appendix 1 (Combined Price Form, 2 pages) and replace with the revised Bid and Acceptance Form including Appendix 1 (2 pages).

**2. Issue Addendum number 1.**

**ALL OTHER TERMS AND CONDITIONS REMAIN UNCHANGED**

Solicitation No. - N° de l'invitation

EP750-151857/A

Amd. No. - N° de la modif.

001

Buyer ID - Id de l'acheteur

fg350

Client Ref. No. - N° de réf. du client

20151857

File No. - N° du dossier

fg350EP750-151857

CCC No./N° CCC - FMS No/ N° VME

---

## AMENDMENT 001

Solicitation No. - N° de l'invitation  
EP750-151857/A  
Client Ref. No. - N° de réf. du client

Amd. No. - N° de la modif.  
001  
File no. - N° du dossier  
FG350 EP750-151857

Buyer ID - Id de l'acheteur  
FG350  
CCC No./N° CCC - FMS No./N° VME

## BID AND ACCEPTANCE FORM (BA)

### BA01 IDENTIFICATION

R.011800.001 – Parliament Hill, North Perimeter Wall, Phase 3 Rehabilitation, 111 Wellington Street,  
Ottawa, Ontario

### BA02 BUSINESS NAME AND ADDRESS OF BIDDER

Name: \_\_\_\_\_

Address: \_\_\_\_\_

Telephone: \_\_\_\_\_ Fax: \_\_\_\_\_ PBN: \_\_\_\_\_

### BA03 THE OFFER

The Bidder offers to Canada to perform and complete the Work for the above named project in accordance with the Bid Documents for the **TOTAL BID AMOUNT INDICATED IN APPENDIX 1**.

### BA04 BID VALIDITY PERIOD

The bid shall not be withdrawn for a period of **sixty (60) days** following the date of solicitation closing.

### BA05 ACCEPTANCE AND CONTRACT

Upon acceptance of the Contractor's offer by Canada, a binding Contract shall be formed between Canada and the Contractor. The documents forming the Contract shall be the contract documents identified in Contract Documents (CD).

### BA06 CONSTRUCTION TIME

The Contractor shall perform and complete the Work within **fifty six (56) weeks** from the date of notification of acceptance of the offer.

### BA07 BID SECURITY

The Bidder is enclosing bid security with its bid in accordance with GI08 - R2710T - General Instructions - Construction Services - Bid Security Requirements.

### BA08 SIGNATURE

\_\_\_\_\_  
Name and title of person authorized to sign on behalf of Bidder (Type or print)      Email address

\_\_\_\_\_  
Signature      Date

## APPENDIX 1

### COMBINED PRICE FORM (2 pages)

- 1) The prices per unit shall govern in establishing the Total Extended Amount. Any arithmetical errors in this Appendix will be corrected by Canada.
- 2) Canada may reject the bid if any of the prices submitted do not reasonably reflect the cost of performing the part of the work to which that price applies.

#### LUMP SUM

The Lump Sum Amount designates Work to which a Lump Sum Arrangement applies.

- (a) Work included in the Lump Sum Amount represents all work not included in the unit price table.

<b>LUMP SUM AMOUNT (LSA)</b> Excluding applicable tax(es)
--

#### UNIT PRICE TABLE

The Unit Price Table designates Work to which a Unit Price Arrangement applies.

- (a) Work included in each item is as described in the referenced specification section.  
(b) The Price per Unit shall not include any amounts for Work that is not included in that unit price item.

Item	Specification Reference	Class of Labour, Plant or Material	Unit of Measurement	Item Estimated Quantity (EQ)	Price per Unit (PU) Excluding applicable tax(es)	Extended amount (EQ) Excluding applicable tax(es)
01	02 41 16	<b>Removal of hazardous construction waste.</b>	m <sup>3</sup>	120		
02	03 10 00 / 03 20 00 / 03 30 00	<b>Foundation Detail on Fill.</b>	lm	20		
03	03 10 00 / 03 20 00 / 03 30 00	<b>Dowelled Foundation Detail.</b>	lm	80		
04	04 03 07	<b>Historic Masonry Repointing (Shallow Rake and Repoint).</b>	lm	500		
05	04 03 07	<b>Historic Masonry Repointing (Deep Rake and Repoint).</b>	lm	300		
06	04 03 41	<b>Historic Repair of Stone (Resetting of Dressed Stone).</b>	ea	25		
07	04 03 41	<b>Historic Repair of Stone (resetting of Rubble Stone).</b>	m <sup>2</sup>	15		
08	04 03 41	<b>Historic Repair of Stone (Fractured, In-Situ).</b>	ea	10		
09	04 03 41	<b>Historic Repair of Stone (Fractured, Removed).</b>	ea	10		
10	04 03 41	<b>Historic Repair of Stone (Cracked).</b>	ea	10		
11	04 03 41	<b>Historic Repair of Stone (Mortar).</b>	ea	10		



Solicitation No. - N° de l'invitation  
**EP750-151857/A**  
 Client Ref. No. - N° de réf. du client

Amd. No. - N° de la modif.  
**001**  
 File no. - N° du dossier  
 FG350 EP750-151857

Buyer ID - Id de l'acheteur  
**FG350**  
 CCC No./N° CCC - FMS No./N° VME

Item	Specification Reference	Class of Labour, Plant or Material	Unit of Measurement	Item Estimated Quantity (EQ)	Price per Unit (PU) Excluding applicable tax(s)	Extended amount (EQ) Excluding applicable tax(s)
12	04 03 41	Historic Repair of Stone (Dutchman).	ea	10		
13	04 03 41	Historic Repair of Stone (Pin Removal).	ea	10		
14	04 03 42	Historic Repair of Stone (Replacement Rubble).	m <sup>2</sup>	15		
15	04 03 43	Historic – Dismantling Stone Masonry.	m <sup>2</sup>	15		
16	31 23 33	Weathered Rock Removal.	m <sup>3</sup>	180		
17	31 23 33	Non-weathered Rock Removal.	m <sup>3</sup>	80		
18	31 23 33	Soil Excavation.	m <sup>3</sup>	20		
19	31 23 33	Engineered Fill.	m <sup>3</sup>	60		
20	31 23 33	Contaminated Soil Removal.	m <sup>3</sup>	1500		
21	31 23 33	Unshrinkable Fill.	m <sup>3</sup>	60		
22	32 13 11	Supply of Type 2 Limestone Pavers – Size 20	units	200		
23	32 13 11	Supply of Type 2 Limestone Pavers – Size 21	units	340		
24	32 13 11	Supply of Type 2 Limestone Pavers – Size 22	units	90		
25	32 13 11	Supply of Type 2 Limestone Pavers – Size 23	units	90		
26	32 13 11	Supply of Type 2 Limestone Pavers – Size 24	units	255		
27	32 13 11	Supply of Type 2 Limestone Pavers – Size 25	units	90		
28	32 13 11	Supply of Type 2 Limestone Pavers – Size 26	units	6		
29	32 13 11	Supply of Type 2 Limestone Pavers – Size 27	units	6		
30	32 13 11	Supply of Type 2 Limestone Pavers – Size 28	units	6		
31	32 13 11	Supply of Type S Limestone Pavers at Summer Pavilion	units	185		
32	32 13 18	Supply of Limestone Borders at Summer Pavilion – Type 1	units	40		
<b>TOTAL EXTENDED AMOUNT (TEA)</b>						
Excluding applicable tax(s)						

<b>TOTAL BID AMOUNT (LSA +TEA)</b>		
Excluding applicable tax(s)		

Solicitation No. - N° de l'invitation  
EP750-151857/A  
Client Ref. No. - N° de réf. du client

Amd. No. - N° de la modif.  
001  
File no. - N° du dossier  
FG350 EP750-151857

Buyer ID - Id de l'acheteur  
FG350  
CCC No./N° CCC - FMS No./N° VME

---

## **ADDENDUM 1**

## **ADDENDUM No. 1**

### **PROJECT NO. R.011800**

---

**The following changes in the bid documents are effective immediately. This addendum will form part of the contract documents.**

The purpose of this addendum is to remove installation of Type 2 limestone pavers, type S pavers, limestone borders, trench drains and sub-drainage piping West of Pier 44 and remove installation of type S pavers at stairs leading up to Summer Pavilion. Supply and installation of type S pavers at Pier 44 remain in the contract. Include the supply of Type 2 and Type S limestone pavers and limestone borders for the area around the Summer Pavilion under Unit Prices. The project mobilization area is reduced to exclude the area around the Summer Pavilion – see revised drawing A100.

## **DRAWINGS**

### **1. A100 – Mobilization Plan**

- 1.1. **DELETE** drawing and **REPLACE WITH** Drawing A100 – Mobilization Plan; Issued for Addendum 1, dated April 1, 2015.

### **2. C101 – Drainage Plan. Piers 40-45**

- 2.1. **DELETE** notes 1.2, 1.3, 1.4, 1.5, 1.6.
- 2.2. Cap weeping tile approximately 1m to the West of Pier 45.

### **3. L101 – Existing Conditions & Demolition Plan. Summer Pavilion to 0+110**

- 3.1. **DELETE** notes 1, 22, 24, 25 in detail 1/L101

### **4. L103 – Landscape Plan. Summer Pavilion to 0+110**

- 4.1. **DELETE** limestone pavers type 2 installation West of Pier 44.
- 4.2. **DELETE** type S pavers installation at stairs leading to Summer Pavilion. Type S pavers at Pier 44 to remain (note 7 – Detail 1/L103).



- 4.3. **DELETE** limestone border installation West of Pier 44.
- 4.4. **DELETE** legend for Limestone pavers Type 2
- 4.5. Make good fill and asphalt West of Pier 44.
- 5. **L105 – Grading & Drainage Plan. Summer Pavilion to 0+110**
  - 5.1. **DELETE** all grading information (elevation points and slopes) West of Pier 45.
  - 5.2. **DELETE** trench drains west of Pier 45 (note 1 - Detail 1/L105).
- 6. **L401 – Construction Details**
  - 6.1. **DELETE** detail 14/L401
  - 6.2. **DELETE** detail 7I/L401

## **SPECIFICATIONS**

- 1. Section 01 00 10 – General Instructions
  - 1.1. **ADD** new article 1.7.9 as follows:
    - .9 The Departmental Representative may request coordination of activities with other contractors working in the near vicinity of the project. The Contractor should expect minor delays to accommodate these coordination activities and every effort should be made to re-deploy resources to reduce the impact of these delays. The Departmental Representative and Contractor will determine on a case-by-case basis if coordination activities constitute a minor delay. It will be assumed that minor delays will not affect the overall schedule or cost of the project.
  - 1.2. **DELETE** article 1.17.1 **and REPLACE WITH:**
    - .1 Plan to mobilize and demobilize the work in a minimum of 2 phases: Phase 1: from contract award to September 1, 2015; Phase 2: September 1, 2015 to end of contract.
- 2. Section 01 32 16 Construction Progress Schedule - Critical Path Method (CPM)
  - 2.1. **DELETE** article 1.9.1.1 **and REPLACE WITH:**
    - .1 Show two stages of mobilization:
      - .1 Phase 1: Contract award to Sept 1, 2015.

.2 Phase 2: Sept 1, 2015 to end of contract.

3. Section 01 52 00 Construction Facilities

3.1. **DELETE** article 1.6 entirely.

4. Section 01 56 00 Temporary Barriers and Enclosures

4.1. **DELETE** article 1.3.4 **and REPLACE WITH:**

.4 Provide shop drawings and written plan for protection and shoring of the monuments and Perimeter Wall in the work area for review and approval of the Departmental Representative, including how the protection will be implemented and materials used.

4.2. **DELETE** article 1.6.1 **and REPLACE WITH:**

.1 Provide protective enclosures around all monuments and lamp post bases within the Construction Site.

5. Section 01 74 11 – Cleaning

5.1. **DELETE** article 1.4.22 entirely.

6. Section 32 13 11 – Limestone Pavers

6.1. **ADD** new article 1.2 Unit Prices as follows:

.1 Unit Prices

.1 Unit Prices apply to the supply and installation of Type 2 and Type S limestone pavers in the area around the Summer Pavilion – West of the S-type pavers at Pier 44. The unit price will include all costs necessary to complete the work including supplying materials and delivery as described herein and reflected in contract.

.1 Supply of Type 2 Limestone Pavers: Supply limestone pavers in the dimensions, quantities and finishes specified. Include transport to Departmental Representative storage facility within the NCA.

.2 Supply of Type S Limestone Pavers at Summer Pavilion: Supply limestone pavers in the dimensions, quantities and finishes specified. Include transport to Departmental Representative storage facility within the NCA.

.2 Measurement and Payment

.1 The measurement and payment of supply of Type 2 limestone pavers will be on a unit price basis and will include all costs associated with supplying materials, and executing work as described herein and reflected in contract. All other limestone paver work is included in the lump sum price.

.2 The work for this Section at the Type 2 limestone pavers will be paid based on the actual quantities measured on site and the unit prices stated in the Bid and Acceptance Form.

6.2. **DELETE** article 2.1.4 **and REPLACE WITH:**

.4. Oversized pavers (Type 2)

.1 Size 26 : 150 x 697 x 697 mm, Finish A.

.2 Size 27 : 150 x 697 x 1297 mm, Finish B.

.3 Size 28 : 150 x 697 x 997 mm, Finish C.

.4 All Oversized Type 2 pavers shall have a 3mm chamfer on the four edges of their top side.

6.3. **DELETE** article 2.1.5 **and REPLACE WITH:**

.5 Across path (Soldiers)

.1 Size S: 100 x 297 x 495 mm, Finish B.

.2 All "Size S" pavers shall have a 1mm chamfer on the four edges of their top side.

7. Section 32 13 18 – Limestone Borders

7.1. **ADD** new article 1.2 Unit Prices as follows:

.1 Unit Prices

.1 Unit Prices apply to the supply and installation of limestone borders in the area around the Summer Pavilion – West of the S-type pavers at Pier 43. The unit price will include all costs necessary to complete the work including supplying materials and delivery as described herein and reflected in contract.

.1 Supply of Limestone Borders at Summer Pavilion: Supply limestone borders in the dimensions, quantities and finishes specified. Include transport to Departmental Representative storage facility within the NCA.

.2 Measurement and Payment

.1 The measurement and payment of supply of limestone borders around the Summer Pavilion will be on a unit price basis and will include all costs associated with supplying materials, and executing work as described herein and reflected in contract. All other limestone border work is included in the lump sum price.

.2 The work for this Section at the limestone borders around the Summer Pavilion will be paid based on the actual quantities measured on site and the unit prices stated in the Bid and Acceptance Form.

**ATTACHMENTS:**

Unit Price Table R1.

Drawing A100 – Mobilization Plan. Issued for Addendum 1, dated April 1, 2015.

**END OF ADDENDUM**