SCHEDULE 1 - LABOUR, MATERIAL PLANT AND/OR EQUIPMENT

Form of Tender Contract Package 1 - Repair to Wharf Substructure Components									
ltem	Description	Class of Labour, Materials, Plant and/or Equip.	Quantity	Unit	Unit Price	Amount			
1	Mobilization & Demobilization		1	LS					
1.0 Lions Gate Dock Repairs									
1.1	Replace Cap and Install New Posts on CIP Sonatube Footings		1	LS					
1.2	Fresh Head and Install Corbel		1	LS					
1.3	Fresh Head and Install Double Corbel		1	LS					
1.4	Install Steel Bands		2	Each					
					Subtotal				
2.0 Lions (Gate Dock Concrete Beam Repair								
2.1	Option A - not jacking the beam								
2.1.1	Investigation, Survey, and Corbel Shop Drawing Preparation		1	LS					
2.1.2	Corbel Material Supply and Fabrication		1	LS					
2.1.3	Corbel Shipping and Erection		1	LS					
2.1.5	Removal of Cracked concrete and		-						
2.1.4	corrosion damaged rebar		1	LS					
2.1.5	Repair interface preparation		1	LS					
2.1.6	Replacement of corroded rebar		1	LS					
2.1.7	Forming and grouting for repair		1	LS					
2.1.1	ronning and groating for repair		1		Subtotal				
2.2	Option B - jacking the beam				Subtotal				
2.2.1	Investigation, Survey, and Corbel Shop Drawing Preparation		1	LS					
2.2.2	Corbel Material Supply and Fabrication		1	LS					
2.2.2	Corbel Shipping and Erection		1	LS					
2.2.0	Removal of Cracked concrete and		-						
2.2.4	corrosion damaged rebar		1	LS					
2.2.5	Repair interface preparation		1	LS					
2.2.6	Replacement of corroded rebar		1	LS					
2.2.7	Forming and grouting for repair		1	LS					
			-		Subtotal				
2.3	Provisional Item								
2.3.1	Concrete beam repair crack injection		1	LS					
3.0 Bridge									
3.1	Install Channel Patch		1	LS					
3.2	Move Large Boulder, Install Steel Angle Brackets w/ Lag Bolts to Prevent Shifting		1	LS					
3.2	Install Steel Bands		7	LS					
3.4	Fill Undermined Concrete Abutment w/		1	LS					
	CIP Concrete								

CMHC Granville Island – Repair of Marine Works ITT, File #201500863 Schedule 1 – Labour, Material Plant and/or Equipment

4.0 West	Dock								
4.1	Install Treated Timber Shims		1	LS					
4.2	Install Steel Bands		11	Each					
4.3	Pile/cap connection		1	Each					
4.4	Fresh Head and Install Double Corbel		2	Each					
4.5	Replace Pile		5	Each					
	·				Subtotal				
5.0 Public	c Market Wharf and Trestle								
5.1	Install Steel Bands		1	LS					
5.2	Fill Undermined Concrete Abutment w/ CIP Concrete		1	LS					
5.3	Fresh Head and Install Additional Corbel		1	LS					
	•				Subtotal				
6.0 Public Market Boardwalk and Sheet Pile Walls									
6.1	Replace Pedestals		1	LS					
6.2	Restore Riprap Slope Protection in Front of Boardwalk		1	LS					
6.3	Restore Riprap Slope Protection in Front of Stairs		1	LS					
					Subtotal				
7.0 North	neast Seawall and Boardwalk								
7.1	Install Steel Plate Patch - Pile 79		1	LS					
7.2	Install Steel Plate Patch Pile - 106		1	LS					
				•	Subtotal				
8.0 Pelica	an Bay Marina Boardwalk Removal								
8.1	Boardwalk Removal		1	LS					
8.2	Lentil Sign Relocation		1	LS					
				-	Subtotal				
9.0 Catho	dic Protection								
9.1	Cathodic Protection of All Outboard Pipe Piles		165	Each					
	•				Subtotal				
10.0 Mari	itime Market Boardwalk								
10.1	Remove riprap and fill that is in conflict with existing dock.		1	LS					
	Interesting over.		1	1	Subtotal				
	6h1	Domoine visione O		llone Cree					
Subtotal Repairs, using Option A for Lions Gate Beam Repair Subtotal Repairs, using Option B for Lions Gate Beam Repair									
	Subtotal	Repairs, using U		cions Gate	e beam kepair				
Contingency (15%) Option A									
Contingency (15%) Option A Contingency (15%) Option B									
Total - Option A									
				Te	otal - Option B				
Total - Decidentificant									
Total - Provisional Items									