

PART 1 - GENERAL

1.1 SUMMARY

- .1 Related Requirements
 - .1 Measurement Procedures.
 - .1 Measure removal of exterior wall materials in square metres.
 - .2 Payment for disposal and restoration will be included in above removal items.
 - .3 Measure removal of waste from the site in tonnes.
 - .2 Measurement Procedures.
 - .1 Measure removal of exterior wall materials in square metres.
 - .2 Payment for disposal and restoration will be included in above removal items.
 - .3 Measure removal of waste from the site in tonnes.

1.2 REFERENCES

- .1 Health Canada/Workplace Hazardous Materials Information System (WHMIS).
 - .1 Material Safety Data Sheets (MSDS).
- .2 Transport Canada (TC).
 - .1 Transportation of Dangerous Goods Act, 1992 (TDGA), c. 34.

1.3 DEFINITIONS

- .1 Hazardous Materials: dangerous substances, dangerous goods, hazardous commodities and hazardous products, may include but not limited to: asbestos PCB's, CFC's, HCFC's poisons, corrosive agents, flammable substances, ammunition, explosives, radioactive substances, or other material that can endanger human health or well being or environment if handled improperly.
- .2 Waste Audit (WA): detailed inventory of materials in building. Indicates quantities of reuse, recycling and

landfill.

.1 Involves quantifying by volume/weight amounts of materials and wastes generated during construction, demolition, deconstruction, or renovation project.

.2 Indicates quantities of reuse, recycling and landfill.

.3 Waste Management Coordinator (WMC): contractor representative responsible for supervising waste management activities as well as coordinating related, required submittal and reporting requirements.

.4 Waste Reduction Workplan (WRW): written report which addresses opportunities for reduction, reuse, or recycling of materials. WRW is based on information acquired from WA.

1.4 ACTION AND INFORMATIONAL SUBMITTALS

.1 Submittals in accordance with Section 01 33 00 - Submittal Procedures.

.2 Hazardous Materials: provide description of Hazardous Materials and Notification of Filing with proper authorities prior to beginning of Work as required.

.3 Waste Reduction Workplan: prior to beginning of Work on site submit detailed Waste Reduction Workplan in accordance with Section 01 74 21 - Construction/Demolition Waste Management And Disposal and indicate:

.1 Descriptions of and anticipated quantities [in percentages] of materials to be salvaged reused, recycled and landfilled.

.2 Schedule of selective demolition.

.3 Number and location of dumpsters.

.4 Anticipated frequency of tippage.

.5 Name and address of haulers, waste facilities waste receiving organizations.

.4 Certificates: submit copies of certified weigh bills receipts from authorized disposal sites and reuse and recycling facilities for material removed from site on weekly basis upon request of Departmental Representative.

.1 Written authorization from Departmental Representative is required to deviate from haulers facilities listed in Waste Reduction Workplan.

1.5 QUALITY ASSURANCE

- .1 Regulatory Requirements: ensure Work is performed in compliance with CEPA, CEAA, TDGA, and applicable Provincial/Territorial regulations.
- .2 Site Meetings.
 - .1 Convene pre-installation meeting one week prior to beginning work of this Section and on-site installations
 - Schedules - Bar Chart to:
 - .1 Verify project requirements.
 - .2 Review installation [and substrate]conditions.
 - .3 Co-ordination with other building subtrades.
 - .4 Review manufacturer's installation instructions and warranty requirements.
 - .3 Hold project meetings every week.
 - .4 Ensure key personnel site supervisor project manager subcontractor representatives attend.
 - .5 Reporting Requirements: WMC to complete.
 - .6 WMC must provide written report on status of waste diversion activity at each meeting.
 - .7 Departmental Representative will provide written notification of change to meeting schedule established upon contract award 24 hours prior to scheduled meeting.
- .3 Health and Safety.
 - .1 Do construction occupational health and safety in accordance with Section 01 35 30 - Health and Safety Requirements.
- .4 Sustainable Requirements.
 - .1 Construction: in accordance with Section 01 47 17 - Sustainable Requirements

1.6 DELIVERY, STORAGE AND HANDLING

- .1 Store and manage hazardous materials in accordance with Section 01 47 17 - Sustainable Requirements: Construction.
- .2 Storage and Protection.
 - .1 Protect existing items designated to remain and items designated for salvage. In event of damage to such items, immediately replace or make repairs to approval of Departmental Representative and at no cost to Departmental Representative.
 - .2 Remove and store materials to be salvaged, in manner to prevent damage.
 - .3 Store and protect in accordance with

requirements for maximum preservation of material.
.4 Handle salvaged materials as new materials.

.3 Waste Management and Disposal.

.1 Separate waste materials for reuse and recycling] in accordance with Section 01 74 21 - Construction/Demolition Waste Management And Disposal.

.2 Divert excess materials from landfill to site approved by Departmental Representative.

.3 Separate for recycling and place in designated containers Steel, Metal waste in accordance with Waste Management Plan.

.4 Place materials defined as hazardous or toxic in designated containers.

.5 Handle and dispose of hazardous materials in accordance with Regional and Municipal, regulations.

.6 Label location of salvaged material's storage areas and provide barriers and security devices.

.7 Ensure emptied containers are sealed and stored safely.

.8 Source separate for recycling materials that cannot be salvaged for reuse including wood, metal, concrete and asphalt, and gypsum.

.9 Remove materials that cannot be salvaged for reuse or recycling and dispose of in accordance with applicable codes at licensed facilities.

1.7 SITE CONDITIONS

.1 Site Environmental Requirements:

.1 Ensure that selective demolition work does not adversely affect adjacent wildlife, or contribute to excess air and noise pollution.

.2 Do not dispose of waste of volatile materials including but not limited to, mineral spirits, oil, petroleum based lubricants, or toxic cleaning solutions into storm or sanitary sewers.

.1 Ensure proper disposal procedures are maintained throughout the project.

.3 Do not pump water containing suspended materials into storm or sanitary sewers or onto adjacent properties.

.4 Control disposal or runoff of water containing suspended materials or other harmful substances in accordance with local authorities as directed by Departmental Representative.

1.8 SCHEDULING

- .1 Meet project time lines without compromising specified minimum rates of material diversion.
 - .1 Notify Departmental Representative in writing when unforeseen delays occur.

PART 2 - PRODUCTS n/a

2.1 SUSTAINABLE REQUIREMENTS

- .1 Materials and resources in accordance with Section 01 47 17 - Sustainable Requirements: Construction.

2.2 EQUIPMENT

- .1 Leave machinery running only while in use, except where extreme temperatures prohibit shutting machinery down.

PART 3 - EXECUTION

3.1 PREPARATION

- .1 Inspect site with Departmental Representative and verify extent and location of items designated for removal, disposal, alternative disposal, recycling, salvage and items to remain.
- .2 Locate and protect utilities. Preserve active utilities traversing site in operating condition.
- .3 Notify and obtain approval of utility companies before starting demolition.
- .4 Disconnect and Cap Designated Mechanical Services.

3.2 REMOVAL OF HAZARDOUS WASTES

- .1 Remove contaminated or dangerous materials defined by authorities having jurisdiction, relating to environmental protection, from site and dispose of in safe manner to minimize danger at site or during disposal.

3.3 REMOVAL OPERATIONS

- .1 Remove items as indicated.
- .2 Do not disturb items designated to remain in place.
- .3 Salvage.
 - .1 Dismantle items containing materials for salvage and stockpile salvaged materials at locations [as indicated].
- .4 Disposal of Material.
 - .1 Dispose of materials not designated for salvage or reuse on site as instructed by Departmental Representative at authorized facilities approved in Waste Reduction Workplan.

3.4 STOCKPILING

- .1 Label stockpiles, indicating material type and quantity.
- .2 Designate appropriate security resources/measures to prevent vandalism, damage and theft.
- .3 Locate stockpiled materials convenient for use in new construction to eliminate double handling wherever possible.
- .4 Stockpile materials designated for alternate disposal in location which facilitates removal from site and examination by potential end markets, and which does not impede disassembly, processing, or hauling procedures.

3.5 REMOVAL FROM SITE

- .1 Remove stockpiled material as directed by Departmental Representative, when it interferes with operations of project.
- .2 Remove stockpiles of like materials by alternate disposal option once collection of materials is complete.
- .3 Transport material designated for alternate disposal

using approved haulers, facilities, receiving organizations listed in Waste Reduction Workplan and in accordance with applicable regulations.

.1 Written authorization from Departmental Representative is required to deviate from haulers, facilities listed in [Waste Reduction Workplan.

.4 Dispose of materials not designated for alternate disposal in accordance with applicable regulations.

.1 Disposal Facilities: approved and listed in Waste Reduction Workplan.

.2 Written authorization from Departmental Representative is required to deviate from disposal facilities listed in Waste Reduction Workplan.

3.6 RESTORATION

.1 Restore areas and existing works outside areas of demolition to conditions that existed prior to beginning of Work match condition of adjacent, undisturbed areas.

3.7 FIELD QUALITY CONTROL

.1 Verification requirements in accordance with Section 01 47 17 - Sustainable Requirements: Contractor's Verification], include:

.1 Materials and resources.

.2 Storage and collection of recyclables.

.3 Construction waste management.

.4 Resource reuse.

.5 Recycled content.

.6 Local/regional materials.

.7 Wood.

.8 Low-emitting materials.

3.8 CLEANING

.1 Remove debris, trim surfaces and leave work site clean, upon completion of Work, refer section 01 74 11 cleaning.

.2 Use cleaning solutions and procedures which are not harmful to health, are not injurious to plants, and do not endanger wildlife, adjacent water courses or ground water.