

Part 1 General

1.1 SECTION INCLUDES

- .1 Barriers.
- .2 Environmental Controls.
- .3 Traffic Controls.
- .4 Fire Routes.

1.2 PROTECTION

- .1 Close off areas of work using barricades, fences and/or caution tape as noted on the drawings. Re-open these areas at the end of the work day and clean up any mortar debris on the ground.
- .2 Existing overhead protections are to remain on site for the duration of the project. Costs related to the overhead protection are to be paid by the Departmental Representative. Contractor to remove any mortar debris on overhead protection at the end of the work day.

1.3 PUBLIC TRAFFIC FLOW

- .1 Provide and maintain competent signal flag operators and barricades as required to perform Work and protect the public.

1.4 FIRE ROUTES

- .1 Maintain access to property including overhead clearances for use by emergency response vehicles.

1.5 PROTECTION FOR OFF-SITE AND PUBLIC PROPERTY

- .1 Protect surrounding private and public property from damage during performance of Work.
- .2 Be responsible for damage incurred.

1.6 PROTECTION OF BUILDING FINISHES

- .1 Provide protection for finished and partially finished building finishes and equipment during performance of Work.
- .2 Provide necessary screens, covers, and hoardings.
- .3 Confirm with Departmental Representative locations and installation schedule 3 days prior to installation.
- .4 Be responsible for damage incurred due to lack of or improper protection.

1.7 WORKZONE LOCATION & IDENTIFICATION

- .1 The contractor shall agree to install proper site separation and identification in order to maintain "Time and Space" at all times throughout the life of the project.

Project No.
R.06814.011

Temporary Barriers and Enclosures

Section 01 56 00

Page 2

Part 2 Products

2.1 NOT USED

.1 Not Used.

Part 3 Execution

3.1 NOT USED

.1 Not Used.

END OF SECTION