

RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:
PWGSC/TPSGC Acquisitions
1045 Main Street
1st Floor, Lobby C
Unit 108
Moncton, NB E1C 1H1
Bid Fax: (506) 851-6759

SOLICITATION AMENDMENT MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
NB / PEI Division - Moncton Acquisitions Office
1045 Main Street
1st Floor, Lobby C
Unit 108
Moncton, NB E1C 1H1

Title - Sujet Floating Docks Kouchibou/Beaubears	
Solicitation No. - N° de l'invitation 5P131-141002/A	Amendment No. - N° modif. 002
Client Reference No. - N° de référence du client 5P131-141002	Date 2015-04-24
GETS Reference No. - N° de référence de SEAG PW-\$MCT-011-4996	
File No. - N° de dossier MCT-4-37148 (011)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2015-05-12	Time Zone Fuseau horaire Atlantic Daylight Saving Time ADT
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Sharpe, Charlene A.	Buyer Id - Id de l'acheteur mct011
Telephone No. - N° de téléphone (506) 851-3467 ()	FAX No. - N° de FAX (506) 851-6759
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction:	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Solicitation Amendment

Title Floating Docks - Kouchibouguac/Beaubears

Solicitation Amendment No. **002**

This solicitation is hereby amended to provide the following questions and answers

Q1. Delivery Date: Since the solicitation closes on May 12, 2015 and that it will take about a week to determine to whom the contract will be awarded, that leaves only about two weeks for delivery at Kouchibouguac Park. Is it possible to add another week or so to the proposed delivery date of June 1st?

A1. Floating docks and all associated materials shall be delivered at Kouchibouguac NP by June 8, 2015. Installation and training of the docks at Kouchibouguac NP and Beaubears Island Shipbuilding NHS shall be scheduled for the week of June 8th and coordinated with the park representative.

Q2. Beaubears Island: What is the minimum length accepted for the T-portion of the Beaubears Island dock?

A2. The minimum lengths and widths for the docks at Beaubears Island are as indicated on the proposed layout for this location.

Q3. Gangway: There is no mention of a transition plate for the gangways. Since the dock could be used by people with disabilities (wheel chair), should a transitional plate be added to the quote?

A3. A transition plate for each gangway is to be added to the quote as being incidental to the gangways.

AND

This solicitation is hereby amended to:

- (1) Reference: Page **12 of 15, Annex A - Statement of Work and Specifications**
DELETE Annex A - Statement of Work and Specifications (revised April 17, 2015) in its entirety; and
INSERT Annex A - Statement of Work and Specifications (**revised April 24, 2015**) attached.

(2) Reference: **Page 7 of 15 - 6.4.1 Delivery Date**

DELETE “All the deliverables must be received on or before June 12, 2015 (please note supply and installation of docks to be received on or before June 1, 2015; installation training to be received on or before June 12, 2015).”

INSERT “All the deliverables must be received on or before June 12, 2015 (please note **floating docks and all associated materials shall be delivered by June 8, 2015; installation and training of the docks shall be scheduled for the week of June 8th).**”

If your bid has already been forwarded and you wish to revise same, this revision should be sent in a sealed envelope and mailed to the above address and reach the undersigned before the appropriate closing date. The solicitation number and the closing date are to be shown on the outside of the sealed envelope or on the facsimile transmission.

All other terms and conditions of the solicitation document remain unchanged.

All enquiries concerning this amendment are to be forwarded to:

Name Charlene Sharpe
Telephone No: (506) 851-3467
Facsimile No: (506) 851-6759

(Derived from - Provenant de: XNB025D, 23/01/2008)

ANNEX A - STATEMENT OF WORK AND SPECIFICATIONS
(Revised April 24, 2015)

SUPPLY AND INSTALLATION OF FLOATING DOCKS IN KOUCHIBOUGUAC NATIONAL PARK OF CANADA AND BEAUBEAR ISLAND SHIPBUILDING NATIONAL HISTORIC SITE OF CANADA

1. Description of work

Supply and installation of floating docks and associated components at Kouchibouguac National Park of Canada and at Beaubears Island Shipbuilding National Historic Site of Canada.

2. Location

2.1 Kouchibouguac National Park:

Docks will be installed at Ryans rental concession: Lat 46.8300 Long -64.9323.

2.2 Beaubears Island Shipbuilding National Historic Site:

Docks will be installed on the island: Lat 46.9778 Long -65.5610.

3. Materials

3.1. Docks

- Minimum lengths and widths to be as per indicated on the attached drawings.
- Maximum length of 3.65 meters (12 feet) for individual dock section.
- Individual dock sections shall consist of decking surface and the float structure, which are to be constructed as a single, integrated component.
- Docks to be constructed of polyethylene.
- Docks must be resistant to ultra-violet exposure.
- Individual dock sections to have a maximum weight of 182 kg (400 lbs).
- Wall thickness of docks to be a minimum of 7.9 mm (5/16 in).
- Floatability for each dock section to be a minimum of 2.87 KN/sq.m. (60 lbs/sq.ft.).
- Freeboard shall be at least 30 cm (12 in) and not more than 38 cm (15 in).
- Docks shall be of a light color and resistant to fading.
- Docks shall have a cold brittleness temperature of no less than -85° Celsius (-121° F)
- Dock sections to be modular.
- Dock sections must have individual floating chambers and must not contain any type of foam.
- The surface of the deck shall be constructed to allow drainage of water.
- The decking surface must be slip resistant.
- The platform must be have the capacity to be installed in multiple arrangements and have the ability to be extended.
- Dock edging shall be provided for the perimeter of the proposed layouts.
- All hardware must be corrosion resistant or non-corroding.
- Connectors holding the dock sections together must be made of a flexible and durable material to minimize risks of damage during extreme conditions.
- Dock platform must have the ability to be assembled and disassembled manually.
- Minimum warranty of 5 years.

3.2 Gangways (with railings)

- Quantity = 2.
- Minimum length of 4.87 meter (16 ft).
- Minimum width of 1.52 meters (5 ft).
- Gangway to be constructed of aluminium.
- Must include shore connector hinges and rollers.
- The surface of the gangway must be slip resistant.

3.3 Anchoring

- Must be seasonal and cause minimal damage to the river bed.
- Must be capable of allowing for a minimum of 2 meters (6.5 ft) variation in water level
- Must utilize a pipe and auger system. Anchor chain brackets (2) will be also be required at Beaubears Island Shipbuilding NHS.
- Pipes must be galvanized dipped with a minimum gauge of schedule 40 with a minimum 6 cm (2 3/8 in) OD.
- Solar lights will be required for all anchoring posts.

3.4 Other

- Corrosion resistant/non-corrosion tie down cleats (60).
- Dock bumpers (4).
- Dock wheels (for moving docks on dry land)
- All specialty tools required to assemble and disassemble the components shall be included.
- All accessories and/or components (corner gussets, etc.) recommended by the supplier to ensure the structural stability of the platform shall be included.

4. Installation

4.1 Initial installation

- Supplier will provide a minimum of one person to instruct and assist park employees in the initial installation of the dock platform in Kouchibouguac NP and Beaubears Island Shipbuilding NHS. The installation at Kouchibouguac NP and Beaubears Island Shipbuilding will be scheduled during the week of June 8, 2015, during regular working hours. Scheduling will be dependent on the weather and/or tides and coordinated with the park representative.