

OFFICER'S DECK


NAVIGATING BRIDGE DECK

WHEELHOUSE TOP

ITEM NO.	SYMBOL	DESCRIPTION	QTY.	SUPPLIER	MANUFACTURER TYPE NO.	REQ. NO.	REMARKS
1	[Symbol]	VENTILATION REHEAT DISTRIBUTION PANEL	10	NORRIS WARMING		221-900-8	
2	[Symbol]	SAFETY CONTROL PANEL	4	"		"	
3	[Symbol]	ATTENUATOR BOX WITH ELEC. REHEATER, WARD SWITCH, TRANSFORMER & MANUAL Q/T TRIP, 440V, CULHEAD MTD.	92	"		"	
4	[Symbol]	CABIN THERMOSTAT (FLUSH MOUNTED)	51	"		"	
5	[Symbol]	CABIN THERMOSTAT (SURFACE MOUNTED)	30	"		"	
6	[Symbol]	ACCOMMODATION HEATING PANEL	1	"		"	ACQUISITIONED BY AIR SYST.
7	[Symbol]	AIR CONDITIONING PLANT	5	"		"	
8	[Symbol]	AEROTHERME AVEC THERMOSTAT INTEGRE					
9	[Symbol]	AEROCONVECTEUR AVEC THERMOSTAT INTEGRE					
10	[Symbol]	PLINthe ELECTRIQUE					
11	[Symbol]	PLINthe ELECTRIQUE AVEC THERMOSTAT INTEGRE					
12	[Symbol]	CONVECTEUR SANS THERMOSTAT					

NOTES:

- CABLES TO THERMOSTATS TO BE 30 #14. ALL OTHER CABLES ARE 30 #14 A.W.G. CROSS-LINKED POLYETHYLENE P.V.C. BROWN BRAID ARMOUR, UNLESS OTHERWISE INDICATED.
- FOR A/C VENTILATION & HEATING SYSTEM ELEMENTARY WIRING DIAGRAM, SEE REF. NO. 1.
- MAIN WIREWAYS TO BE UTILIZED WHERE POSSIBLE.
- EQUIPMENT LOCATIONS SHOWN ON THIS DRAWING ARE APPROXIMATE ONLY. EXACT LOCATIONS TO BE DETERMINED ON BOARD.
- ALL METALLIC ENCLOSURES OF ELECTRICAL EQUIPMENT TO BE GROUNDED.
- ALL THERMOSTATS TO BE INSTALLED AT A MINIMUM OF 8 FEET FROM REHEATER BOX IN COMPARTMENTS.



FLIGHT & BOAT DECK

REF. NO.	TITLE	DWG. NO.
1	A/C VENTILATION & HEATING SYSTEM, E.W.D.	221-900-8 SHT 23-32
2	ACCOMMODATION VENTILATION M.C.C. # 11	221-900-8 SHT 15
3	WIREWAY ARRANGEMENT & DETAILS	221-930-1 SHT.
4	ACCOMMODATION HEATING DISTRIBUTION PANEL	221-900-8 SHT 21

REVISION	BY	DATE
1. RHA-6, 7 ET RHF-3, 4 POUTHE 400 VAC INSTALLEE	S.C.L.	18/10/78
2. GENERAL REVISION	J.D.V.	04/2081
3. UNIT REMOVED WIRE IN TOP	J.D.V.	FEB 99
4. DRAWING MADE AS FITTED HULL 221	J.D.V.	17 JAN 93
5. ITEM 5 CHANGED	J.D.V.	17 JAN 93
6. CABLES FROM DISTRIBUTION PANEL TO REHEAT PANELS CHANGED TO 30 #14	J.D.V.	17 JAN 93
7. CABLE LEADS CHANGED. LOCATIONS OF THERMOSTATS CHANGED TO SUIT ARRANGEMENT OF COMPARTMENTS. ELECTRIC REHEATERS DELETED FROM WASHROOMS AND WHEELHOUSE	J.D.V.	17 JAN 93

DEPARTMENT	QTY.	DEPARTMENT	QTY.	DEPARTMENT	QTY.
General	5	Yard Manager	1	Shipwright	1
Classification	1	New Const. Sect.	1	Trainer	1
Structural Inspection	3	Naval Sup.	1	Paint Shop	1
		Steel Shop	1	Machine Shop	1
				Plumbers	1
				Electric Shop	1
				Welding Shop	1




BURRARD DRY DOCK CO. LTD.
SHIPBUILDERS • SHIP REPAIRERS • GENERAL ENGINEERS
NORTH VANCOUVER, B.C. CANADA

DIVISION: ELECTRICAL
HULL NO. 221
JOB NO. 900
OWNERS: MINISTRY OF TRANSPORT

TITLE: A/C VENTILATION AND HEATING SYSTEM- DECK PLAN

REPRESENTATIVE	DATE	DESIGN	APP.
M.D.T. L. LAMONT	11/04/78	CHECKED	C.E.N.
C.S.L. M. DUBREUIL	11/04/78	APPROVED	C.E.N.
		SCALE: N.T.S.	DATE: 11/04/78

DWG No 221-900-7 SHT. 1



8	CIRCUITS RHE-7 ET RHE-14 REMIS EN FONCTION	G.D.	12-2009
9	CIRCUIT RHO-2 3 & 4 REPLACE UNIT DE CHAUFFAGE DU SALON DE TELEVISION ET LES DEUX DU SALON D'ÉQUIPAGE PAR UNITES AEC THERMOSTAT INTEGRE. LES THERMOSTATS D'ORIGINE ONT ÉTÉ RETIRÉS. LE CÂBLAGE EST TOUJOURS EN PLACE.	JDV	12/2003
10	AS FITTED	JDV	04/2001
11	DRAWING MADE AS FITTED - HULL 221	H.M.	MAY 3 78
12	CIRCUITS RHJ-3 & RHJ-13 INTERCHANGED	H.M.	MAY 3 78
13	COMPARTMENT NAME CHANGED.	JRP	29/06/78
14	CABLES FROM DISTRIBUTION PANELS TO REHEAT PANELS CHANGED TO 36#14.	JRP	17/04/77
15	CABLE LEADS CHANGED. LOCATIONS OF THERMOSTATS CHANGED TO SUIT ARRANGEMENT OF COMPARTMENTS. ELECTRIC HEATERS DELETED FROM WASHROOMS AND GALLEY. REHEATERS ADDED TO SUIT NEW ACCOMMODATION ARRANGEMENT ON UPPER DECK FR. TO E.	JRP	1 SEP 76
REVISION			
No.	REVISION	BY	DATE
DISTRIBUTION			
DEPARTMENT	QTY.	DEPARTMENT	QTY.
Owners	5	Yard Manager	Shipwright
Crew/Engineer	1	Yard Chief Sup.	Rigger
Electrical Inspection	3	Quilt Sup.	Joiner
		Repair Sup.	Pipe Fitter
		Steel Sup.	Machine Shop
		Painting	Blacksmith
Hull D.O.	1		Sheet Metal
Machinery D.O.	1	Left	Electric Shop
Electrical D.O.	1	Plater	2
Welding Engineer		Welder	
BURRARD DRY DOCK CO. LTD.			
SHIPBUILDERS • SHIP REPAIRERS • GENERAL ENGINEERS			
NORTH VANCOUVER, B.C. CANADA			
DIVISION	HULL 221	JOB No.	900
ELECTRICAL	OWNERS	MINISTRY OF TRANSPORT	
TITLE			
A/C VENTILATION AND HEATING SYSTEM - DECK PLAN			
APPROVALS	REPRESENTATIVE	DATE	DRAWN
M.O.T.	L. LENOX	21 APR 76	CHECKED
C.S.I.	N. SODGORTH	5 MAY 76	APPROVED
		SCALE	N.T.S.
		DATE	21/4/76
		DRG No.	221-900-7
		SHT.	2/2