

PART 1 - GENERAL

- 1.1 SECTION INCLUDES
- .1 Barriers.
 - .2 Environmental Controls.
 - .3 Traffic Controls.
 - .4 Fire Routes.
- 1.2 RELATED SECTIONS
- .1 Section 01 50 00 - Temporary Facilities and Controls.
- 1.3 REFERENCES
- .1 Canadian General Standards Board (CGSB):
 - .1 CAN/CGSB-1.189-2000, Exterior Alkyd Primer for Wood.
 - .2 CAN/CGSB-1.59-97, Alkyd Exterior Gloss Enamel.
 - .2 Canadian Standards Association (CSA):
 - .1 CSA-O121-08, Douglas Fir Plywood.
- 1.4 INSTALLATION AND REMOVAL
- .1 Provide temporary controls in order to execute Work expeditiously.
 - .2 Remove from site all such work after use.
- 1.5 HOARDING
- .1 Erect temporary site enclosure using new 1.2 m high snow fence wired to rolled steel "T" bar fence posts spaced at 2.4 m o.c. Provide one lockable truck gate. Maintain fence in good repair.
 - .2 Provide barriers around trees and plants designated to remain. Protect from damage by equipment and construction procedures.
-

- 1.6 GUARD RAILS AND BARRICADES .1 Provide secure, rigid guard rails and barricades around open excavations.
- .2 Provide barricades along wharf structure when wheelguard is removed.
- .3 Provide as required by governing authorities as indicated.

- 1.7 ACCESS TO SITE .1 Provide and maintain access roads, sidewalk crossings, ramps and construction runways as may be required for access to Work.

- 1.8 PUBLIC TRAFFIC FLOW .1 Provide and maintain competent signal flag operators, traffic signals, barricades and flares, lights, or lanterns as required to perform Work and protect the public.

- 1.9 FIRE ROUTES .1 Maintain access to property including overhead clearances for use by emergency response vehicles.

- 1.10 PROTECTION FOR OFF-SITE AND PUBLIC PROPERTY .1 Protect surrounding private and public property from damage during performance of Work.
- .2 Be responsible for damage incurred.

PART 2 - PRODUCTS

- 2.1 NOT USED .1 Not Used.

PART 3 - EXECUTION

3.1 NOT USED .1 Not Used.