



RETURN BIDS TO:

RETOURNER LES SOUMISSIONS Á:

Parks Canada Agency
P.O. Box 220
McKay Compound, Stores Building
6300 Highway 93S
Radium, BC V0A 1M0

SOLICITATION AMENDMENT
 MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same

Ce document est par la présente revise; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaries

Vendor/Firm Name and Address
 Raison sociale et adresse du fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution

Parks Canada Agency
 Lake Louise, Yoho, Kootenay Field Unit
 P.O. Box 220
 Radium, BC V0A 1M0

Title-Sujet Lake Louise Campground Flood Control		Date May 15, 2015
Solicitation No. - No. de l'invitation 5P424-15-0202/A	Amendment No. - No modif. 003	
GETS Reference No. - No de reference de SEAG N/A		
Solicitation Closes L'invitation prend fin - at - á 02:00 PM on - le May 21, 2015	Time Zone Fuseau horaire - Mountain Daylight Saving Time (HAR)	
F.O.B. - F.A.B.		
Address Inquiries to: - Adresser toute demande de renseignements à : Eloise Meredith eloise.meredith@pc.gc.ca		
Telephone No. - No de téléphone (250) 347-6622	Fax No. - No de FAX: (250) 347-6621	
Destination of Goods, Services, and Construction: Destinations des biens, services et construction: Lake Louise, Yoho, Kootenay Field Unit		
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur		
Name and title of person authorized to sign on behalf of the Vendor/Firm Nom et titre de la personne autorisée a signer au nom du fournisseur/ de l'entrepreneur		
Signature		Date

This amendment is raised to answer questions

Q1 Do you have some additional information on how you want this Erosion Control Plane to be done?

A1 The type and manner of erosion sediment control is to be proposed by the Contractor. The Contractor will prepare a short Environmental Protection Plan (EEP) for approval by Parks Canada which outlines how the Contractor intends to control sedimentation during the project. The main intent of erosion sediment control on this project is to eliminate sediment getting into the Bow River.

Q2 Do you require the trees which need to be removed to be replaced with new ones?

A2 Trees identified for removal on the drawings do not need to be replaced. Tree that are removed over and above those identified on the drawings, or trees damaged by the Contractor will be required to be replaced.

Q3 Seed mixture you require does it need to be exact? Can any substitutions to specified seed mixture be made?

A3 Substitute seed mixtures can be accepted so long as there is no non-native seeds in the mixture. Substitute seed mixtures should be submitted by the Contractor for approval by Parks Canada.

Q4 Are there penalties for delays beyond the June 26, 2015 completion date if, due to some extreme circumstances, the project needs to extend?

A4 There are no penalties or bonuses specified for this project. There are General Conditions and clauses related to GC6 Delays and Changes in the Work and GC7 Default, Suspension or Termination of Contract.

Q5 Any trees that need to be cleared, do the stumps/brush get hauled locally or outside of the Parks and the rest get cut into 2' sections for local fire pits?

A5 The trees, stumps, brush can be cut and left within the floor of the local woods as directed by Parks Canada. In the case where there is any hauling of wood, stumps, or brush it will be to Pit 69.

Q6 The 900 willow stakes, where would we be harvesting these from?

A6 The Willow stakes typically should be got from a local nursery. Parks Canada have previously used Bow Point Nursery in Calgary. It seems the most likely scenario that the willow staking will need to be done in the spring/summer of 2016.

All other terms and conditions remain the same.