

Questions:

- 1) is the pole with mounting plate already on the vessel?
- 2) what speed will the vessel work at to do the surveying?

Answer:

Information already in the leasing specification.

1. The mounting arrangement on the NRCan pole is already established. The bidders are required to furnish a compatible mount which will bolt on to the existing mount at the end of our pole.
2. The bolting flange which we require the bidder to supply (on their mount) is attached in the bidding documentation, as Annex E
3. Typical survey speed of the vessel is 5 knots. However, the bidders supplied mount should be designed to meet the specifications put forward in the bidding documentation which states that the mount must be capable of 10 knots.