

MATCH LINE "G"

NOTES

SURVEY PARTY CHIEF: SURVEY PARTY CHIEF
SURVEY DATE(S) SEPTEMBER 23-25, 2014
LAND SURVEY POSITION BY
DATA TAPE/DISC(S) USED
CAD DRAWING FILE(S): 2 GULL ROCKS.DWG

TIDAL REDUCTION SCHEME TIDAL REDUCTION SCHEME

OFFICE PROCESSOR

DATE OF PROCESSING

CONTROL POINTS		EASTING		NORTHING		CD, ELEV		DESCRIPTION
PT.	NAME							
PWC	1-2014	440296.94	51	5486509.713	51	5.061	m	NAIL IN PAVEMENT
PWC	2-2012	440296.940	51	5486509.713	51	4.980	m	NAIL IN WOODEN FENCE
PWC	2-12	442908.250	51	5483372.924	51	3.794	m	NAIL INTO CORNER OF WALL
BM	89F192	441718.571	51	5484548.651	51	9.775	m	GEODETIC BRASS
BM	89F193	440472.080	51	5486097.338	51	6.332	m	GEODETIC BRASS

ALL ELEVATIONS REFERRED TO ANY OF THE CONTROL POINTS LISTED ABOVE IN THE CONTROL POINTS TABLE AND ARE REFERRED TO CHART DATUM.

COORDINATES FOR HORIZONTAL CONTROL ARE GIVEN ON THE U.T.M. MAPPING PLANE, ZONE 21, USING THE NORTH AMERICAN DATUM OF 1983(NAD83).

LEGEND

SYMBOLS

	ACRES		MANHOLE
	BOREHOLE		MARSH
	BOUNDARY MARKER		MAST/TOWER
	CATCH BASIN		NAVIGATION LIGHT
	CLEAR		SAFETY POST
	CULVERT		SIGN
	DISPOSAL		SEWER OUTFLOW PIPE
	DREDGE CONTROL		TELEPHONE POLE
	ELECTRICAL OUTLET		RANGE LIGHT
	FIRE HYDRANT		TREE
	FIRST AID		UTILITY POLE
	FUEL PUMP		VERTICAL CONTROL
	HORIZONTAL CONTROL		WATER TAP/OUTLET
	INVERT PIPE		WATER VALVE
	FLAG POLE		WATER WELL
	LADDER		WOOD PILE
	LADDER STANDARD		

LINE TYPE

	ARMOUR STONE		MARSH OUTLINE
	CL RAILROAD	PROPERTY BOUNDARY
	DRAIN PIPE	---	RANGE LIGHT EXTENSION
	EDGE ROAD / SHOULDER	W	RETAINING WALL
	FENCE LINE	RIPRAP	RIPRAP
	FLOATING WANKBREAK	---	TOE OF BANK
	GUARD RAIL		TREE LINE
	HIGH WATER MARK	---	UNDERGROUND CABLE
	LOW WATER MARK		

HORIZONTAL CONTROL POINTS FOR AREA "B"

CONT'L POINT	EASTING	NORTHING
W1	440488.21	5485718.26

SITE PLAN
SCALE: 1/250

SCALE: 1:250

0m 5m 10m 15m 20m 25m

NOTES:

1. THERE ARE VARIOUS LOCATIONS ALONG THE PROJECT SITE, BETWEEN THE PAVED ROAD SURFACE AND THE PROPOSED ARMOUR STONE LOCATION, THAT MAY BE SUITABLE FOR TEMPORARY STORAGE OF MATERIALS. THIS WILL BE CO-ORDINATED BY THE CONTRACTOR, IF REQUIRED, WITH THE PROJECT MANAGER AND THE DEPARTMENTAL REPRESENTATIVE.
2. ENSURE NO TREES ARE CUT OR DAMAGED AS THE RESULT OF ANY WORK.
3. REINSTATE ALL AREAS DISTURBED DURING CONSTRUCTION OPERATIONS AND MATERIAL STORAGE TO CONDITIONS SIMILAR TO PRE-CONSTRUCTION AND TO APPROVAL OF PARKS CANADA.