

NOTES:

- THERE ARE VARIOUS LOCATIONS ALONG THE PROJECT SITE BETWEEN THE PAVED ROAD SURFACE AND THE PROPOSED ARMOUR STONE LOCATION, THAT MAY BE SUITABLE FOR STORAGE OF MATERIALS. THIS WILL BE DETERMINED BY THE CONTRACTOR IN CONSULTATION WITH THE DEPARTMENTAL REPRESENTATIVE OF PARKS CANADA AND THE DEPARTMENTAL REPRESENTATIVE OF ANY WORK.
- ENSURE NO TREES ARE CUT OR DAMAGED AS THE RESULT OF ANY WORK.
- REINSTATE ALL AREAS DISTURBED DURING CONSTRUCTION OPERATIONS AND MATERIAL STORAGE TO CONDITIONS SIMILAR TO PRE-CONSTRUCTION AND TO APPROVAL OF PARKS CANADA.

NOTES:



SURVEY PARTY CHIEF: RICHARD HEALEY
 SURVEY DATE(S): SEPTEMBER 23-25, 2014
 LAND SURVEY POSITION BY: DFGS
 DATA TAPE/DISC(S) USED: 2 GULL ROCKS.DWG
 CAD DRAWING FILE(S): TIDAL REDUCTION SCHEME

OFFICE PROCESSOR: EDDIE BEARNS
 DATE OF PROCESSING: DECEMBER 2014

CONTROL POINTS:

PL. NAME	EASTING	NORTHING	CD. ELEV	DESCRIPTION
PWC 1-2014	440296.051	5486509.713	5.061 m	NAIL IN PAVEMENT
PWC 2-2014	440296.840	5486538.250	4.980 m	NAIL IN WOODEN PEG
PWC 2-12	442908.458	548322.944	3.704 m	NAIL IN GOVT WHARF
BM 89F192	441718.571	5484548.651	8.375 m	GEODETIC BRASS PLAQUE SET IN BEDROCK
BM 89F193	440472.080	5486097.938	6.332 m	GEODETIC BRASS PLAQUE SET IN BEDROCK

ALL ELEVATIONS REFERRED TO ANY OF THE CONTROL POINTS LISTED ABOVE IN THE CONTROL POINTS TABLE AND ARE REFERRED TO CHART DATUM.
 COORDINATES FOR HORIZONTAL CONTROL ARE GIVEN ON THE U.T.M. MAPPING PLANE, ZONE 21, USING THE NORTH AMERICAN DATUM OF 1983 (NAD83).



HORIZONTAL CONTROL POINTS FOR AREA "A"

CONTROL POINT	EASTING	NORTHING
A	440186.10	5486888.05
B	440195.30	5486850.64
C	440200.92	5486828.51
D	440211.15	5486808.05
E	440224.67	5486766.35
F	440232.88	5486745.18
G	440239.38	5486723.47

