

PART 1 - GENERAL

- 1.1 DESCRIPTION
- .1 This section specifies requirements for demolishing and removing wholly or in part various items designated to be removed or partially removed.
 - .2 Demolition and removal will consist of, but not necessarily be limited to, the following:
 - .1 Demolition, removal and disposal of the existing steel cable and post guide rail system as noted on the drawings.
 - .2 Demolition, removal and disposal of a corroded 4.0 metre section of 1200mm diameter corrugated steel pipe. Also include any culvert ends removed to ensure suitable ends for addition of culvert extensions.
- 1.2 PROTECTION
- .1 Protect existing objects designated to remain. In event of damage, immediately replace or make repairs to approval of and at no additional cost to Canada.

PART 2 - PRODUCTS

NOT APPLICABLE

PART 3 - EXECUTION

- 3.1 EXECUTION
- .1 Inspect site and verify with Departmental Representative objects designated for removal.
- 3.2 REMOVAL
- .1 Remove in their entirety all materials and objects specified for removal.
 - .2 Do not disturb adjacent work designated to remain in place.
- 3.3 DISPOSAL OF MATERIAL
- .1 All demolished materials or salvaged materials will become property of contractor and will be removed from site and disposed or salvaged of to satisfaction of Departmental Representative and in accordance with environmental guidelines.
 - .2 It is the sole responsibility of the contractor to dispose of all demolished materials at an

approved disposal site.

- .3 Ensure that disposal site is approved and willing to accommodate any materials disposed of from work site.
- .4 Contractor shall obtain and pay for all necessary permits and disposal fees for use of an approved waste disposal site.