

RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:
Bid Receiving - PWGSC / Réception des soumissions
- TPSGC
11 Laurier St. / 11, rue Laurier
Place du Portage, Phase III
Core 0B2 / Noyau 0B2
Gatineau, Québec K1A 0S5
Bid Fax: (819) 997-9776

SOLICITATION AMENDMENT MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Electrical & Electronics Products Division
11 Laurier St./11, rue Laurier
7B3, Place du Portage, Phase III
Gatineau, Québec K1A 0S5

Title - Sujet UPGRADE & RECONFIG MCCP COLLINS BAY	
Solicitation No. - N° de l'invitation 21120-157663/A	Amendment No. - N° modif. 003
Client Reference No. - N° de référence du client 2057663	Date 2015-06-03
GETS Reference No. - N° de référence de SEAG PW-\$\$HN-461-67070	
File No. - N° de dossier hn461.21120-157663	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2015-06-30	Time Zone Fuseau horaire Eastern Daylight Saving Time EDT
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Hallman, Patti	Buyer Id - Id de l'acheteur hn461
Telephone No. - N° de téléphone (819) 956-7390 ()	FAX No. - N° de FAX () -
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction:	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Amendment 003 is being issued to provide responses to the questions received, to update the STR with additional information and to amend the Financial Bid Presentation and to update the solicitation close date.

1) At Table of Contents

Insert:

Attachments

Attachment 001 Questions and Answers

Attachment 001 Questions and Answers

Q1 During the Site visit there was some concern raised that touch screen manufacturers no longer support the required protocols in order to mitigate supplying the wrong part could the crown please inquire with the PIDS and FAAS vendor the recommended 22 inch touch screen model # required to operate the PIDS and FAAS controllers?

A1 The existing PIDS and FAAS touch screens are manufactured by Elographics. Elographics confirmed that there are several models available that support the required serial protocol

Q2 During the site visit a Cash allowance was discussed for the fire alarm system. Will the cash allowance provide for all requirements listed in 3.16 of the STR?

A2 The requirement to include this in the Proposal will be removed. CSC will obtain a quote for the repackaging of the fire alarm system primary and secondary alarm panels and pc equipment and PWGSC will include this cost into contract for the winning bidder.

Q3 During the site visit it was agreed that a cash allowance would be provided for reinstalling moving the fire system could the Crown also include reinstalling the smoke detector(s) on the ceiling tiles as it is included as part of the fire system?

A3 CSC will ensure the reinstallation of any ceiling mounted fire alarm sensors is included in the quote for repackaging of the fire alarms system as detailed in Question #2

Q4 Are ceiling tiles to be replaced ?

A4 All ceiling tiles in the MCCP must be replaced

Q5 The STR section 3.3 (e) states "Supply and install new computer flooring (similar to existing) as required." The supporting documents received during the site visit requests "all new tiles" could the Crown confirm?

A5 All floor tiles in the MCCP must be replaced including the tiles at or under the under the MCCP entry or exit doors.

The floor tiles must meet or exceed industry standards for control room environments (e.g. rated at 1000 lbs, high pressure laminate surface) They must match the existing tile size requirements and be installed on the existing under structure system.

All cable entry holes through the floor tiles must be equipped with a suitable grommet to prevent cable chafing.

Q6 If a new computer floor is required can the access floor match existing?

A6 The new floor tiles must meet or exceed industry standards for control room environments (e.g. rated at 1000 lbs with high pressure laminate surface) and match the existing tile size and be installed on the existing under structure system. CSC will provide the bidders with details of the tiles required.

Q7 What is the height of the existing raised floor?

A7 10"

Q8 Will the floor need to be bonded?

A8 The new floor tiles must be installed in accordance with manufacturers specifications.

Q9 Can the crown take a closer picture of the floor as well as the support underneath?

A9 Photos provided.

Q10 Can the Crown provide a spare, fully equipped S100 as a back up for cut over?

A10 No. A spare S100 computer is not required. The Bidder should make use of the existing dual redundant PIDS/FAAS architecture to cut the system over.

Q11 Should a second Operator Chair be included in the spares list?

A11 Yes

Q12 Can the Crown provide additional information concerning the Sally Port Gate Controller, especially Supervision?

A12 South/West Sally Port Gate Control.

Maker: Dupline

Components: - Channel Generator

- 8 Channel Generator

- Fibre Optic Repeater

Installer: Delco Automation

Supervision: Supervision of gate position is done via the FDS only

Interface: Fibre optics, not sure of protocol, 600 volt system.

Link to manufacturer: <http://www.dupline.com/scheletro.asp?Language=UK&page=1>

North/East Sally Port Gate Control.

Maker: Unknown

Components: Push button control in the MCCP and N/E Tower

Installer: Unknown

Supervision: FDS System

Interface: Hardwire control, 120 volt

Q13 Can the Crown provide details of which items of obsolete equipment must be removed from the walls?

A13 The Contractor must remove any and all abandoned security and/or fire alarm equipment/panels located on the walls of the MCCP and turn them over to CSC for disposal or reallocation.

Q14 Will CSC will provide a space assessment of the space available in the existing CER racks?

A14 CSC will complete a space assessment of the existing CER rack units and will identify to the Bidders the space available for the relocation of the equipment from the MCCP. This will also identify opportunities to mount existing wall mount style equipment that is improperly rack mounted in the CER more effectively.

Q15 Has CSC considered whether the existing NVUSs at site will support the proposed video monitor configurations?

A15 In accordance with the CSC's standard, a maximum of two (2) monitors, each displaying four (4) camera views should be associated with any one NVUS. The provided as-builts identify the number of NVUS currently integrated into the MCCP. Two (2) NVUS will be required to support the four (4) PIDS CCTV monitors, a third NVUS will be required for the two (2) large non-PIDS monitors, and a fourth will be required to act as the VMS desktop monitor.

Q16 Will the contractor be required to remove non-security related storage furniture or cabinets from the MCCP?

A16 CSC will make arrangements for these items to be removed.

Q17 Will the bidder be required to remove all unused cables under the floor in the MCCP, especially cables between the MCCP and CER?

A17 Following contract award, Contractor to identify cabling not being replaced. ADGA to inspect the cabling not being replaced by the Contractor and provide feedback to the Design Authority and the Contractor during the project. Contractor to remove all unused cabling identified by ADGA and the Design Authority.

Q18 Will the bidder be required to label all User Interfaces, Monitors and CCTV Monitors in the MCCP?

A18 Bidder will be required to label all User Interfaces, Monitors and CCTV Monitors and equipment in MCCP. The labels must be mechanically generated using clear, non-handwritten type and approved by the Design Authority.

Q19 Will the bidder be required to replace all non-rack mounted servers?

A19 No

Q20 Will CSC clarify the status of the C25 construction cameras at CBI?

A20 CSC will replace the first sentence of section 1.1.5 with "Two (2) 27" video monitors were previously installed on top of console bays 1 and 2 to provide views of C25 cameras associated with a new construction areas. " Replace the first two sentences of section 3.9 with " the temporary construction CCTV system has now been decommissioned The contractor must ensure that all S100 programming and cabling associated with this system is removed. "

Q21 Will CSC require Grounding Straps on the new Console?

A21 Yes

Q22 Will CSC require that the PIDS PA activation functionality be modified to allow an operator to use the PA on a per sector basis when there is no PIDS alarm present on that sector?

A22 The Bidder must relocate the PIDS PA and integrate it to meet the current activation functionality at the site.

Q23 Will CSC provide additional details concerning the features and specifications of the proposed MCCP Console?

A23 Yes. See MCCP Design Requirements

2) At Supplied under separate cover (Attachment 1)

Insert: PDF document titled "Additional Design Requirements - dated May 15, 2015"

Insert: Photos requested at Mandatory Site Visit, provided via email to Bidders who attended

Insert: Three additional MCCP photos provided via email to Bidders on May 28, 2015.

Insert: Soft copy of PPT presentation and As Builts provided via email to Bidders on May 28, 2015.

3) At Annex "A" Pricing Sheet

Insert: 7. Fire Alarm Monitoring

Firm lot price for the integration of the fire alarm system controls will be reimbursed at cost and is not part of Bid Price Calculation.

4) At page 1 of the Solicitation:

Delete: L'invitation prend fin à 2015-06-16

Insérer: L'invitation prend fin à 2015-06-30

ALL OTHER TERMS AND CONDITIONS REMAIN UNCHANGED