


- NOTES
- ① EXISTING BULKHEAD TO REMAIN (2590 +/- ABOVE FINISHED FLOOR (A.F.F.)).
 - ② NEW 508x1524 CEILING GRID AND TILE @ 2750 A.F.F..
-SEE SPECIFICATIONS FOR TYPE.
 - ③ NEW PAINTED GYPSUM BOARD CEILING @2590 A.F.F..

DESIGN STUDIO
COMMERCIAL INTERIOR DESIGN
PROJECT MANAGEMENT

BEVERLY BARRETT
REGISTERED INTERIOR DESIGNER
ARIDNB, IDC
P.O.Box 1803 MONCTON NEW BRUNSWICK E1C 9X6
PH 857-9003 design@beverlybarrett.ca
www.beverlybarrett.ca



REFLECTED CEILING PLAN



INTERIOR FINISH SCHEDULE

REV.	No.	ROOM NAME	FLOOR		WALLS								CEILINGS		REMARKS	
					BASE		NORTH		SOUTH		EAST		WEST			
			MAT.	FIN.	MAT.	FIN.	MAT.	FIN.	MAT.	FIN.	MAT.	FIN.	MAT.	FIN.		
	101	LOBBY	LVP	NOTE 1	RB	GB	P	GB	P	GB	P P4	GB	P	GB	P P6	
	102	EDITING ROOM	LVP		RB	GB	P P5	GB	P P5	GB	P P5	GB	P P5	SG/AT		
	103	SPS VIEWING ROOM	LVT		RB	GB	P	GB	P	GB	P P4	GB	P	SG/AT	EB	P P6
	104	STORAGE	LVP		RB	GB	P	GB	P	GB	P	GB	P	SG/AT	EB	P P6
	105	KITCHENETTE	LVT		RB	GB	P	GB	P	GB	P P3	GB	P	SG/AT	EB	P P6
	106	ENCLOSED OFFICE	LVP		RB	GB	P	GB	P	GB	P P2	GB	P	SG/AT	EB	P P6
	107	ENCLOSED OFFICE	LVP		RB	GB	P	GB	P	GB	P	GB	P P2	SG/AT	EB	P P6
	108	OPEN WORK AREA	LVP		RB	GB	P	GB	P P2	GB	P P2	GB	P	SG/AT	EB	P P6
	109	SHARED EQUIPMENT AREA	LVP		RB	GB	P	GB	P	GB	P	GB	P	SG/AT		
	110	LAN ROOM	LVP		RB	GB	P	GB	P	GB	P	GB	P	SG/AT		
	111	SEATING AREA	LVP		RB	GB	P	GB	P P2	GB	P	GB	P	SG/AT	EB	P P6
	112															

FLOOR

LVP - LUXURY VINYL PLANK
LVT - LUXURY VINYL TILE
NOTE 1 - PROVIDE ALUMINUM
TRANSITION THRESHOLD
BETWEEN PUBLIC CORRIDOR
100 AND LOBBY 101

BASE

RB - RUBBER

WALLS

GB - GYPSUM BOARD

CEILING

GB - GYPSUM BOARD
AT - ACOUSTIC TILE
SG - SUSPENDED GRID
EB - EXISTING BULKHEAD

MISCELLANEOUS

E - EXISTING
P - PAINTED
P1 = BENJAMIN MOORE (BeMo) OC-14 NATURAL CREAM
OVERALL COLOUR - TYPICAL U.N.O.
P2 = BeMo AF-500 BLUE ECHO
P3 = BeMo AAF-415 GRASSHOPPER
P4 = BeMo AF-100 PASHIMA
P5 = SICO 4203-31 WARM GREY
P6 = BULKHEAD - UNDERSIDE PAINTED CEILING WHITE
WITH VERTICAL FACE TO MATCH WALL COLOUR

GENERAL NOTES :

- CONTRACTOR TO CHECK AND VERIFY ALL DIMENSIONS IN THE FIELD AND REPORT ANY DISCREPANCIES OR OMISSIONS TO THE DESIGNER BEFORE COMMENCING WITH THE WORK.
- DIMENSIONS TO TAKE PRECEDENCE OVER SCALE.
- ALL WORK TO BE DONE IN COMPLIANCE WITH THE LATEST NATIONAL, LOCAL AND FIRE PROTECTION SERVICES CODES.
- CONTRACTOR TO MAKE GOOD ALL SURFACES TO RECEIVE NEW MATERIALS.
- DO NOT PROCEED WITH ANY MODIFICATIONS TO THESE DRAWINGS WITHOUT APPROVAL OF THE DESIGNER.
- CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL PERMITS NECESSARY TO COMPLETE PROJECT.
- PROVIDE BLOCKING AT WALLS TO SUPPORT MILLWORK.
- CONTRACTOR RESPONSIBLE FOR ANY DAMAGE TO HIS WORK DUE TO THE LACK OF REASONABLE PROTECTIVE PRECAUTIONS.
- CONTRACTOR TO SUBMIT FINAL SAMPLES OF MATERIALS FOR APPROVAL BY DESIGNER BEFORE INSTALLATION.
- ALL MATERIALS AND FINISHES SPECIFIED ARE TO BE INSTALLED IN ACCORDANCE WITH MANUFACTURE'S SPECIFICATIONS.
- BARRIER-FREE STANDARDS ARE TO BE FOLLOWED AS PER CAN/CSA-B651-12 ACCESSIBLE DESIGN FOR THE BUILT ENVIRONMENT.

	ISSUED FOR TENDER	06/11/15
	ISSUED FOR 100%	03/03/15
revisions		date

NATIONAL FILM BOARD
FIT-UP
GOCB MONCTON
1081 MAIN STREET
MONCTON, NB

REFLECTED CEILING PLAN
FINISH SCHEDULE
GENERAL NOTES

designed	BB	conçu
date		
drawn	FK	dessiné
date	March 03, 2015	
approved		approuvé
date		
Tender		Soumission
PWGSC Project Manager	2015/05/19	Administrateur de projets TPSCGC
project number		no. du projet
	R.064333.001	
drawing no.		no. du dessin
	A-3	

FINISH SCHEDULE

GENERAL NOTES

